SITE IMPROVEMENT PLANS

A TRACT OF LAND BEING PART OF THE SE 1/4 OF SECTION 20,
TOWNSHIP 1 SOUTH, RANGE 14 WEST
CITY OF BRYANT, SALINE COUNTY, ARKANSAS

LEGEND


- BENCH MARK
- FOUND IRON ROD
- FOUND IRON PIPE
- RIGHT OF WAY MARKER
- UTILITY POLE
- SUPPORT POLE
- UTILITY POLE WITH LIGHT
- LIGHT STANDARD
- ELECTRIC METER
- ELECTRIC MANHOLE
- ELECTRIC PEDESTAL
- ELECTRIC SPLICE BOX
- ELECTRIC BREAKER
- GAS DRIP
- GAS METER
- GAS VALVE
- TELEPHONE MANHOLE
- TELEPHONE PEDESTAL
- TELEPHONE SPLICE BOX
- CABLE TV PEDESTAL
- FIRE HYDRANT
- FIRE DEPARTMENT CONNECTION
- WATER MANHOLE
- WATER METER
- WATER VALVE
- POST INDICATOR VALVE
- CLEAN OUT
- STORM MANHOLE
- GRATED MANHOLE
- STORMWATER INLET
- GRATED STORMWATER INLET
- SANITARY MANHOLE
- TREE
- BUSH
- TRAFFIC SIGNAL
- PARKING METER
- STREET SIGN
- SPRINKLER
- MAIL BOX

LINE TYPE LEGEND

- EX CONT MJR
- EX CONT MNR
- TREE LINE
- FEMA ELEV
- FEMA LIMIT
- PAVEMENT
- WALL
- GUARD RAIL
- CHAINLINK/WIRE FENCE
- WOOD/VINYL FENCE
- GAS
- UNDER GROUND ELEC
- OVERHEAD ELEC
- TELEPHONE LINE
- FIBER OPTIC LINE
- WATERLINE
- FLOODWAY
- SLOPE/LEVEE

ABBREVIATIONS

C.O.	–	CLEANOUT
DB.	–	DEED BOOK
E	–	ELECTRIC
FL	–	FLOWLINE
FT	–	FEET
FND.	–	FOUND
G	–	GAS
M.H.	–	MANHOLE
N/F	–	NOW OR FORMERLY
PB.	–	PLAT BOOK
PG.	–	PAGE
P.V.C.	–	POLYVINYL CHLORIDE PIPE
R.B.	–	RADIAL BEARING
R.C.P.	–	REINFORCED CONCRETE PIPE
SQ.	–	SQUARE
T	–	TELEPHONE CABLE
V.C.P.	–	VETRIFIED CLAY PIPE
W	–	WATER
(80'W)	–	RIGHT-OF-WAY WIDTH



SHEET INDEX

C1.0	TITLE SHEET
C2.0	SPECIFICATIONS
C3.0	EXISTING CONDITIONS & DEMOLITION PLAN
C3.1	EXISTING PROPERTY SURVEY
C3.2	SUBDIVISION PLAT
C4.0	PRE-CONSTRUCTION SWPPP
C4.1	CONSTRUCTION SWPPP
C4.2	POST-CONSTRUCTION SWPPP
C4.3	STORMWATER POLLUTION PREVENTION DETAILS
C5.0	SITE GRADING PLAN
C5.1	ENTRANCE WARPING DETAIL
C6.0	SITE UTILITY PLAN
C7.0	SITE GEOMETRIC PLAN
C8.0	STORM SEWER PROFILES
C9.0	CONSTRUCTION DETAILS
C9.1	CONSTRUCTION DETAILS
C9.2	CONSTRUCTION DETAILS
C10.0	PRE-DEVELOPED DRAINAGE AREA MAP
C10.1	POST-DEVELOPED DRAINAGE AREA MAP
L1.01	LANDSCAPE PLAN

PERTINENT DATA

TRACT AREA:	1.99 ± AC.
CURRENT OWNER:	NEATHERY SHARON CLYDENA
SITE ADDRESS:	3205 HWY 5 N, BRYANT, AR 72019 2320 HURRICANE LAKE RD, BRYANT, AR 72019
PARCEL ID:	840-12042-000, 840-12038-000
FEMA FLOOD MAP:	05125C0360E (REVISED JUNE 05, 2020)
EXISTING ZONING:	"C-2" – HIGHWAY COMMERCIAL
PROPOSED USE:	COMMUNITY BUSINESS – MARIJUANA DISPENSARY

PARKING CALCS.

MINIMUM PARKING FOR C-2 DISTRICT:
1.0 SPACES PER 300 SF
(1,960 SF/300 SF) * 1.0 SPACE = 6.53 OR A MINIMUM OF 7 SPACES

PARKING SPACES PROVIDED = 36 SPACES (2 ADA)

GENERAL NOTES

1. BOUNDARY AND TOPOGRAPHIC SURVEY BY STOCK & ASSOCIATES CONSULTING ENGINEERS, INC.
2. ALL UTILITIES SHOWN HAVE BEEN LOCATED BY THE ENGINEER FROM AVAILABLE RECORDS. THEIR LOCATION SHOULD BE CONSIDERED APPROXIMATE. THE CONTRACTOR HAS THE RESPONSIBILITY TO NOTIFY ALL UTILITY COMPANIES, PRIOR TO CONSTRUCTION, TO HAVE EXISTING UTILITIES FIELD LOCATED.
3. ALL IMPROVEMENTS SHALL CONFORM TO THE CITY OF BRYANT STANDARDS AND SPECIFICATIONS.

UTILITY CONTACTS

SUMMIT UTILITIES (GAS) – SHANE GIBBONS, (501) 581-9428
BRYANT PUBLIC WORKS – BRYCE RIMMER, (501) 943-0458
WATER CONTACT – VERNON WILLIAMS, (501) 452-2771
SALEM WATER USERS – (501) 772-2212

FLOOD NOTE

SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X (AREA OF MINIMAL FLOOD HAZARD) ACCORDING TO THE NATIONAL FLOOD INSURANCE RATE MAP NUMBER 05125C0360E WITH AN EFFECTIVE DATE OF 06/05/2020.

PREPARED FOR:
GOOD DAY FARM
C/O REGAN ETHERIDGE
SENIOR PROJECT MANAGER–
STORE DEVELOPMENT, DESIGN & CONSTRUCTION
425 W. CAPITOL AVE.,
LITTLE ROCK, AR 72201

USGS BENCHMARK

BENCHMARK# R 338 ELEV.=405.60 (NAVD88)
DESCRIBED BY ARKANSAS DEPARTMENT OF TRANSPORTATION 2013 THE STATION IS LOCATED ABOUT 5.9 MI (9.5 KM) EAST-SOUTHEAST OF CONGO, 3.0 MI (4.8 KM) WEST OF ALEXANDER AND 1.8 MI (2.9 KM) NORTH OF BRYANT.
TO REACH FROM THE INTERSECTION OF BASELINE ROAD AND NORTH FRONTAGE ROAD PARALLELING I-30, GO WEST ON NORTH FRONTAGE ROAD FOR 7.48 MITO THE STATION ON THE RIGHT, IN THE CENTER OF A HEADWALL.
IT IS 85 FT (25.9 M) WEST OF A COMBINATION POLE AND 20 FT (6.1 M) NORTH OF THE CENTERLINE OF NORTH FRONTAGE ROAD.

DISCLAIMER

STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. AND THE UNDERSIGNED ENGINEER HAVE NO RESPONSIBILITY FOR SERVICES PROVIDED BY OTHERS TO IMPLEMENT THE IMPROVEMENTS SHOWN ON THIS PLAN AND ALL OTHER DRAWINGS WHERE THE UNDERSIGNED ENGINEER'S SEAL APPEARS. THE CONSTRUCTION MEANS AND METHODS ARE THE SOLE RESPONSIBILITY OF THE OWNER AND CONTRACTOR. STOCK AND ASSOCIATES CONSULTING ENGINEERS, INC. HAS NO RESPONSIBILITY TO VERIFY FINAL IMPROVEMENTS AS SHOWN ON THIS PLAN UNLESS SPECIFICALLY ENGAGED AND AUTHORIZED TO DO SO BY THE OWNER OR CONTRACTOR.

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH. (636) 530-9100 FAX (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:
GOOD DAY FARM - BRYANT
3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
GEORGE M. STOCK
REGISTERED PROFESSIONAL ENGINEER
E-25116
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
TITLE SHEET

SHEET NO.:
C1.0

Drawing File: S:\Stock\2025\07\Good Day Farm - Bryant\Civil\CAD\Sheets\Site Plan.dwg 7/16/2025 12:57:56 PM Brent PUTTER 64 bit (LMS Tech plotters).ctb

GENERAL NOTES

1. SAFETY NOTICE TO CONTRACTOR: IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS OF THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT WILL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
2. THE CONTRACTOR SHALL ALSO BE SOLELY RESPONSIBLE FOR THE SAFETY FOR THE GENERAL PUBLIC AND PASSERBY WITH RESPECT TO WORK ZONE AREAS, MEANS AND METHODS AND PEDESTRIAN SAFETY.
3. ALL EXCAVATIONS, WHETHER THEY ARE FOR RETAINING WALLS, UTILITY TRENCHES OR FOOTING EXCAVATIONS, SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE LATEST OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) "CONSTRUCTION STANDARDS FOR EXCAVATIONS".
4. PROPERTY LINES, EASEMENTS AND TOPOGRAPHIC SURVEY BY STOCK & ASSOCIATES CONSULTING ENGINEERS.
5. ALL UTILITIES, STRUCTURES AND UNDERGROUND FACILITIES HAVE BEEN PLOTTED FROM BEST AVAILABLE RECORDS. THEREFORE, THE RELATIONSHIP BETWEEN PROPOSED WORK AND EXISTING FACILITIES, STRUCTURES AND UTILITIES MUST BE CONSIDERED APPROXIMATE; AND IT IS THE CONTRACTORS RESPONSIBILITY TO DETERMINE THEIR LOCATION AND THE EXISTENCE OF ANY NOT SHOWN. THE CONTRACTOR HAS THE RESPONSIBILITY TO NOTIFY ALL UTILITY COMPANIES, PRIOR TO CONSTRUCTION, TO HAVE EXISTING UTILITIES FIELD LOCATED, UNCOVERED AND DEPTHS VERIFIED TO AVOID CONFLICTS.
6. IT IS NOT WARRANTED THAT THESE PLANS CONTAIN COMPLETE INFORMATION REGARDING EASEMENTS, RESERVATIONS, RESTRICTIONS, RIGHT-OF-WAY, BUILDING LINES AND OTHER ENCUMBRANCES. FOR COMPLETE INFORMATION, A TITLE OPINION OR COMMITMENT FOR TITLE INSURANCE SHOULD BE OBTAINED.
7. THIS PLAN IS SUBJECT TO ALL LOCAL, STATE AND FEDERAL REGULATIONS. THERE HAS BEEN NO WETLAND DELINEATION, GEOTECHNICAL OR ENVIRONMENTAL DATA PROVIDED TO THIS ENGINEER PRIOR TO DESIGNING THIS PLAN.
8. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY CONFLICTS WITH PROPOSED IMPROVEMENTS.
9. IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE HE HAS THE LATEST SET OF IMPROVEMENT PLANS. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR COORDINATING ALL PERMIT PLAN SETS AND ANY SUBSEQUENT PLAN ISSUANCES.
10. IMPROVEMENTS SHALL BE STAKED IN THE FIELD BY THE CONTRACTOR AND REVIEWED BY THE ARCHITECT AND OWNER PRIOR TO INSTALLATION. CONTRACTOR SHALL REVIEW OTHER SITE-RELATED SHEETS BY OTHER DESIGNERS (LANDSCAPING, ARCHITECT, ETC.) IN ADDITION TO CIVIL SHEETS FOR COORDINATION PURPOSES. ANY CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY AND PRIOR TO ANY START OF CONSTRUCTION.
11. THE CONTRACTOR SHALL MAINTAIN A COMPLETE SET OF RECORD DRAWINGS AT THE JOB SITE AND MARK THEREON ANY CHANGES AS THE WORK PROCEEDS. THE CONTRACTOR SHALL SUBMIT COMPUTER GENERATED, LEGIBLE RECORD DRAWINGS TO THE ENGINEER PRIOR TO FINAL INSPECTION AND ACCEPTANCE.
12. ALL WORK WITHIN PUBLIC RIGHT-OF-WAY SHALL BE TO CITY OF BRYANT OR ARKANSAS HIGHWAYS AND TRANSPORTATION STANDARDS, WHERE APPLICABLE.
13. ALL MATERIALS AND METHODS OF CONSTRUCTION TO MEET THE CURRENT STANDARDS AND SPECIFICATIONS OF CITY OF BRYANT OR ARKANSAS HIGHWAYS AND TRANSPORTATION, WHERE APPLICABLE.
14. THE CONTRACTOR SHALL COORDINATE AND/OR OBTAIN ALL NECESSARY LOCAL, STATE, AND FEDERAL PERMITS RELATED TO CONSTRUCTION OF THE IMPROVEMENTS.
15. PRIOR TO BEGINNING ANY WORK, THE CONTRACTOR SHALL CONTACT THE OFFICE OF THE OWNER FOR SPECIFIC INSTRUCTIONS RELEVANT TO THE SEQUENCING OF WORK.
16. ALL WORK MUST BE PERFORMED WITHIN EXISTING OR ACQUIRED EASEMENTS. AGENCY APPROVAL OF THESE PLANS DOES NOT AUTHORIZE OR CONDONE WORK OUTSIDE OF THE EASEMENTS.
17. THE DEVELOPER OR OWNER IS ADVISED THAT UTILITY COMPANIES MAY REQUIRE COMPENSATION FOR RELOCATION OF THEIR FACILITIES WITHIN THE PUBLIC RIGHT-OF-WAY. THE DEVELOPER OR OWNER SHALL ALSO BE MADE AWARE OF EXTENSIVE DELAYS IN UTILITY COMPANY RELOCATIONS AND ADJUSTMENTS WHICH MAY OCCUR.
THE DELAYS DUE TO UTILITY RELOCATION AND ADJUSTMENTS WILL NOT CONSTITUTE A CAUSE TO ALLOW OCCUPANCY PRIOR TO COMPLETION OF ROAD IMPROVEMENTS.
18. THE CONTRACTOR SHALL VERIFY PROPOSED AND COORDINATE PROPOSED SERVICES AND LOCATIONS OR RELOCATIONS WITH ALL UTILITIES. CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL UTILITY PERMITS, UNLESS SPECIFICALLY MENTIONED OTHERWISE.
19. ALL PROPOSED UTILITIES TO BE LOCATED UNDERGROUND, UNLESS STATED OTHERWISE.
20. ALL HYDRANTS, POWER POLES OR OTHER OBSTRUCTIONS SHALL HAVE A MINIMUM TWO FOOT SETBACK FROM FACE OF CURB OR EDGE OF SHOULDER OF THE ULTIMATE PAVEMENT SECTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONFIRMING THIS REQUIREMENT, PRIOR TO CONSTRUCTION. ANY LOCATION WHICH DOES NOT MEET THIS REQUIREMENT SHALL BE BROUGHT TO THE ENGINEER'S ATTENTION IMMEDIATELY. THE CONTRACTOR SHALL ASSUME ALL LIABILITY IF CONFLICTS ARE NOT BROUGHT TO THE ENGINEERS ATTENTION FOR A DETERMINATION HOW TO PROCEED PRIOR TO CONSTRUCTION.
21. ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH THE CURRENT EDITION OF THE MANUAL FOR UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND ArDOT, WHERE APPLICABLE.
22. ACCESS TO PRIVATE PROPERTIES SHALL BE MAINTAINED AT ALL TIMES. EXISTING COMMERCIAL ENTRANCES MAY HAVE ACCESS RESTRICTED TO 1/2 OF THE ENTRANCE AT A TIME, UNLESS OTHERWISE APPROVED IN THIS PLAN SET.
23. NO SIDEWALK SHALL BE REMOVED WITHOUT CONFIRMING ADEQUATE PEDESTRIAN FACILITIES WILL EXIST DURING CONSTRUCTION. PROJECT NEEDS TO PROVIDE CONTINUOUS PEDESTRIAN ACCESS DURING CONSTRUCTION, UNLESS APPROVED ELSEWHERE. FOR SIDEWALK REMOVAL/REPLACEMENT VERIFY THERE IS ADEQUATE PEDESTRIAN ACCESS AROUND SITE, OR PROVIDE TEMPORARY PEDESTRIAN ACCESS.
24. IF A PEDESTRIAN DETOUR PLAN IS NOT INCLUDED IN THIS PLAN SET, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CREATING A DETOUR PLAN AND SUBMITTING SAID PLAN TO THE ENGINEER AND AGENCIES FOR REVIEW AND APPROVAL.
25. ALL SIDEWALKS, CURB RAMPS, RAMPS, ACCESSIBLE PARKING SPACES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT APPROVED "AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES" (ADAAG) ALONG WITH THE GRADES, CONSTRUCTION MATERIALS, SPECIFICATIONS, AND SIGNAGE. IF ANY CONFLICT OCCURS BETWEEN THE ABOVE INFORMATION AND THE PLANS, THE ADAAG GUIDELINES SHALL TAKE PRECEDENCE, AND THE CONTRACTOR, PRIOR TO ANY CONSTRUCTION, SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL VERIFY THESE IMPROVEMENTS WITH THE ENGINEER PRIOR TO INSTALLATION.
26. THE CONTRACTOR SHALL BE MADE AWARE THAT CERTAIN EXCEPTIONS TO ADA REQUIREMENTS MAY BE APPLICABLE. UNLESS SPECIFICALLY NOTED WITHIN THIS PLAN SET, THE CONTRACTOR SHALL ASSUME THAT NO EXCEPTION WILL APPLY.
27. ALL SIDEWALKS (THICKNESS AND WIDTH) AND CURB RAMPS TO BE CONSTRUCTED IN ACCORDANCE WITH ADA, CITY OF BRYANT OR ARKANSAS HIGHWAYS AND TRANSPORTATION STANDARDS.
28. ANY DISTURBED OFF-SITE PROPERTY (I.E. BUSHES, TREES, FENCES, MAILBOXES, ETC.), WHICH MAY NOT BE LABELED, SHALL BE REPLACED IN-KIND AT THE DEVELOPER'S EXPENSE.
29. SIGNAGE SHALL BE IN ACCORDANCE WITH CITY OF BRYANT SIGN ORDINANCE(S).
30. THE MINIMUM REQUIREMENTS OF THE STORMWATER MANAGEMENT PLAN SHALL BE CONSISTENT WITH THE CURRENTLY EFFECTIVE VERSION OF THE ADEQ'S NPDES CONSTRUCTION STORM WATER PERMIT REQUIREMENTS.

DEMOLITION NOTES

1. CONTRACTOR SHALL VISIT THE PROJECT SITE TO DETERMINE EXTENT OF DEMOLITION.
2. USE OF EXPLOSIVES OR BURNING IS NOT PERMITTED.
3. PAVEMENT AREAS, CURBS, BUILDINGS, TREES, ETC. SHALL BE REMOVED IN COMPLIANCE WITH ALL GOVERNING AGENCIES.
4. CONTRACTOR SHALL OBTAIN HAUL ROUTE APPROVAL FROM CITY OF BRYANT OR ARKANSAS DEPARTMENT OF TRANSPORTATION PRIOR TO COMMENCEMENT OF HAULING OPERATIONS, IF REQUIRED.
5. THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE UTILITY COMPANY PRIOR TO BEGINNING ANY WORK THAT WILL AFFECT AN EXISTING UTILITY.
6. CONTRACTOR TO COORDINATE RELOCATIONS, ABANDONMENT OR REMOVAL OF EXISTING UTILITIES WITH UTILITY COMPANIES TO AVOID INTERRUPTION OF SERVICE TO BUILDINGS OUTSIDE OF SPECIFIED PHASE OF WORK.
7. CONTRACTOR SHALL COORDINATE ALL UTILITY SERVICE INSTALLATIONS, REMOVALS, RELOCATIONS AND ABANDONMENT WITH PROPOSED IMPROVEMENTS. CONTRACTOR SHALL AVOID CONDITION WHERE NEW PAVEMENT, CURBING, SIDEWALK, ETC. WILL BE DISTURBED BY UTILITY INSTALLATION.
8. ALL EROSION CONTROL AND SILTATION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO DEMOLITION.
9. PROTECT EXISTING TREES AND VEGETATION INDICATED TO REMAIN SHALL BE PROTECTED AGAINST UNNECESSARY CUTTING OR SKINNING OF ROOTS, BRANCHES OR BARK, SMOTHERING OF TREES BY STOCKPILE MATERIAL, OR PARKING VEHICLES WITHIN DRIP LINE. PROTECT TREES AND VEGETATION TO REMAIN WITH TEMPORARY CONSTRUCTION FENCING, PRIOR TO SITE CLEARING OPERATIONS.
10. EXISTING PROPERTY CORNERS AND/OR SURVEY MONUMENTS DISTURBED BY CONSTRUCTION TO BE REMOVED AND REPLACED BY LICENSED SURVEYOR IN MISSOURI.
11. REMOVAL AND/OR ABANDONMENT OF EXISTING SEWERS SHALL BE IN ACCORDANCE WITH THE STANDARD CONSTRUCTION SPECIFICATIONS FOR SEWER AND DRAINAGE FACILITIES OF ArDOT OR THE CITY OF BRYANT SEWER DISTRICT, WHERE APPLICABLE.
12. EXISTING SEWERS INDICATED TO BE REMOVED AND/OR ABANDONED SHALL BE SECURELY BLOCKED AT ANY POINTS OF INTAKE OR DISCHARGE (OF THE SYSTEM TO REMAIN) WITH THE BULKHEAD OR PREFORMED PLUG. IF THE SEWER IS ABANDONED, IT SHALL BE COMPLETELY FILLED WITH GROUT.
13. ANY SEWER INLETS INDICATED TO REMAIN IN PLACE BUT ARE CHOKED SHALL BE CLEANED OUT AND POSITIVE FLOW SHALL BE VERIFIED. IF INLETS ARE UNABLE TO BE REPAIRED, THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY.
14. EXISTING WATER METERS, HYDRANTS AND VALVES INDICATED TO REMAIN SHALL HAVE CONNECTING PIPES FIELD LOCATED AND ANY CONFLICTS WITH THE PROPOSED IMPROVEMENTS SHALL BE REPORTED TO THE ENGINEER.
15. CONSTRUCTION DEBRIS, INCLUDING BUT NOT LIMITED TO, CONDUIT, DUCTS, FITTINGS, VALVES, PIPES AND OTHER DEBRIS TO BE REMOVED, SHALL BE DISPOSED OF OFF-SITE, AND IN ACCORDANCE WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS.
16. CONTRACTOR TO PROVIDE ALL NECESSARY FENCING, BARRICADES, SIGNAGE, ETC. FOR PEDESTRIAN SAFETY DURING SITE DEMOLITION/CONSTRUCTION ACTIVITIES.
17. A PEDESTRIAN DETOUR PLAN SHALL BE IMPLEMENTED IF PUBLIC SIDEWALKS ARE TO BE CLOSED DURING CONSTRUCTION.
18. DEMOLITION LIMITS OF EXISTING SIDEWALK, CURB LINE, CURB RAMPS AND ROADWAY HAS BEEN APPROXIMATED AND SHOWN ON THE DEMOLITION SHEET(S).
19. REMOVAL OF PAVEMENT, CURB & GUTTER, SIDEWALKS, ETC. SHALL BE TO THE NEAREST EXISTING JOINT OR FULL DEPTH SAWCUT AT LIMITS OF REMOVAL.
20. SAWCUTTING, CURB AND PAVEMENT REMOVALS TO BE COORDINATED WITH INSTALLATION OF PROPOSED UTILITY MAINS AND SERVICES WITH INSTALLATION OF PROPOSED UTILITY MAINS AND SERVICES. CONTRACTOR TO CONTACT UTILITY COMPANIES TO COORDINATE PAVEMENT REMOVAL AND/OR REPLACEMENT BY UTILITY COMPANY WITH ON-SITE DEMOLITION BY CONTRACTOR.
21. EXISTING PAVEMENT SHOWN TO BE REMOVED SHALL REQUIRE BACKFILL AND PROPER COMPACTION WITH GRADES TO BE RE-ESTABLISHED TO AVOID CONDITIONS WHERE PONDING WATER OCCURS.
23. DEBRIS AND FOUNDATION MATERIAL FROM ANY EXISTING ON-SITE BUILDING OR STRUCTURE WHICH IS SCHEDULED TO BE RAZED FOR THIS DEVELOPMENT MUST BE PROPERLY DISPOSED OF OFF-SITE.
24. CONTRACTOR TO COORDINATE REMOVAL AND/OR DISCONNECTION OF EXISTING SERVICE LINES TO ANY BUILDING PRIOR TO BUILDING DEMOLITION.

SANITARY SEWER NOTES

1.) ALL SEWER CONSTRUCTION AND MATERIALS TO BE IN ACCORDANCE WITH THE CITY OF BRYANT SPECIFICATIONS AND STANDARDS.

2.) 6" AND 8" LATERALS CONSTRUCTED OF P.V.C.S.D. R.-35 THICKWALL PIPE, A.S.T.M. D-3034.

3.) 6" AND 8" LATERAL JOINTS TO CONFORM TO A.S.T.M. STANDARD S.D.R.-35 THICKWALL COMPRESSION JOINT FOR P.V.C..

4.) ALL MANHOLE FRAMES AND COVERS SHALL BE CITY OF BRYANT STANDARD FRAME AND COVER.

5.) ALL LATERAL SEWER CONSTRUCTION METHODS TO CONFORM TO LATEST STANDARDS AND SPECIFICATIONS OF THE CITY OF BRYANT PLUMBING CODE.

6.) ALL TRENCHES UNDER AREAS TO BE PAVED SHALL BE GRANULARLY FILLED WITH 3/4" CLEAN ROCK BEDDING. BACKFILL SHALL BE PLACED IN ACCORDANCE WITH THE CITY OF BRYANT SPECIFICATIONS AND STANDARDS.

7) CONTRACTOR TO START LAYING PIPE AT DOWNSTREAM MANHOLE AND WORK UPSTREAM.

8.) CLEANOUTS SHALL BE LOCATED AT ALL HORIZONTAL AND VERTICAL CHANGES IN DIRECTION OF FLOW OF HOUSE LATERALS AND ANY SANITARY LATERAL OF 100 FEET OR LONGER.

9.) HAUNCH CATEGORY I BEDDING PER CITY STANDARDS REQUIRED FOR PIPES IN ROCK.

10.) VERTICAL CLEARANCE BETWEEN SEWER AND WATER MAINS SHALL BE A MINIMUM OF 2' - 0".

11.) ALL TRENCH BACKFILLS UNDER PAVEMENT WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE GRANULAR BACKFILLED. TRENCH BACKFILLS UNDER PAVED AREAS, OUTSIDE OF PUBLIC RIGHT-OF-WAY SHALL BE GRANULAR BACKFILL IN LIEU OF THE EARTH BACKFILL COMPACTED TO 95 PERCENT OF THE STANDARD AASHTO T-99 COMPACTION TEST A.S.T.M. D-698.

12.) JETTING IS NOT AN ACCEPTABLE METHOD OF ACHIEVING BACKFILL COMPACTION. ALL BACKFILL MATERIAL SHALL BE MECHANICALLY COMPACTED TO AT LEAST 95 PERCENT OF THE MATERIAL'S STANDARD PROCTOR MAXIMUM DRY DENSITY.

13.) FOR SEWER PIPE (STORM AND SANITARY) WITH A DESIGN GRADE LESS THAN ONE PERCENT (1%), VERIFICATION OF THE PIPE GRADE WILL BE REQUIRED FOR EACH INSTALLED REACH OF SEWER, PRIOR TO ANY SURFACE RESTORATION OR INSTALLATION OF ANY SURFACE IMPROVEMENTS. THE CONTRACTOR'S FIELD SUPERVISOR WILL BE REQUIRED TO PROVIDE DAILY DOCUMENTATION VERIFYING THAT THE AS-BUILT PIPE GRADE MEETS THE DESIGN GRADE THROUGH THE SUBMITTAL OF SIGNED CUT SHEETS TO THE CITY OF BRYANT INSPECTOR UPON REQUEST.

FIELD SURVEYED VERIFICATION MUST BE MADE UNDER THE DIRECTION OF A LICENSED LAND SURVEYOR OR REGISTERED ENGINEER. THE CONTRACTOR WILL BE REQUIRED TO REMOVE AND REPLACE ANY SEWER REACH HAVING AN AS-BUILT GRADE WHICH IS FLATTER THAN THE DESIGN GRADE BY MORE THAN 0.1%. SEWERS WITH GRADES GREATER THAN THE DESIGN SLOPE MAY BE LEFT IN PLACE, PROVIDED NO OTHER SEWER GRADE IS REDUCED BY THIS VARIANCE IN THE AS-BUILT GRADE.

THE CITY ALSO RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO REMOVE AND REPLACE ANY SEWER (AT ANY TIME PRIOR TO CONSTRUCTION APPROVAL) FOR WHICH THE AS-BUILT GRADE DOES NOT COMPLY WITH THE GRADE TOLERANCE STATED IN THE ABOVE PARAGRAPH.

THE SEWER CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COSTS ASSOCIATED WITH THE FIELD VERIFICATION OF THE SEWER GRADE, OR REMOVAL AND REPLACEMENT OF THE SEWER PIPE OR ASSOCIATED APPURTENANCES.

14.) ADJUSTMENT OF MANHOLE TO GRADE:
IF A MANHOLE IS TO BE RAISED: MANHOLES MAY BE RAISED USING COURSES OF BRICK OR APPROVED GRADE RING(S), PROVIDED THE TOTAL ADJUSTMENT OF THE MANHOLE DOES NOT EXCEED 12-INCHES (INCLUDING THE EXISTING RINGS OR COURSES OF BRICK). FOR MANHOLES WHICH WILL EXCEED THE MAXIMUM OF 12-INCHES, THE TRANSITION SECTION OF THE STRUCTURE SHALL BE REMOVED AND THE BOTTOM SECTION RAISED USING THE SAME MATERIAL AS THE EXISTING STRUCTURE.

IF A MANHOLE IN TO BE LOWERED: MANHOLES MAY BE LOWERED BY REMOVING THE TRANSITION SECTION, AND LOWERING THE EXISTING BOTTOM SECTION BY SAWCUTTING THE EXISTING CAST-IN-PLACE CONCRETE, REMOVING THE REQUIRED COURSES OF BRICK, OR REMOVING THE PRECAST RISER SECTION AS APPROPRIATE.

15.) FOUNDATION DRAINS, IF INSTALLED, SHALL NOT CONNECT TO THE SANITARY SEWER.

16.) EXTERNAL GREASE TRAP REQUIRED. GREASE TRAP TO BE LOCATED IN AN ACCESSIBLE LOCATION FOR CITY INSPECTION. GREASE TRAP TO PROVIDE MEANS FOR VISUAL INSPECTION FROM ABOVE FOR BOTH THE INFLUENT AND EFFLUENT SIDES.

17.) ALL SEWER CONSTRUCTION AND MATERIALS TO BE IN ACCORDANCE WITH THE CITY OF BRYANT SPECIFICATIONS AND STANDARDS.

18.) ALL SEWER CONSTRUCTION AND MATERIALS TO BE IN ACCORDANCE WITH THE CLEAN WATER ACT.

GRADING NOTES

1. ALL EROSION AND SILTATION CONTROL SHALL BE INSTALLED PRIOR TO STARTING CONSTRUCTION OR GRADING.
2. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTORS TO CONSULT PROJECT GEOTECHNICAL ENGINEER(S), FOR REVIEW OF THIS PLAN PRIOR TO GRADING OPERATIONS AND FOR GRADING RECOMMENDATIONS AND FIELD TESTING.
3. PROPOSED GRADES AND CONTOURS SHOWN ARE TO FINISHED ELEVATION. CONTRACTOR TO ACCOUNT FOR ALL TOP FINISHES INCLUDING BUT NOT LIMITED TO PAVEMENT, SUB-BASES, SOD, TOPSOIL, RIP-RAP AND FIELD TOP MIXES.
4. ALL GRADING WILL UTILIZE STANDARD GRADING EQUIPMENT TO ACHIEVE THE PROPOSED GRADES SHOWN ON THIS PLAN.
5. TOP OF SEWER STRUCTURE ELEVATIONS SHALL BE VERIFIED BY THE CONTRACTOR IN THE FIELD PRIOR TO FINAL INSTALLATION OF STRUCTURE TOP.
6. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR COSTS INCURRED DUE TO UNSUITABLE MATERIAL THAT MUST BE REMOVED FROM SITE.
7. NO EXCAVATION SHALL BE MADE SO CLOSE TO THE PROPERTY LINE AS TO ENDANGER ANY ADJOINING PROPERTY OF ANY PUBLIC OR PRIVATE STREET WITHOUT SUPPORTING AND PROTECTING SUCH PUBLIC OR PRIVATE STREET, PROPERTY OR UTILITY FROM SETTLING, CRACKING OR OTHER DAMAGE.
8. ALL EXCAVATIONS, GRADING OR FILLING SHALL HAVE A FINISHED GRADE NOT TO EXCEED A 3:1 SLOPE (33%), UNLESS SPECIFICALLY APPROVED OTHERWISE.
9. EARTHWORK QUANTITIES ARE THE RESPONSIBILITY OF CONTRACTORS. THE CONTRACTOR IS RESPONSIBLE FOR HAUL-ON OR HAUL-OFF MATERIAL FROM SITE, AS MAY BE REQUIRED.
10. ALL FILLS AND BACKFILLS SHALL BE MADE OF SELECTED EARTH MATERIALS FREE FROM BROKEN MASONRY, ROCK, FROZEN EARTH, RUBBISH, ORGANIC MATERIAL AND DEBRIS, AND AS APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER.
11. ALL FILLS PLACED UNDER PROPOSED STORM AND SANITARY SEWER LINES AND/OR PAVED AREAS, INCLUDING TRENCH BACKFILLS AND WITHIN AND OFF THE ROAD RIGHT-OF-WAY, SHALL BE COMPACTED TO 90% OF MAXIMUM DENSITY AS DETERMINED BY THE "MODIFIED AASHTO T-180 COMPACTION TEST" (ASTM D-1557) FOR THE ENTIRE DEPTH OF THE FILL. COMPACTED GRANULAR BACKFILL IS REQUIRED IN ALL TRENCH EXCAVATION WITHIN THE STREET RIGHT-OF-WAY AND UNDER ALL PAVED AREAS. ALL TESTS SHALL BE PERFORMED UNDER THE DIRECTION OF AND VERIFIED BY A SOILS ENGINEER CONCURRENT WITH GRADING AND BACKFILLING OPERATIONS.
12. SOFT SOILS IN THE BOTTOM AND BANKS OF ANY EXISTING OR FORMER POND SITES OR TRIBUTARIES OR ANY SEDIMENT BASINS OR TRAPS SHOULD BE REMOVED, SPREAD OUT AND PERMITTED TO DRY SUFFICIENTLY TO BE USED AS FILL. NONE OF THIS MATERIAL SHOULD BE PLACED IN PROPOSED PUBLIC RIGHT-OF-WAY LOCATIONS OR IN ANY STORM SEWER LOCATIONS.
13. THE CONTRACTOR SHALL VERIFY THAT ALL AREAS WILL DRAIN POSITIVELY AND WITHOUT PONDING PRIOR TO INSTALLATION OF IMPROVEMENTS.
14. STORMWATER TO BE DISCHARGED AT ADEQUATE NATURAL DISCHARGE POINT. SINKHOLES ARE NOT AN ADEQUATE NATURAL DISCHARGE POINTS.
15. ANY WELLS, CISTERNS AND/OR SPRINGS, WHICH MAY EXIST ON THE PROPERTY, SHOULD BE LOCATED AND SEALED IN A MANNER ACCEPTABLE TO CITY OF BRYANT AND THE ARKANSAS DEPARTMENT OF AGRICULTURE .
16. DESIGN OF SHORING FOR UTILITY TRENCHES AND/OR SEWER CONSTRUCTION IS THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS OTHERWISE NOTED IN THIS SET OF PLANS.
17. TRUCKS SHALL NOT EXCEED POSTED WEIGHT LIMITS FOR ANY ROAD TRAVELED OR BRIDGES DURING HAUL OPERATIONS.
18. CONTRACTOR SHALL OBTAIN HAUL ROUTE APPROVAL FROM CITY OF BRYANT OR ARKANSAS DEPARTMENT OF TRANSPORTATION PRIOR TO COMMENCEMENT OF HAULING OPERATIONS, IF REQUIRED.
19. PROTECT EXISTING TREES AND VEGETATION INDICATED TO REMAIN SHALL BE PROTECTED AGAINST UNNECESSARY CUTTING OR SKINNING OF ROOTS, BRANCHES OR BARK, SMOTHERING OF TREES BY STOCKPILE MATERIAL, OR PARKING VEHICLES WITHIN DRIP LINE. PROTECT TREES AND VEGETATION TO REMAIN WITH TEMPORARY CONSTRUCTION FENCING, PRIOR TO SITE CLEARING OPERATIONS.
20. ALL OPEN SPACE DETENTION AREAS SHALL BE REVEGETATED WITH BERMUDA SOD.

STORM SEWER NOTES

1.) ALL CONCRETE PIPE SHALL BE REINFORCED, AND CONFORM TO A.S.T.M. DESIGNATION C76-80 CLASS UNLESS NOTED.

2.) ALL SEWER CONSTRUCTION AND MATERIALS TO BE IN ACCORDANCE WITH THE CITY OF BRYANT STREET, STORM DRAIN AND SANITARY SEWER SPECIFICATIONS AND STANDARDS.

3.) ALL TRENCHES UNDER AREAS TO BE PAVED AND UNDER EXISTING PAVING SHALL BE GRANULARLY FILLED WITH 3/4" CLEAN BACKFILL ONLY. BACKFILL SHALL BE PLACED IN ACCORDANCE WITH CITY OF BRYANT STANDARDS.

4.) ALL TRENCH BACKFILLS UNDER PAVEMENT WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE GRANULAR BACKFILLED. TRENCH BACKFILLS UNDER PAVED AREAS, OUTSIDE OF PUBLIC RIGHT-OF-WAY SHALL BE GRANULAR BACKFILL IN LIEU OF THE EARTH BACKFILL COMPACTED TO 95 PERCENT OF THE STANDARD AASHTO T-99 COMPACTION TEST A.S.T.M. D-698.

5.) JETTING IS NOT AN ACCEPTABLE METHOD OF ACHIEVING BACKFILL COMPACTION. ALL BACKFILL MATERIAL SHALL BE MECHANICALLY COMPACTED TO AT LEAST 95 PERCENT OF THE MATERIAL'S STANDARD PROCTOR MAXIMUM DRY DENSITY.

6.) FOR SEWER PIPE (STORM AND SANITARY) WITH A DESIGN GRADE LESS THAN ONE PERCENT (1%), VERIFICATION OF THE PIPE GRADE WILL BE REQUIRED FOR EACH INSTALLED REACH OF SEWER, PRIOR TO ANY SURFACE RESTORATION OR INSTALLATION OF ANY SURFACE IMPROVEMENTS. THE CONTRACTOR'S FIELD SUPERVISOR WILL BE REQUIRED TO PROVIDE DAILY DOCUMENTATION VERIFYING THAT THE AS-BUILT PIPE GRADE MEETS THE DESIGN GRADE THROUGH THE SUBMITTAL OF SIGNED CUT SHEETS TO THE CITY OF BRYANT INSPECTOR UPON REQUEST.

FIELD SURVEYED VERIFICATION MUST BE MADE UNDER THE DIRECTION OF A LICENSED LAND SURVEYOR OR REGISTERED ENGINEER. THE CONTRACTOR WILL BE REQUIRED TO REMOVE AND REPLACE ANY SEWER REACH HAVING AN AS-BUILT GRADE WHICH IS FLATTER THAN THE DESIGN GRADE BY MORE THAN 0.1%. SEWERS WITH GRADES GREATER THAN THE DESIGN SLOPE MAY BE LEFT IN PLACE, PROVIDED NO OTHER SEWER GRADE IS REDUCED BY THIS VARIANCE IN THE AS-BUILT GRADE.

THE CITY ALSO RESERVES THE RIGHT TO REQUIRE THE CONTRACTOR TO REMOVE AND REPLACE ANY SEWER (AT ANY TIME PRIOR TO CONSTRUCTION APPROVAL) FOR WHICH THE AS-BUILT GRADE DOES NOT COMPLY WITH THE GRADE TOLERANCE STATED IN THE ABOVE PARAGRAPH.

THE SEWER CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COSTS ASSOCIATED WITH THE FIELD VERIFICATION OF THE SEWER GRADE, OR REMOVAL AND REPLACEMENT OF THE SEWER PIPE OR ASSOCIATED APPURTENANCES.

7.) ADJUSTMENT OF MANHOLE TO GRADE:
IF A MANHOLE IS TO BE RAISED: MANHOLES MAY BE RAISED USING COURSES OF BRICK OR APPROVED GRADE RING(S), PROVIDED THE TOTAL ADJUSTMENT OF THE MANHOLE DOES NOT EXCEED 12-INCHES (INCLUDING THE EXISTING RINGS OR COURSES OF BRICK). FOR MANHOLES WHICH WILL EXCEED THE MAXIMUM OF 12-INCHES, THE TRANSITION SECTION OF THE STRUCTURE SHALL BE REMOVED AND THE BOTTOM SECTION RAISED USING THE SAME MATERIAL AS THE EXISTING STRUCTURE.

IF A MANHOLE IS TO BE LOWERED:
MANHOLES MAY BE LOWERED BY REMOVING THE TRANSITION SECTION, AND LOWERING THE EXISTING BOTTOM SECTION BY SAWCUTTING THE EXISTING CAST-IN-PLACE CONCRETE, REMOVING THE REQUIRED COURSES OF BRICK, OR REMOVING THE PRECAST RISER SECTION AS APPROPRIATE.

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS REGISTERED PROFESSIONAL ENGINEER G. M. STOCK No. 8105

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO.: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
SPECIFICATIONS

SHEET NO.:
C2.0

Plotted by: EVANSTROUDT\ltroudt Plotted on: Thursday, July 24, 2025 - 1:58pm K:\2775\Dgn\Sheets\2775 Site.dwg

DEMO LEGEND

TBR = TO BE REMOVED

TBA = TO BE ABANDONED


TBR&R = TO BE REMOVED & REPLACED

DND = DO NOT DISTURB

UIP = USE IN PLACE

ATG = ADJUST TO GRADE

– – – – LIMITS OF DISTURBANCE



FLOOD NOTE

SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X (AREA OF MINIMAL FLOOD HAZARD) ACCORDING TO THE NATIONAL FLOOD INSURANCE RATE MAP NUMBER 05125C0360E WITH AN EFFECTIVE DATE OF 06/05/2020.

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS GEORGE M. STOCK REGISTERED PROFESSIONAL ENGINEER 2511E6 EXPIRES 6/30/26 GEORGE STOCK

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
EXISTING CONDITIONS AND DEMOLITION PLAN

SHEET NO.:
C3.0

Drawing File: S:\Drawings\2025\07\Good Day Farm - Bryant\Plans\Site Plan\GDF C3.0 EX. Conditions & Demo PLOTTED on 16, 2025 - 10:04am PLOTTED BY: Lisa Miller



FLOOD NOTE

SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X (AREA OF MINIMAL FLOOD HAZARD) ACCORDING TO THE NATIONAL FLOOD INSURANCE RATE MAP NUMBER 05125C0360E WITH AN EFFECTIVE DATE OF 06/05/2020.

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
GEORGE M. STOCK
No. 9116
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #
M.D.N.R. #:	

SHEET TITLE:
EXISTING PROPERTY SURVEY

SHEET NO.:
C3.1

Drawing File: G:\Drawings\2025\7775\Civil\Planning\7775 Base Map 1.dwg, 7/16/2025 2:41:16 PM, Plotted by: Lindsey Williams

GOOD DAY FARM - BRYANT

A TRACT OF LAND BEING PART OF THE SE 1/4 OF SECTION 20, TOWNSHIP 1 SOUTH, RANGE 14 WEST CITY OF BRYANT, SALINE COUNTY, ARKANSAS

LEGEND

- BENCH MARK
- FOUND IRON ROD
- FOUND IRON PIPE
- RIGHT OF WAY MARKER

GRAPHIC SCALE


250 0 125 250 500 1000

(IN FEET)
1 inch = 250 ft.

ARKANSAS SOUTH ZONE
US SURVEY FEET

ABBREVIATIONS

DB.	–	DEED BOOK
FL	–	FLOWLINE
FT.	–	FEET
FND.	–	FOUND
N/F	–	NOW OR FORMERLY
PB.	–	PLAT BOOK
PG.	–	PAGE
SQ.	–	SQUARE
(86'W)	–	RIGHT-OF-WAY WIDTH



LOCATION MAP
(NOT TO SCALE)

We, the undersigned , owners of the real estate shown and described herein do hereby certify that we have laid off, platted and subdivided, and do hereby lay off, plat and subdivide said real estate in accordance with the within plat.

_____ _____
Date of Execution Name
Address

AGENTS NATIONAL
TITLE INSURANCE COMPANY
December 6, 2024 at 12:00 AM
Source of Title D.R. 2025-002935

CERTIFICATE OF RECORDING

This document, number _____, filed for record _____, 19_____, in Plat Book _____, Page _____.

_____
Mark Smith, City Clerk

For Bill of Assurance see Deed Record Book _____, Page ____

CERTIFICATE OF ENGINEERING ACCURACY

I, _____, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their locations, size, type, and material are correctly shown; and that all requirements of the City of Bryant Subdivision Rules and Regulations have been fully complied with.

_____ _____
Date of Execution Registered Professional
Engineer No. _____, Arkansas


PRELIMINARY SURVEYING ACCURACY
hereby certify that this proposed preliminary plat correctly represents a survey completed by me, or under my supervision on _____, 2025; that the boundary lines shown hereon correspond with the description in the deeds cited in the above Source of Title; and that all monuments which were found or placed on the property are correctly described and located.

_____ Name: Randall S.Rosson
Registered Land Surveyor
_____ No. 1663
Date of Execution

CERTIFICATE OF FINAL PLAT APPROVAL
Pursuant to the City of Bryant Subdivision Rules and Regulations, this document was given approval by the Bryant Planning Commission at a meeting held _____, 2025. All of the document is hereby accepted, and this certificate executed under the authority of said rules and regulations.

_____ _____
Date of Execution Bryant Planning Commission

Approval of the Final Plat shall be null and void unless said plat is filed for record within one hundred twenty (120) days from the date of execution of this certificate.



GENERAL NOTES:

1) Lot 1 is Zoned : C-2 - GENERAL COMMERCIAL DISTRICT

SETBACKS: FRONT - 15 FEET MIN.
SIDE - 15 FEET
REAR - 25 FEET

Lot 2 is Zoned: Manufactured Home Residential District R-M

SETBACKS: FRONT - 20 FEET MIN.
SIDE - 8 interior 15 FEET exterior
REAR - 20 FEET

Note: The above zoning provided by the City of Bryant and to verify the client should obtain a zoning endorsement from their title company.

2) Subject property lies within Flood Zone X (Areas of minimal flood hazard) according to the National Flood Insurance Rate Map Number 05125C0360E with and effective date of June 6, 2020.

PARCEL 840-12042-000:
PART OF THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER (SE1/4 SE1/4) OF SECTION 20, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **COMMENCING** AT THE SOUTHWEST CORNER OF THE SAID SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 20 LOCATED AT THE CENTERLINE OF ARKANSAS STATE HIGHWAY NO. 5; RUN THENCE N2°22'23"E, ALONG THE WEST LINE THEREOF, FOR A DISTANCE OF 75.52 FEET TO THE **POINT OF BEGINNING;** THENCE N2°22'23"E, CONTINUING ALONG THE WEST LINE THEREOF, FOR A DISTANCE OF 150.88 FEET TO A POINT; THENCE S87°23'08"E, LEAVING SAID WEST LINE, FOR A DISTANCE OF 167.50 FEET TO A FOUND 5/8" REBAR WITH CAP #568; THENCE S6°38'43"E FOR A DISTANCE OF 70.04 FEET TO A FOUND 1 1/4" PIPE LOCATED ON THE NORTHERLY RIGHT OF WAY OF ARKANSAS STATE HIGHWAY NO. 5; THENCE S87°57'46"W, ALONG SAID NORTHERLY RIGHT OF WAY, FOR A DISTANCE OF 196.00 FEET TO THE **POINT OF BEGINNING,** CONTAINING 0.44 ACRES, MORE OR LESS. THE WEST 20 FEET OF THIS LAND SHALL BE DEDICATED FOR ROADWAY, SEE DEED BOOK 2009 PAGE 025836. SUBJECT TO THE RIGHTS OF WAY OF ARKANSAS STATE HIGHWAY NO. 5 AND HURRICANE LAKE ROAD. SUBJECT TO ANY EASEMENTS OF RECORD.

PARCEL 840-12038-000:
PART OF THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER (SE1/4 SE1/4) OF SECTION 20, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **COMMENCING** AT THE SOUTHWEST CORNER OF THE SAID SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 20 LOCATED AT THE CENTERLINE OF ARKANSAS STATE HIGHWAY NO. 5; RUN THENCE N2°22'23"E, ALONG THE WEST LINE THEREOF, FOR A DISTANCE OF 226.40 FEET TO THE **POINT OF BEGINNING;** THENCE S87°23'08"E, LEAVING SAID WEST LINE, FOR A DISTANCE OF 167.50 FEET TO A FOUND 5/8" REBAR WITH CAP #568; THENCE N0°50'01"E FOR A DISTANCE OF 135.16 FEET TO A FOUND 5/8" REBAR WITH CAP #1399; THENCE N87°25'03"W FOR A DISTANCE OF 163.87 FEET TO A POINT LOCATED ON THE WEST LINE OF SAID SE1/4 SE1/4; THENCE S2°22'23"W, ALONG SAID WEST LINE, FOR A DISTANCE OF 135.00 FEET TO THE **POINT OF BEGINNING,** CONTAINING 0.52 ACRES, MORE OR LESS. THE WEST 20 FEET OF THIS LAND SHALL BE DEDICATED FOR ROADWAY, SEE DEED BOOK 2009 PAGE 026702. SUBJECT TO THE RIGHT OF WAY OF HURRICANE LAKE ROAD. SUBJECT TO ANY EASEMENTS OF RECORD.

PARCEL 840-12037-000:
PART OF THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER (SE1/4 SE1/4) OF SECTION 20, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **COMMENCING** AT THE SOUTHWEST CORNER OF THE SAID SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF SECTION 20 LOCATED AT THE CENTERLINE OF ARKANSAS STATE HIGHWAY NO. 5; RUN THENCE N2°22'23"E, ALONG THE WEST LINE THEREOF, FOR A DISTANCE OF 361.40 FEET TO THE **POINT OF BEGINNING;** THENCE S87°25'03"E, LEAVING SAID WEST LINE, FOR A DISTANCE OF 163.87 FEET TO A FOUND 5/8" REBAR WITH CAP #1399; THENCE N3°36'42"E FOR A DISTANCE OF 135.15 FEET TO A FOUND 5/8" REBAR WITH CAP #1399; THENCE N87°27'39"W FOR A DISTANCE OF 166.79 FEET TO A POINT LOCATED ON THE WEST LINE OF SAID SE1/4 SE1/4; THENCE S2°22'23"W, ALONG SAID WEST LINE, FOR A DISTANCE OF 135.00 FEET TO THE **POINT OF BEGINNING,** CONTAINING 0.52 ACRES, MORE OR LESS. THE WEST 20 FEET OF THIS LAND SHALL BE DEDICATED FOR ROADWAY, SEE DEED BOOK 2009 PAGE 029839. SUBJECT TO THE RIGHT OF WAY OF HURRICANE LAKE ROAD. SUBJECT TO ANY EASEMENTS OF RECORD.

TOTAL TRACT DESCRIPTION

Part of the Southeast Quarter of the Southeast Quarter (SE1/4 SE1/4) of Section 20, Township 1 South, Range 14 West, Saline County, Arkansas, being more particularly described as follows:

Commencing at the Southwest corner of said Southeast Quarter of the Southeast Quarter of Section 20, located at the centerline of Arkansas State Highway No. 5; thence along the west line thereof North 02 degrees 25 minutes 38 seconds East, 75.52 feet (per record) to the northern right-of-way line of said state highway; thence along said right-of-way line North 68 degrees 01 minutes 01 seconds East, 21.96 feet to the POINT OF BEGINNING of the herein described tract; then departing said right-of-way line North 02 degrees 25 minutes 38 seconds East, 411.75 feet to the north line of a tract of land as conveyed to Wedgeo, LLC with the parcel ID# 840-12037-000, by instrument recorded as Document 2025-002935 of the Saline County records,; thence along the north line thereof, South 87 degrees 24 minutes 23 seconds East, 146.79 feet to a found Iron Rod located at the northeast corner of said tract; thence South 03 degrees 39 minutes 57 seconds West, 135.15 feet to the a found Iron Rod; thence South 00 degrees 53 minutes 17 seconds West, 135.16 feet to a found Iron Rod; thence South 06 degrees 35 minutes 28 seconds East, 70.04 feet to the northern line of above said Arkansas State Highway No. 5; thence along said right-of-way line, South 68 degrees 01 minute 01 second West, 174.03 feet to the POINT OF BEGINNING.

Containing 55,633 square feet or 1.277 acres, more or less.

FLOOD NOTE

SUBJECT PROPERTY LIES WITHIN FLOOD ZONE X (AREA OF MINIMAL FLOOD HAZARD) ACCORDING TO THE NATIONAL FLOOD INSURANCE RATE MAP NUMBER 05125C0360E WITH AN EFFECTIVE DATE OF 06/05/2020.

SURVEYOR'S CERTIFICATION

This is to certify that Stock & Associates Consulting Engineers, Inc. have, during June, 2025 by order or the use of the Good Day Farm executed a Property Boundary Survey and a Subdivision Plat of tracts of land located in the Southeast Quarter of the Southeast Quarter (SE1/4 SE1/4) of Section 20, Township 1 South, Range 14 West, located in City of Bryant, Saline County, Arkansas, and that the results of said survey and Subdivision are shown hereon. We further certify that said survey meets or exceeds the current minimum standards for Property Boundary Surveys for "Class Urban Property" in the State of Arkansas.

STOCK & ASSOCIATES CONSULTING ENGINEERS, INC.
4355

By: _____
Randall Scott Rosson, Arkansas P.L.S. No. 1663

PREPARED FOR:
GOOD DAY FARM
C/O REGAN ETHERIDGE SENIOR PROJECT MANAGER-STORE DEVELOPMENT, DESIGN & CONSTRUCTION
425 W. CAPITOL AVE.,
LITTLE ROCK, AR 72201

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH. (636) 530-9100 FAX (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:
GOOD DAY FARM - BRYANT
3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS REGISTERED PROFESSIONAL ENGINEER GEORGE M. STOCK No. 6105 07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO.: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
SUBDIVISION PLAT


SHEET NO.:
C3.2

Plotted by: EVANSTROUDT\CharlesHenry1777 Plotted on: 07/16/25 - 10:16 - 125pm XLSTYLES: Full.stb

SWPPP LEGEND

- CONSTRUCTION ENTRANCE
- WASHDOWN STATION
- SF — SILTATION FENCE
- DISTURBED LIMITS

TOTAL AREA DISTURBED: 1.41 Ac.±



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH. (636) 530-9100 FAX (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS GEORGE M. STOCK 25116 REGISTERED PROFESSIONAL ENGINEER
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
PRE-CONSTRUCTION SWPPP


SHEET NO.:
C4.0

DRAWING FILE: C:\Users\lcwilson\Desktop\2025 Projects\2025 Projects\2025-7775 Good Day FARM - BRYANT\PLOTTED\C4.0 PRE-CONSTRUCTION SWPPP.dwg, 7/16/2025 11:47:29 AM, lcwilson, 1:1 Plot to PLOTTED BY: lcwilson

TOTAL AREA DISTURBED:
1.41 Ac.±

SWPPP LEGEND

- IP — INLET PROTECTION
- OP — OUTLET PROTECTION
- CONSTRUCTION ENTRANCE
- WASHDOWN STATION
- CONCRETE WASHOUT AREA
- SF — SILTATION FENCE
- DISTURBED LIMITS
- ROCK CHECK DAM
- PORTABLE RESTROOM
- DRAINAGE ARROW



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS REGISTERED PROFESSIONAL ENGINEER GEORGE M. STOCK No. 25116
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS


DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
CONSTRUCTION SWPPP

SHEET NO.:
C4.1

SWPPP LEGEND

- OUTLET PROTECTION
- LAWN SEED AND EROSION CONTROL AREAS
- DRAINAGE ARROW



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:

STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
POST-CONSTRUCTION SWPPP

SHEET NO.:
C4.2


Attached to: S:\2025\7775\CDD\Plans\Drawings\7775 Site.dwg, LAYOUT: C4.2 Post SWPPP, PLOTTED: Jul 16, 2025 - 1:56pm, PLOTTED BY: Lisa Weber

STORM WATER POLLUTION PREVENTION PLAN NOTES

1. IT IS THE RESPONSIBILITY OF ALL CONTRACTORS TO CONTACT UTILITY COMPANIES AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION ON OR RELATING TO THIS PROJECT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE OR ARRANGE FOR THE RELOCATION OF ANY UTILITIES AFFECTED BY THE PROJECT CONSTRUCTION.
2. CONTRACTOR SHALL TAKE ALL MEASURES NECESSARY TO PROTECT THE ADJOINING PROPERTIES FROM THE DELETERIOUS EFFECTS OF EROSION UNTIL PROJECT COMPLETION AND ACCEPTANCE.
3. SOIL SHALL BE COMPACTED IN ACCORDANCE WITH THE CITY OF BRYANT AND SALINE COUNTY STANDARD SPECIFICATIONS FOR STREET CONSTRUCTION.
4. 6" OF TOPSOIL SHALL BE STRIPPED UNDER ALL FILL AREAS.
5. FIBER ROLLS AND WATTLES SHALL BE USED AS INLET PROTECTION FOR INLETS WITHIN PARKING LOTS AND ALONG ROADWAYS.
6. EROSION AND SILTATION CONTROL SHALL BE INSTALLED AND BE MAINTAINED THROUGHOUT THE PROJECT UNTIL/ACCEPTANCE OF THE WORK BY THE VA AND ADEQUATE VEGETATIVE GROWTH INSURES NO FURTHER EROSION OF THE SOIL.
7. AT LEAST ONCE EVERY WEEK AND AFTER EVERY RAINFALL EVENT OF 0.25 INCHES OR MORE, EROSION AND SILTATION CONTROL DEVICES SHALL BE INSPECTED BY THE CONTRACTOR FOR DAMAGE AND AMOUNT OF SEDIMENTATION ACCUMULATED AND CORRECTIVE ACTIONS TAKEN.
8. TEMPORARY SILTATION CONTROL MEASURES (STRUCTURAL) SHALL BE MAINTAINED UNTIL VEGETATIVE COVER IS ESTABLISHED AT A SUFFICIENT DENSITY TO PROVIDE EROSION CONTROL ON THE SITE.
9. WHERE NATURAL VEGETATION IS REMOVED DURING GRADING, VEGETATION SHALL BE REESTABLISHED IN SUCH A DENSITY AS TO PREVENT EROSION.
10. WHEN GRADING OPERATIONS ARE COMPLETED OR SUSPENDED FOR MORE THAN 5 DAYS IN ANY AREA, THE DISTURBED AREA SHALL BE SEEDED OR OTHERWISE STABILIZED TO SIGNIFICANTLY REDUCE THE ERODING OF THE SOIL. PROTECTIVE MEASURES MAY INCLUDE A COMBINATION OF SEEDING, SODDING, MULCHING OR OTHER SUITABLE MEANS TO PROTECT THE GROUND SURFACE FROM EROSION.
11. IF CUT AND FILL OPERATIONS OCCUR DURING A SEASON NOT FAVORABLE FOR IMMEDIATE ESTABLISHMENT OF PERMANENT GROUND COVER, A FAST GERMINATING ANNUAL SUCH AS RYE GRASSES SHALL BE UTILIZED TO RETARD EROSION, IF EROSION CONTROL DEVICES HAVE NOT BEEN ESTABLISHED.
12. ALL FINISHED GRADES (AREAS NOT TO BE DISTURBED BY FUTURE IMPROVEMENT) IN EXCESS OF 20% SLOPES (5:1) SHALL BE MULCHED AND TACKED AT THE RATE OF 100 POUNDS PER 1,000 SQUARE FEET WHEN SEEDED.
13. STORM WATER PIPES, OUTLETS AND CHANNELS SHALL BE PROTECTED BY SILT BARRIERS AND KEPT FREE OF WASTE AND SILT AT ALL TIMES PRIOR TO FINAL SURFACE STABILIZATION AND/OR PAVING.
14. SEDIMENT BUILD-UP REMOVED DURING ROUTINE BMP MAINTENANCE SHALL REMAIN ON-SITE. SEDIMENT SHALL BE RELOCATED TO WITHIN THE STOCKPILE AREA OR TO A LEVEL AREA (1% MAX.) ABSENT OF CONCENTRATED FLOWS. LEVEL OUT SEDIMENT AND ALLOW TO DRY.
15. THE SILTATION CONTROL NOTES, IMPLEMENTATION SCHEDULE, AND SILTATION CONTROL DETAILS, ALONG WITH THE SILTATION CONTROL PLANS INCLUDED ON SHEET C4.1 CONSTITUTE THE STORMWATER POLLUTION PREVENTION PLAN AND IS INFORMATIONAL IN NATURE. THE CONTRACTOR IS REQUIRED TO CREATE A PROJECT SPECIFIC EROSION CONTROL PLAN AND UPDATE IT THROUGHOUT CONSTRUCTION.

SILTATION IMPLEMENTATION SCHEDULE

1. INSTALL PERIMETER SILTATION CONTROL AND CONSTRUCTION ENTRANCE.
2. DEMO EXISTING PARKING LOT AND BEGIN PLACING AGGREGATE BASE IN PAVEMENT AREAS ONCE AREA HAS REACHED FINAL GRADE TO PREVENT EROSION.
3. PLACE SILT FENCE AROUND EACH STORM SEWER INLET AS IT IS CONSTRUCTED.
4. IMMEDIATELY SOD GRADED AREAS UPON REACHING FINAL GRADE THAT ARE TO BE PERMANENTLY TURFED.



CONSTRUCTION ENTRANCE/WASHDOWN/PARKING AREA - PROFILE

N.T.S.
(SEE SHEET C4.0 FOR LOCATION)

CONSTRUCTION ENTRANCE:

INSTALLATION/CONSTRUCTION PROCEDURES:

1. GRADE AND COMPACT AREA OF CONSTRUCTION ENTRANCE
2. INSTALL CULVERT UNDER ENTRANCE IF NEEDED TO MAINTAIN POSITIVE DRAINAGE
3. PLACE FABRIC AND COVER WITH AGGREGATE, FORMING DIVERSION ACROSS ENTRANCE IF NEEDED TO DIRECT RUNOFF AWAY FROM ROADWAY
4. SEE WASHDOWN STATION BMP FOR ADDITIONAL STEPS

OPERATIONS & MAINTENANCE PROCEDURES:

1. IMMEDIATELY REMOVE ANY MUD OR DEBRIS TRACKED ONTO PAVED SURFACES
2. REMOVE SEDIMENT AND CLODS OF DIRT FROM CONSTRUCTION ENTRANCE CONTINUOUSLY
3. REPLACE ROCK IF NECESSARY TO MAINTAIN CLEAN SURFACE
4. REPAIR SETTLED AREAS

SITE CONDITIONS FOR REMOVAL:

REMOVE WHEN VEHICLES AND EQUIPMENT WILL NO LONGER ACCESS UNPAVED AREAS

WASHDOWN:
INSTALLATION/CONSTRUCTION PROCEDURES:


1. GRADE AND COMPACT AREA FOR DRAINAGE UNDER WASHDOWN PAD
2. INSTALL STEEL-RIBBED PLATE ON FRAME OR OTHER SUPPORT TO ALLOW A 2" DRAIN SPACE
3. GRADE AND VEGETATE DOWNSTREAM BMP (V-DITCH SHOWN ON DETAIL)
4. INSTALL WATER SUPPLY AND HOSE
5. POST SIGN IN ADVANCE OF STATION INDICATING THAT ALL EXITING VEHICLES AND EQUIPMENT MUST USE STATION PRIOR TO EXITING SITE


OPERATIONS & MAINTENANCE PROCEDURES:

1. REMOVE SEDIMENT DAILY
2. REPAIR SETTLED AREAS
3. REPLACE ROCK IF NECESSARY TO MAINTAIN CLEAN SURFACE

SITE CONDITIONS FOR REMOVAL:


REMOVE WHEN VEHICLES AND EQUIPMENT WILL NO LONGER ACCESS UNPAVED AREAS.





WASHDOWN


N.T.S.
(SEE SHEET C4.0 FOR LOCATION)




NOTE:
FIBER ROLLS OR WATTLES MAY BE USED AT INLETS IN LIEU OF SILT FENCE AS CONTRACTORS OPTION.


INLET PROTECTION

N.T.S.
(SEE SHEET C4.0 FOR LOCATIONS)









NOTE: IF FABRIC IS INSTALLED BY EQUIPMENT DESIGNED TO SLICE INTO THE GROUND, THE TRENCH IS NOT NEEDED

SILT FENCE

N.T.S.
(SEE SHEET C4.0 FOR LOCATION)

SILT FENCE:
INSTALLATION/CONSTRUCTION PROCEDURES:

1. DRIVE POST FOR FENCE LINE.
2. DIG TRENCH TO REQUIRED DIMENSIONS IN FRONT OF POSTS FOR FABRIC BURIAL.
3. ATTACH WIRE MESH TO POSTS.
4. ATTACH FABRIC TO POSTS, ALLOWING REQUIRED LENGTH BELOW GROUND LEVEL TO RUN FABRIC ALONG BOTTOM OF TRENCH.
5. BACKFILL AND COMPACT SOIL IN TRENCH TO PROTECT AND ANCHOR FABRIC.


ALTERNATE CONSTRUCTION - INSTALL FENCE BY SLICING IT INTO GROUND WITH SPECIALIZED EQUIPMENT.
INSTALL POSTS AT REDUCED SPACING INDICATED ON DETAIL.

O&M PROCEDURES:

1. INSPECT ONCE A WEEK AND AFTER EVERY STORM.
2. REMOVE SEDIMENT BUILDUP DEEPER THAN 1/2 THE FENCE HEIGHT OR 12" DEPTH, WHICHEVER IS LESS.
3. REPLACE TORN OR CLOGGED FABRIC. REPAIR LOOSE FABRIC.
4. REPAIR UNSTABLE OR BROKEN POSTS.
5. STABILIZE ANY AREAS SUSCEPTIBLE TO UNDERMINING.
6. EXTEND FENCE OR ADD ADDITIONAL ROW(S) FENCE IF NECESSARY TO PROVIDE ADEQUATE PROTECTION.
7. SILT THAT HAS MIGRATED PAST SILT FENCE INTO UNWANTED AREAS OF THE FACILITY OR OFFSITE THROUGH TORN OR LOOSE FABRIC SHALL BE REMOVED AND THE AFFECTED AREAS SHALL BE RESTORED IMMEDIATELY AT THE COST OF THE CONTRACTOR.

SITE CONDITIONS FOR REMOVAL:

AFTER PERMANENT VEGETATION OF SLOPE IS ESTABLISHED. REMOVE FENCE, REGRADE TRENCH AREA AND VEGETATE.



NOTE:
1) DO NOT SCALE DRAWING, FOLLOW DIMENSIONS.
2) ROW SPACING FOR SLOPE INSTALLATIONS SHOULD BE DETERMINED BY SITE CONDITIONS SUCH AS SLOPE GRADIENT AND SOIL TYPE.
3) NETTING, FILTER SOCK OR OUTER COVER OF ROLLS MUST BE CONSTRUCTED OF PHOTODEGRADABLE OR BIODEGRADABLE MATERIAL.
4) FIBER ROLLS AND WATTLES SHALL CONTAIN STRAW, FLAX, COCONUT FIBER (COIR), RICE STRAW OR ASPEN EXCELSIOR, IN A TIGHT TUBULAR ROLL, SPECIFICALLY DESIGNED FOR REMOVAL OF SOLIDS FROM STORM WATER RUNOFF. FILL MATERIAL MUST BE BIODEGRADABLE AND CONTAIN NO CHEMICAL ADDITIVES.
6) FIBER ROLLS OR WATTLES MAY BE WEIGHTED FOR USE AROUND STREET INLETS (INTERNAL ROLL WEIGHT OR PLACING A WEIGHT, SUCH AS A CONCRETE BLOCK, ON THE DOWNSTREAM SIDE OF THE ROLL.
7) FOLLOW THE ROLL MANUFACTURERS INSTRUCTIONS AND RECOMMENDATIONS FOR THE SIZING, INSTALLATION AND MAINTENANCE OF ALL FIBER ROLLS OR WATTLES.

FIBER ROLLS AND WATTLES

(SEE SHEET C4.0 FOR LOCATION)

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
GEORGE M. STOCK
No. 9916
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	


SHEET TITLE:
STORM WATER POLLUTION PREVENTION DETAILS

SHEET NO.:
C4.3

DRAWING FILE: E:\DRAWINGS\2025\7775\Submittal\Permit\7775sw.dwg, LAYOUT: C4.3 (ARCH D Sheet), PLOTTED: Jul 16, 2025 - 1:56pm, PLOTTED BY: Lucas Wood

HALF-STREET LEGEND

HALF-STREET PAVEMENT LIMITS



GRAPHIC SCALE

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
SITE GRADING PLAN

SHEET NO.:
C5.0

Plotted by: G:\DRAWINGS\2025\7775\Drawings\7775 Site.dwg, 07/16/25 10:54:44 AM, Stock Site Grading Plan, 7775 SITE, 24 x 36, 1:30pm




ENTRANCE PLAN VIEW
SCALE 1"=10'

GRAPHIC SCALE

10 0 5 10 20 40

(IN FEET)
1 inch = 10 ft.



ENTRANCE PROFILE VIEW
HORIZONTAL SCALE 1"=10'
VERTICAL SCALE 1"=3.33'

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stocksassoc.com
Web: www.stocksassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:

1	07/15/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
ENTRANCE
WARPING DETAIL

SHEET NO.:
C5.1

Drawing File: K:\Work\7700s\7775\Civil\Plotting\7775Base.dwg LAYOUT: C5.1 Entrance Warping 7/17/2025 @ 8:36 AM by LUCAS.WILLIAMS (Opt Out Preference) Xrefs Used: 7775Base.dwg

UTILITY CONTACTS

SUMMIT UTILITIES (GAS) – SHANE GIBBONS, (501) 581-9428

BRYANT PUBLIC WORKS – BRYCE RIMMER, (501) 943-0458

WATER CONTACT – VERNON WILLIAMS, (501) 452-2771

SALEM WATER USERS – (501) 772-2212


GENERAL NOTE

1) ALL EXISTING UTILITIES TO BE PROTECTED, INCLUDING BUT NOT LIMITED TO THE FORCE MAIN

2) ALL EXISTING UTILITIES TO BE VERIFIED BY CONTRACTOR TO AVOID ANY CONFLICTS

HALF-STREET LEGEND

HALF-STREET PAVEMENT LIMITS



LINE TYPE LEGEND

- EX CONT MJR
- EX CONT MNR
- TREE LINE
- FEMA ELEV
- FEMA LIMIT
- PAVEMENT
- WALL
- GUARD RAIL
- CHAINLINK/WIRE FENCE
- WOOD/VINYL FENCE
- GAS
- UNDER GROUND ELEC
- OVERHEAD ELEC
- TELEPHONE LINE
- FIBER OPTIC LINE
- WATERLINE
- FLOODWAY
- SLOPE/LEVEE

LEGEND

- BENCH MARK
- FOUND IRON ROD
- FOUND IRON PIPE
- RIGHT OF WAY MARKER
- UTILITY POLE
- SUPPORT POLE
- UTILITY POLE WITH LIGHT
- LIGHT STANDARD
- ELECTRIC METER
- ELECTRIC MANHOLE
- ELECTRIC PEDESTAL
- ELECTRIC SPLICE BOX
- ELECTRIC BREAKER
- GAS DRIP
- GAS METER
- GAS VALVE
- TELEPHONE MANHOLE
- TELEPHONE PEDESTAL
- TELEPHONE SPLICE BOX
- CABLE TV PEDESTAL
- FIRE HYDRANT
- FIRE DEPARTMENT CONNECTION
- WATER MANHOLE
- WATER METER
- WATER VALVE
- POST INDICATOR VALVE
- CLEAN OUT
- STORM MANHOLE
- GRATED MANHOLE
- STORMWATER INLET
- GRATED STORMWATER INLET
- SANITARY MANHOLE
- TREE
- BUSH
- TRAFFIC SIGNAL
- PARKING METER
- STREET SIGN
- SPRINKLER
- MAIL BOX

ABBREVIATIONS

C.O.	–	CLEANOUT
DB.	–	DEED BOOK
E	–	ELECTRIC
FL	–	FLOWLINE
FT	–	FEET
FND.	–	FOUND
G	–	GAS
M.H.	–	MANHOLE
N/F	–	NOW OR FORMERLY
PB.	–	PLAT BOOK
PG.	–	PAGE
P.V.C.	–	POLYVINYL CHLORIDE PIPE
R.B.	–	RADIAL BEARING
R.C.P.	–	REINFORCED CONCRETE PIPE
SQ.	–	SQUARE
T	–	TELEPHONE CABLE
V.C.P.	–	VETRIFIED CLAY PIPE
W	–	WATER
(86'W)	–	RIGHT-OF-WAY WIDTH

GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
SITE UTILITY PLAN

SHEET NO.:
C6.0

PARKING CALCS.

MINIMUM PARKING FOR C-2 DISTRICT:
1.0 SPACES PER 300 SF
(1,960 SF/300 SF) * 1.0 SPACE = 6.53 OR A MINIMUM OF 7 SPACES


PARKING SPACES PROVIDED = 36 SPACES (2 ADA)

HALF-STREET LEGEND

HALF-STREET PAVEMENT LIMITS

PAVEMENT LEGEND

- LIGHT DUTY ASPHALT – PARKING AREAS
- HEAVY DUTY ASPHALT – DRIVE AISLES
- HEAVY DUTY CONCRETE – ENTRANCE
- CONCRETE SIDEWALK PAVING



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
GEOMETRIC PLAN

SHEET NO.:
C7.0

Plotted by: G:\DATA\1775\SDP\1775SitePlan.dwg, LAYOUT C7.0 Color Plot, 7/16/2025 - 2:31 PM, PLOTTED BY: Lance Wood



LINETYPE LEGEND

EXISTING GRADE.....

PROPOSED GRADE...

HYDRAULIC GRADE...

PROPOSED PAVEMENT....

GRANULAR BACKFILL.....

COMPACTED FILL.....

STORM SEWER PROFILES

HORIZONTAL SCALE: 1"=30'
VERTICAL SCALE: 1"=10'

Project name:	*GDF - BRYANT*	Calculated By:	*L.C.W.*	100-year Pipe Hydraulics																								
Project number:	*2024-7775*	Checked By:	*G.M.S.*	*Bend Coefficients :*																								
Project Location:	*BRYANT, AR*	Date:	*5/21/2025*	5° = 0.06	20° = 0.24	35° = 0.4	50° = 0.50	65° = 0.57	80° = 0.65																			
				10° = 0.11	25° = 0.30	40° = 0.43	55° = 0.52	70° = 0.60	85° = 0.67																			
				15° = 0.18	30° = 0.35	45° = 0.47	60° = 0.55	75° = 0.62	90° = 0.70																			

	LINE		FLOW LINE ELEVATIONS													HEAD LOSS					Hydraulic Elevations									
Structure Number	Upper structure	Lower structure	Upper structure	Lower structure	Length (ft)	Flowline Grade ft/ft	Pipe Size (in.)	Full Flow Cap. (cfs)	Total (Q) (cfs)	Mean Full Flow Vel.(V) (ft/s)	Bend Coef.	Curve Coef.	Velocity Head (Vh) (ft)	QVh (ft³/s)	Pipe Coef. (n)	Hj (ft)	Junction (ft)	Bend (ft)	Curve (ft)	Total H_{BT}	Upper F.L + Dia.	Lower H.E. +Hj	Lower H.E.	Structure Upper H.E. + H_{BT}	Top/Sill Structure Elevation	Free Board	Structure Number	Remarks	Velocity Mannings Formula (ft/s)
2.1	2.1	2.0	402.71	402.42	38.78	0.0075	18	9.12	6.51	3.68	0.00	0.00	0.21	1.37	0.013	0.15	0.00	0.00	0.00	0.00	404.21	404.07	403.92	404.21	408.00	3.79	2.1	Outfall Structure	5.16
2.0	2.0		402.42																		Top of Pipe =			403.92			2.0	FES	
1.4	1.4	1.1	406.63	405.58	34.64	0.0100	12	3.57	0.74	0.94	0.00	0.00	0.01	0.01	0.013	0.01	0.00	0.00	0.00	0.00	407.63	407.29	407.27	407.63	409.83	2.20	1.4	Curb Inlet	4.55
1.1	1.1		405.58																		From Below =			407.27			1.1	Grate Inlet	
1.3	1.3	1.2	407.16	406.58	57.72	0.0100	12	3.57	0.44	0.56	0.00	0.00	0.00	0.00	0.013	0.01	0.01	0.00	0.00	0.01	408.16	408.06	408.05	408.17	410.37	2.20	1.3	Curb Inlet	4.55
1.2	1.2	1.1	406.58	405.58	100.12	0.0100	12	3.57	2.47	3.14	0.60	0.00	0.15	0.38	0.013	0.48	0.20	0.09	0.00	0.30	407.58	407.75	407.27	408.05	409.69	1.64	1.2	Grate Inlet	4.55
1.1	1.1	1.0	405.58	405.00	57.93	0.0100	15	6.48	5.63	4.59	0.30	0.00	0.33	1.84	0.013	0.44	0.35	0.10	0.00	0.44	406.83	406.69	406.25	407.27	408.22	0.95	1.1	Grate Inlet	5.28
1.0	1.0		405.00																		Top of Pipe =			406.25			1.0	FES	

	MEAN FULL FLOW VELOCITY:	$V = Q_{ACT}/A_{PIPE}$	JUNCTION LOSSES (JUNC.) = [$Q_{out}Vh_{out}$ - Sum ($Q_{in}V_{in}$)]x1.33/[Q_{out}]
	FRICTION LOSS (H_f) :	$Hf = 2.87\ n^2\ (LV^2/d^{1.33})$	BEND LOSES (BEND) = (V^2) * ANGLE COEFFICIENT
	VELOCITY HEAD :	$V_h = V^2/2g$	CURVE LOSS=V_h*CURVE COEFFICIENT
Note(s):			


Note:
1. IF MORE THAN ONE INCOMING LINE, CALC. EACH BEND LOSS AND ADD TOGETHER.
2. NO STRUCTURE LOSES TO BE CALCULATED AT A DROP
3. IF $QV_{h(in)} > QV_{h(out)}$, NO JUNCTION LOSES TO BE CALCULATED.

100-YEAR PIPE HYDRAULICS

OUTFALL STRUCTURE NOTES:
1) CONTROL STRUCTURE TO BE REINFORCED CONCRETE: WALL THICKNESS IS 8" w/ TWO (2) ROWS OF #4 STEEL.

2) OUTFALL STRUCTURE SHALL BE PRE-CAST OR CAST-IN-PLACE.

3) CONTRACTOR SHALL PROVIDE A HIGH LEVEL OF CARE WHEN PLACING & COMPACTING "CLAY" SOILS AROUND OUTFALL STRUCTURE & PIPING. THE GEOTECHNICAL ENGINEER SHALL BE PRESENT TO CONFIRM THE "LEVEL OF PLACEMENT"



OUTFALL STRUCTURE #2.1

(N.T.S.)

UTILITY CONFLICT NOTE:
CONTRACTOR SHALL NOTIFY THIS ENGINEER IMMEDIATELY OF ANY POTENTIAL UNDERGROUND UTILITY CONFLICT AT TIME OF EXCAVATION.

ALL DETAILS SHOWN ON THESE PLANS ARE FOR THE CONVENIENCE OF THE CONTRACTOR. THE DETAILS ARE TO BE VERIFIED PER BRYANT'S STANDARD CONSTRUCTION SPECIFICATIONS ALL METHODS, MEANS AND MATERIALS SHALL CONFORM TO BRYANT'S CURRENT STANDARD CONSTRUCTION SPECIFICATIONS.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH. (636) 530-9100 FAX (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
STORM SEWER PROFILES

SHEET NO.:
C8.0

G:\Projects\2025\2025-7775\Civil\Preliminary\7775 Base.dwg, 5/21/2025 2:54:59 PM, Chris Phillips, DWG To PDF.pc3, ANSI B (11.00 x 17.00 Inches), By Chris Phillips



LIGHT DUTY ASHPALT
(CAR PARKING)
(N.T.S.)


HEAVY DUTY ASHPALT
(DRIVE LANES)
(N.T.S.)

HEAVY DUTY CONCRETE
(DUMPSTER PADS)
(N.T.S.)


PAVEMENT DETAILS ARE SUBJECT TO GEOTECHNICAL ENGINEER, OWNER AND CONTRACTOR VERIFICATION AND APPROVAL PRIOR TO CONSTRUCTION

PAVEMENT NOTES:


1. ALL MEANS AND METHODS OF CONCRETE AND ASPHALT CONCRETE SHALL BE IN ACCORDANCE WITH THE CITY OF BRYANT STANDARD CONSTRUCTION SPECIFICATIONS AND ACI 330R-01. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN CURRENT EDITIONS PRIOR TO CONSTRUCTION.
2. ALL PAVEMENT SECTIONS AND DETAILS ARE SUBJECT TO GEOTECHNICAL ENGINEER AND OWNER REVIEW AND APPROVAL PRIOR TO SUBMISSION OF SHOP DRAWINGS.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO APPLY THE RECOMMENDATIONS SUPPLIED IN THE GEOTECHNICAL ENGINEERING REPORT.
4. ALL EXPOSED CONCRETE EDGES TO BE CHAMFERED.
5. ALL CONCRETE SHALL BE 4,000 PSI, 28-DAY STRENGTH, AIR ENTRAINMENT IN THE RANGE OF 6% TO 8% MAXIMUM SLUMP OF 4 INCH +/- 1 INCH IS ACCEPTABLE.
6. PAVEMENT SECTIONS WITHIN THE PUBLIC RIGHT-OF-WAY TO BE REVIEWED AND APPROVED BY THE CITY OF KANSAS CITY.
7. IT IS THE CONTRACTORS RESPONSIBILITY TO HIRE A THIRD PARTY TESTING AGENCY FOR THE PLACEMENT AND SUBGRADE TESTING OF THE PROPOSED PAVEMENT.




SAWED CONTROL JOINT




TRANSVERSE CONSTRUCTION JOINT




LONGITUDINAL JOINT




TRANSITION BETWEEN NEW & EXISTING PAVEMENT



ISOLATION JOINT



EXPANSION JOINT




ALTERNATE EXPANSION JOINT


STAKING PIN

DOWEL BARS – EPOXY COATED		
PAVEMENT THICKNESS	BAR SIZE DIAMETER	LENGTH
7 INCHES	1 INCH	18 INCHES
8 INCHES	1 INCH	18 INCHES
9 INCHES	1-1/4 INCHES	18 INCHES
10 INCHES	1-1/4 INCHES	18 INCHES
11 INCHES or <	1-1/2 INCHES	18 INCHES

JOINT DETAILS
(N.T.S.)




ISOLATION/EXPANSION JOINT DETAIL



CONSTRUCTION, CONTROL AND LONGITUDINAL JOINT DETAIL


JOINT NOTES

1. CONSTRUCTION JOINTS ARE REQUIRED BETWEEN ALL POURS SEPARATED BY MORE THAN 90 MINUTES TIME.
2. FIFTEEN FOOT (15) MAXIMUM SPACING BETWEEN CONTROL JOINTS. PAVING CONTRACTOR SHALL FOLLOW "GUIDE FOR DESIGN AND CONSTRUCTION OF CONCRETE PARKING LOTS" AS REPORTED BY ACI COMMITTEE 330.
3. FILL JOINTS TO WITHIN 1/8" OF SURFACE WITH JOINT SEALER.
4. ISOLATION JOINTS REQUIRED AROUND ALL UTILITY STRUCTURES THAT ARE LOCATED WITHIN THE LIMITS OF CONCRETE PAVEMENT.
5. EXPANSION JOINT MAY BE REQUIRED DEPENDING ON COLD WEATHER, i.e. IF PAVING OCCURS WHEN AMBIENT TEMPERATURES ARE BELOW 40 DEGREES



SIDEWALK DETAIL
(N.T.S.)
(NOT FOR USE IN WITHIN R/W)

NOTE:
EXPANSION JOINT MATERIAL SHALL BE INSTALLED IN THE WALK FOR ITS FULL WIDTH AND DEPTH AT INTERVALS OF APPROX. 20', CONTROL JOINTS AT INTERVALS OF 5' CENTERS.



NOTES: A CURB RAMP(S) MUST BE PROVIDED ALONG AN ACCESSIBLE PATH FROM THE PARKING LOT TO CURBED SIDEWALK.

A CURB RAMP(S) MUST ALSO BE PROVIDED IN THE PARKING LOT AT ALL INTERMEDIATE AND PERIMETER CURBS ALONG THE ACCESSIBLE ROUTE CONNECTING TO PUBLIC SIDEWALKS.

A RAMP IS ANY SLOPE GREATER THAN 1:20 (5%) AND SHALL HAVE A MAXIMUM SLOPE OF 1:12 (8.33%). THE MAXIMUM SLOPE IS 1" OF RISE PER FOOT OF DISTANCE TRAVELED. ALL SLOPED AREAS OF THE RAMP ARE TO HAVE AN INTEGRAL RED COLOR.


THE CLEAR WIDTH OF ANY RAMP IS A MINIMUM OF 36".

CURB RAMPS HAVE A MAXIMUM RISE OF 6" AND DO NOT REQUIRE HANDRAILS.

ANY RAMP WITH GREATER THAN A 6" RISE SHALL HAVE HANDRAILS ON BOTH SIDES AND SHALL HAVE EDGE PROTECTION WITH SIDES. EDGE PROTECTION CONSISTS OF CURBS, WALLS, RAILINGS, OR PROJECTING SURFACES THAT PREVENT PEOPLE FROM SLIPPING OFF THE RAMP.

CURB RAMPS MUST HAVE A DETECTABLE WARNING FEATURE EXTENDING THE FULL WIDTH AND DEPTH OF THE RAMP INCLUDING ANY FLARES. THE DETECTABLE WARNING MUST CONTAIN RAISED, TRUNCATED DOMES WITH A DIAMETER OF NOMINAL 0.9 INCHES, A HEIGHT OF NOMINAL 0.2 INCHES AND A CENTER-TO CENTER SPACING OF NOMINAL 2.35 INCHES. THE TEXTURE OF THE DETECTABLE WARNING FEATURE MUST CONTRAST WITH THE SURROUNDING SURFACES (EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT). SEE ABOVE.

HANDICAP RAMP DETAILS



NOTE: EXPANSION JOINT MATERIAL SHALL BE INSTALLED IN THE WALK FOR ITS FULL WIDTH AND DEPTH AT INTERVALS OF APPROX. 50', CONTROL JOINTS AT INTERVALS OF 1.5' TIMES ITS WIDTH.


OPTIONAL INTEGRAL SIDEWALK/CURB DETAIL
(n.t.s.)

PAVEMENT MARKING PAINT:
1. LATEX, WATERBORNE EMULSION, LEAD AND CHROMATE FREE. READY MIXED, COMPLYING WITH FS TT-P-1952, WITH DRYING TIME OF LESS THAN 3 MINUTES.
2. WHITE FOR TYPICAL PARKING STALLS, BLUE FOR HANDICAP STALLS, VERIFY WITH OWNER.




PAINT GRAPHIC ON PAVING @ H.D.C.P. STALLS

PAINTED HANDICAP SYMBOL
(N.T.S.)




TYPICAL PARKING STALLS
(N.T.S.)




NOTE:
2,500 psi, PRE-CAST, AIR ENTRAINED CONCRETE, 6"H x 9"W x 7'L, CENTERED ON PARKING STALL, PROVIDE CHAMFERED CORNERS AND DRAINAGE SLOTS ON THE UNDERSIDE. PROVIDE MFG. STANDARD CONCRETE ANCHORS, OR #4 STEEL REINFORCING ROD STAKES OF SUFFICIENT LENGTH TO PENETRATE THE ROCK BASE PLUS 4", TWO PER WHEEL STOP.

PRE-CAST PARKING BUMPER
(N.T.S.)

NOTES: 1. PROVIDE ONE SIGN PER ACCESSIBLE SPACE.
2. PAINT BACK OF SIGNS TO MATCH POST.




ACCESSIBLE PARKING SIGN
(N.T.S.)




NOTE (R7-8 SIGN): THIS IS A STANDARD SIGN AND MAY BE ORDERED FROM ANY TRAFFIC SIGN SUPPLIER BY NUMBER. THE SIGN MUST BE SUPPLEMENTED WITH A "LIFT VAN ACCESSIBLE ONLY" SIGN AS APPLICABLE AND/OR AMOUNT OF THE FINE FOR ILLEGALLY PARKING IN THE RESERVED SPACE(S) A MUNICIPALITY MAY IMPOSE. CONFIRM WITH LOCAL REGULATIONS.


ACCESSIBLE SIGN DETAIL
(N.T.S.)



LIGHT POLE BASE
(n.t.s.)




POINT DISCHARGE STONE
(N.T.S.)



CONCRETE CURB DETAIL
(N.T.S.)
(NOT FOR USE IN ST. LOUIS COUNTY R/W)


NOTE:
1. ALL CONCRETE SHALL BE MIN. FC. = 4000 PSI. (UNLESS OTHERWISE NOTED)
2. ANY UNSUITABLE SOIL (AS DETERMINED BY SOILS ENGINEER) BELOW STRUCTURE SHALL BE REMOVED AND REPLACED WITH SELECT EARTHEN MATERIAL COMPACTED IN PLACE WITH VIBRATORY TAMPER.
3. ALL EXPOSED CONCRETE EDGES TO HAVE 3/4" CHAMFER.



CONCRETE CURB TAPER DETAIL
(N.T.S.)
(FOR USE WHERE CURBED ISLANDS MEET FLUSH CURB)

.67 S.F. MIN OF EARTHEN CONTACT PER BLOCK ON 90° TO 45° BEND

.36 S.F. MIN OF EARTHEN CONTACT PER BLOCK ON 45° BEND OR LESS




EQUATION USED FOR T-BLOCK CALCULATIONS
T=2(PAΦSIN Φ/2) x f.o.s. of 1.5
ASSUMED PRESSURE OF 150 PSI AND
AND SOIL BEARING CAPACITY OF 1500 PSF

A = CONTACT BEARING AREA OF BLOCK WITH EARTH IN SQUARE FEET


PIPE DIA. IN.	PLUG	45° WYE	TEE CONNECTION	UP TO 22.5°	UP TO 45°	UP TO 90°
	A (SQ. FT.)	A (SQ.FT.)	A (SQ.FT.)	A (SQ.FT.)	A (SQ.FT.)	A (SQ.FT.)
4" and smaller	0.5	1.4	2.6	1.8	2.2	2.0
6"	1.5	3.0	6.0	4.0	4.5	4.5
8"	2.5	5.0	9.5	6.5	9.5	8.0
10"	4.1	8.0	13.0	9.5	12.5	12.5
12"	5.5	11.5	19.0	13.5	16.0	18.0
16"	9.0	18.0	33.0	23.0	27.0	32.0
20"	14.0	28.0	51.0	36.0	42.0	50.5

NOTES:
1. BEARING AREAS ARE BASED ON UNDISTURBED SOIL WITH A BEARING CAPACITY OF 1,000 POUNDS PER SQUARE FOOT. FOR A LESSER SOIL BEARING CAPACITY THESE AREAS SHALL BE INCREASED ACCORDINGLY.
2. ALL CONCRETE THRUST BLOCKS SHALL BE 3000 p.s.i. CONCRETE.
3. THRUST BLOCKS SHALL BE POURED AGAINST UNDISTURBED EARTH.
4. NO JOINT SHALL BE COVERED WITH CONCRETE.
5. JOINTS THAT LOCATED AGAINST THRUST BLOCKS ARE TO BE WRAPPED IN A CLOTH MATERIAL.
6. APPROVED MECHANICAL JOINT RESTRAINTS ARE REQUIRED AT ALL VERTICAL BENDS AND MAY BE USED IN LIEU OF THRUST BLOCKS AT HORIZONTAL BENDS AT THE OPTION OF THE ENGINEER, AT NO ADDITIONAL COST TO THE OWNER.

THRUST BLOCK DETAIL
(N.T.S.)



FIRE HYDRANT DETAIL
(n.t.s.)



WATER SERVICE PIPE BEDDING DETAIL
(N.T.S.)
(NOT FOR USE IN ArDOT R/W)

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9101
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
GEORGE M. STOCK
No. 9
REGISTERED PROFESSIONAL ENGINEER
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P. #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	


SHEET TITLE:
CONSTRUCTION DETAILS

SHEET NO.:
9.0


DRAWING FILE: G:\DRAWINGS\2025\7775\Civil\Permanent\7775 Details.dwg, LAYOUT: 9.0 Const. Details, PLOTTED: Jul 16, 2025 - 2:50pm, PLOTTED BY: Linda Wood




FLARED END SECTION
(N.T.S.)




2-GRATE INLETS PRECAST CONCRETE
(N.T.S.)




PRECAST CONCRETE MANHOLE
(N.T.S.)




MANHOLE STEP FOR PRECAST AND CAST-IN-PACE MANHOLE
(N.T.S.)




PIPE BEDDING CLASS "C" (MODIFIED FOR REINFORCED CONCRETE PIPE)
(N.T.S.)



PIPE BEDDING CLASS "C" (FOR ALL 6" TO 18" PIPE EXCEPT REINFORCED CONCRETE PIPE)
(N.T.S.)



PRECAST CONCRETE INLET COVER AND STONE
(N.T.S.)



CAST IRON SIDE INTAKE UNIT FOR GRATED INLETS - 249 LBS
(N.T.S.)

ALL DETAILS SHOWN ON THESE PLANS ARE FOR THE CONVENIENCE OF THE CONTRACTOR. THE DETAILS ARE TO BE VERIFIED PER BRYANT'S STANDARD CONSTRUCTION SPECIFICATIONS. ALL METHODS, MEANS AND MATERIALS SHALL CONFORM TO BRYANT'S CURRENT STANDARD CONSTRUCTION SPECIFICATIONS.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9103
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS GEORGE M. STOCK 9-18-19 REGISTERED PROFESSIONAL ENGINEER 10-15-25

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
CONSTRUCTION DETAILS

SHEET NO.:
9.1

DRAWING FILE: E:\DRAWINGS\2025\7775\Civil\Revised\CITY\Sheet Key LAYOUT.DX | Cmd: Default, PLOTTED: Jul 16, 2025 - 2:53pm, PLOTTED BY: Lisa Lenfest



GENERAL NOTES

1. IN AREAS TO RECEIVE BITUMINOUS PAVING, CONCRETE DRIVEWAYS OR CURB AND GUTTER, SUBGRADE SHALL BE COMPACTED TO A DENSITY NOT LESS THAN 95% OF MAXIMUM MODIFIED DENSITY OBTAINED AT OPTIMUM MOISTURE CONTENT.
2. FOR AREAS OF SUBGRADE PREPARATION TO RECEIVE CONCRETE SIDEWALKS, SUBGRADE SHALL BE COMPACTED TO DENSITY OF 90% MAXIMUM MODIFIED DENSITY.
3. CRUSHED STONE – MATERIAL IN EACH COURSE SHALL BE COMPACTED TO A DENSITY OF 98% MAXIMUM MODIFIED DENSITY.
4. CONCRETE SIDEWALK SHALL BE A MINIMUM OF 4' WIDE IN RESIDENTIAL SUBDIVISIONS

* NOTES: PAVEMENT RECONSTRUCTION TO CENTERLINE IS REQUIRED WHEN EXISTING STREET DOES NOT MEET THESE STANDARDS.

CITY OF BRYANT

TYPICAL SECTION LOCAL 1 / RESIDENTIAL STREET

Issue Date APRIL 2013


Revision Date


DETAIL 1

A1

P:\2022 and Previous Projects\Avgsubmit\1135\1136 Street Master Plan Details.dwg, 3/11/2013 9:28:49 AM

CITY OF BRYANT	CURB & GUTTER SECTIONS	Issue Date APRIL 2013	Revision Date
		DETAIL 7	





A7

ALL DETAILS SHOWN ON THESE PLANS ARE FOR THE CONVENIENCE OF THE CONTRACTOR. THE DETAILS ARE TO BE VERIFIED PER BRYANT'S STANDARD CONSTRUCTION SPECIFICATIONS ALL METHODS, MEANS AND MATERIALS SHALL CONFORM TO BRYANT'S CURRENT STANDARD CONSTRUCTION SPECIFICATIONS.

PREPARED BY:
STOCK & ASSOCIATES Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH. (636) 530-9100 FAX (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS GEORGE M. STOCK 25116 REGISTERED PROFESSIONAL ENGINEER
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO.: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:

CONSTRUCTION DETAILS

SHEET NO.:

9.2

Document Set: 5:\WORK\2025\2025-7775\Drawings\7775 Base.dwg, LAYOUT: C9.2 Saved: Date: 7/17/2025 - 10:14:16 AM, Plotted: 7/17/2025 BY: Isaac Wood

STORMWATER DIFFERENTIAL RUNOFF

PRE-DEVELOPED			
	ACRES	C*I	TOTAL Q(100)
GRASS	1.26	5.10	6.40
PVMT/ROOF	0.15	9.50	1.40
		TOTAL Q(100) =	7.81


POST-DEVELOPED			
	ACRES	C*I	TOTAL Q(100)
GRASS	0.61	5.10	3.09
PVMT/ROOF	0.80	9.50	7.58
		TOTAL Q(100) =	10.67

DIFFERENTIAL = POST - PRE = + 2.86

TABLE 1
Allowable Peak Discharge
Pre-Developed Conditions

Design Storm (Year)	*Pre-Development Runoff (c.f.s.)**	*Volume (ac-ft)*
2	2.53	0.210
10	4.61	0.377
25	5.77	0.472
50	7.22	0.593
100	7.75	0.637

* = Includes offsite drainage onto subject property



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:

STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
GEORGE M. STOCK
REGISTERED PROFESSIONAL ENGINEER
No. 25116
07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY NUMBER: 000996

REVISIONS:

1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
EXISTING DRAINAGE AREA MAP

SHEET NO.:
C10.0

Drawing Set: G:\STOCK\PROJECTS\2025\7775\Drawings\PLOT\Site.dwg 07/16/25 10:42a John PLOTTED BY: Lisa Miller

GOOD DAY FARM - BRYANT

2024-7775

STORMWATER RUNOFF CALCULATIONS

100 YEAR 5-MIN
I=10 IN/HR
C (IMPERVIOUS)=0.95*
C (PERVIOUS) = 0.51*
*=FROM TABLE 400-1

Q=CIA
Q=PEAK FLOW, C=RUNOFF COEFF.,
I=RAINFALL INTENSITY, A=DRAINAGE AREA

POST-DEVELOPMENT RUNOFF


	AREA (SQ.FT)		TOTAL AREA		PERVIOUS	C*I	Q	IMPERVIOUS	C*I	Q	Q
SUBAREA	PERVIOUS	IMPERVIOUS	SQ.FT	AC	ACREAGE	(PERV.)	(PERV.)	ACREAGE	(IMPRV.)	(IMPRV.)	(TOTAL)
1	15,088	12,945	28,033	0.64	0.35	5.10	1.77	0.30	9.50	2.82	4.59
2	7,501	0	7,501	0.17	0.17	5.10	0.88	0.00	9.50	0.00	0.88
3	0	10,160	10,160	0.23	0.00	5.10	0.00	0.23	9.50	2.22	2.22
4	0	1,960	1,960	0.04	0.00	5.10	0.00	0.04	9.50	0.43	0.43
5	0	3,415	3,415	0.08	0.00	5.10	0.00	0.08	9.50	0.74	0.74
6	1,500	6,268	7,768	0.18	0.03	5.10	0.18	0.14	9.50	1.37	1.54
7	2,292	0	2,292	0.05	0.05	5.10	0.27	0.00	9.50	0.00	0.27
O-2	854	0	854	0.02	0.02	5.10	0.10	0.00	9.50	0.00	0.10
O-3	1,689	0	1,689	0.04	0.04	5.10	0.20	0.00	9.50	0.00	0.20
O-6	3,424	400	3,824	0.09	0.08	5.10	0.40	0.01	9.50	0.09	0.49
O-7	0	779	779	0.02	0.00	5.10	0.00	0.02	9.50	0.17	0.17

TABLE 2
Peak Discharge - Post-Developed Conditions

Design Storm (Year)	*Allowable Discharge (cfs)*	*Post-Developed Discharge (cfs)*
2	2.53	1.81
10	4.61	3.73
25	5.77	5.83
50	7.22	6.44
100	7.75	6.92

Stormwater Detention Summary

Design Storm (Year)	*Basin Discharge (cfs)*	*Basin WSEL (feet)*	*Basin Freeboard (feet)*
2	1.81	406.46	3.54
10	3.73	407.31	2.69
25	5.83	407.44	2.56
50	6.44	407.72	2.28
100	6.92	407.82	2.18



GRAPHIC SCALE

30 0 15 30 60 120

(IN FEET)
1 inch = 30 ft.

PREPARED BY:
STOCK & ASSOCIATES
Consulting Engineers, Inc.
257 Chesterfield Business Parkway
St. Louis, MO. 63005 PH: (636) 530-9100 FAX: (636) 530-9130
e-mail: general@stockassoc.com
Web: www.stockassoc.com

SITE IMPROVEMENT PLANS FOR:

GOOD DAY FARM - BRYANT

3205 HIGHWAY 5 N.
BRYANT, ARKANSAS 72019

07/16/25

GEORGE M. STOCK E-25116
CIVIL ENGINEER
CERTIFICATE OF AUTHORITY
NUMBER: 000596

REVISIONS:


1	07/16/25 CITY COMMENTS

DRAWN BY: L.C.W.	CHECKED BY: G.M.S.
DATE: 05-14-2025	JOB NO: 2025-7775
M.S.D. P #:	BASE MAP #:
S.L.C. H&T #:	H&T S.U.P. #:
M.D.N.R. #:	

SHEET TITLE:
PROPOSED DRAINAGE AREA MAP


SHEET NO.:
C10.1

Plotted by: gstock@STOCKASSOC.COM 07/16/25 Time: Aug. 14 2025 2:39pm PLOTTED BY: Laura Reed




Landscape Plan
SCALE 1"=20'


0 20 40 80




Spade Cut Bed Edge




Typical Perennial Planting




Typical Canopy Tree Planting






Typical Shrub Planting



Typical Evergreen Planting



Tree Protection Detail

PLANTING SCHEDULE

ID	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
CANOPY-SHADE TREE					
A	2	Acer saccharum 'Bailsta'	Fall Fiesta Sugar Maple	3" caliper	B & B

PLANTING SCHEDULE

ID	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE	REMARKS
SHRUBS-ORNAMENTAL GRASSES-PERENNIALS-ANNUALS-GROUNDCOVER					
a	4	Ilex x meserveae meserveae 'Heckenstar'	Castle Wall Blue Holly	18" tall	60" o.c.
b	3	Ilex x meserveae 'SMNIFA'	Castle Keep Blue Holly	18" tall	60" o.c.
c	6	Abelia x grandiflora 'Radiance'	Radiance Abelia	18" tall	48" o.c.
d	11	Juniperus horizontalis 'Wiltonii'	Blue Rug Juniper	18" tall	36" o.c.

Landscape Summary:

- Minimum landscaping criteria:
  - C-2 zoning = 1 tree per ½ acre
    - 41,666 s.f. / 2 = 1.91 half-acre units x 1 tree = **2** trees required
  - C-2 zoning = 1 evergreen per 2,000 s.f.
    - 1,988 s.f. / 2,000 s.f. = **1** evergreen required

Landscape Notes:

1) Provide lawn in all disturbed areas.
All 3:1 or steeper slopes shall be lawn seed and have erosion control blanket.

2) Topsoil in all disturbed lawn areas at 6" depth.

3) Soil mix in all shrub beds at 8" depth.

4) All mulch to be double ground bark mulch.

5) Bed edges to be spade cut.

Tree Protection Notes:

1) Pre-construction meeting to be held on-site to include a presentation of tree protection measures to operators, construction supervisors, developer's representative, and city zoning inspector.

2) Clearing Limits to be rough staked in order to facilitate location for installation of protection fencing. No early maintenance schedule is required.

3) No clearing or grading shall begin in areas where the treatment and preservation measures have not been completed, including the installation of tree protection fencing as shown on the plan. Where necessary, Contractor may perform minor tree clearing prior to installing silt fencing and tree protection fencing provided they maintain tree protection area.

4) Tree Protection Fencing shall be 4-foot high temporary plastic construction fence. No equipment traffic/parking, concrete washout, material storage or other such construction activity shall be permitted to penetrate the protection fencing except for the removal of dead or invasive plant material. All ground plane in planting areas shall be mulched with hardwood bark mulch. Tree Protection Signage will be placed along the Protection Fencing as shown as the dashed line on the plan.

5) Tree protection measures to be maintained throughout construction.

Licensed Landscape Architect
LEE HESS
Arkansas
5-20-25

Lee Hess - Landscape Architect
AR License # LA-712056

Consultants:

GOOD DAY FARMS

3205 HIGHWAY 5 N
BRYANT, ARKANSAS 72019

Revisions:

Date	Description	No.

Drawn: RS
Checked: LH

LOOMIS ASSOCIATES
landscape architects + planners
750 spirit 40 park drive, chesterfield, missouri 63005
t. 636-519-8668
www.loomis-associates.com

Sheet Title: LANDSCAPE PLAN

Sheet No: L1.01

Date: 5/20/25
Job #: 813.150