PHASE I BMPS:
1. FILE A SHORT TERM ACTIVITY AUTHORIZATION (STAA) FOR ENTRY OF MACHINERY INTO WATER, DEBRIS REMOVAL FROM WATER OR WET LAND; BRIDGE CONSTRUCTION; OTHER WITH ARKANSAS DEPARTMENT OF ENVIRONMENTAL QUALITY.

PHASE II BMPS
1. SEED ALL DENUDED AREAS. SEED ALL DISTURBED AREAS WITHIN 10 DAYS OF COMPLETION OF THE WORK.

PHASE III BMPS
1. INSTALL SOD AND COMPLETE FINAL CLEANUP.

PROJECT CLOSEOUT:
1. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROLS DEVICES. (ONLY WHEN SITE IS STABILIZED.

DATE	REVISION	BY

GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com

DOGWOOD DRAINAGE IMPROVEMENTS PHASE 2
BRYANT, ARKANSAS

STATE OF ARKANSAS
Vernon W. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON W. WILLIAMS

11-8-2021

CONTENTS:
DRAINAGE PLAN

PROJECT NO: 19027

DATE: OCTOBER, 2021

SHEET NO: C1.0

J:\Projects\2019 Projects\19027 Dogwood Drainage Improvements\Drawings\AWD\Design\19027 Dogwood Drainage Improvements Phase 2 Design.dwg