# Bryant Planning Commission Meeting

Boswell Municipal Complex - City Hall Court Room

210 SW 3rd Street

YouTube: https://www.youtube.com/c/bryantarkansas

**Date:** April 10, 2023 - **Time:** 6:00 PM

## Call to Order

## Approval of Minutes

**1. Bryant Planning Commission Meeting Minutes 3/13/2023**

- 2023-03-13 Planning Commission Meeting Minutes..pdf

## Announcements

## Director's Report

## DRC Report

**2. Butler Center** - 1109 N Reynolds

*GarNat Engineering - Requesting the Following:*
*1. Approval of Variance on Side setback and Rear Setback - NO RECOMMENDATION, CONTINGENT UPON REZONING AND SITE PLAN APPROVALS*
*2. Approval for Rezoning from R-E to C-2 - NO RECOMMENDATION*
*3. Site Plan Approval - RECOMMENDED APPROVAL, CONTINGENT UPON VARIANCE AND REZONING APPROVAL*

**3. Elite Volleyballl Academy** - Henry Ave and Christy Ln

*GarNat Engineering - Requesting the Following:*
*1. Approval of Variance on Rear Setback from 75' to 25' - NO RECOMMENDATION, CONTINGENT UPON REZONING AND SITE PLAN APPROVALS*
*2. Approval for Rezoning from R-2 to C-2 - NO RECOMMENDATION*
*3. Site Plan Approval - RECOMMENDED APPROVAL, CONTINGENT UPON VARIANCE AND REZONING APPROVAL*

**4. 3113 Whispering Oak** - Conditional Use Permit

*Kelley Tucker - Requesting Approval for CUP for a duplex - RECOMMENDED APPROVAL*

**5. Pikewood Subdivision Lots 89r & 90r** - Conditional Use Permits

*GarNat Engineering - Requesting Approval for Two Conditional Use Permits for Duplexes - RECOMMENDED APPROVAL*

**6. 25300 I-30 N** - Conditional Use Permit

*Hope Consulting - Requesting Approval for Condtional Use Permit for Self-Storage Facility - NO RECOMMENDATION*

**7. Home 2 Outparcel - Replat** - The Sullivan Place Subdivision Lots 4 & 1

*Charlie Best - Requesting Approval for Replat - RECOMMENDED APPROVAL*

**8. Springhill Grocery - 2725 Springhill Road** - Commercial Plat

*Ali Hamza - Requesting Plat Approval - RECOMMENDED APPROVAL*

**9. Wendy's - 2206 N Reynolds** - Sign Permit

*Action Signs - Requesting Sign Permit Approval - STAFF APPROVED*

- 0677-APP-01.pdf

**10. Alliance Technical Group - 219 Brown Ln** - Sign Permit

*Aero Signs - Requesting Sign Permit Approval - STAFF APPROVED*

- 0678-PLN-01.pdf

**11. Elysian Event - 2102 Brandon Rd** - Sign Permit

*Arkansas Sign and Neon - Requesting Sign Permit Approval - STAFF APPROVED*

- 0696-APP-01.pdf

**12. Auto Glass Now - 1814 N Reynolds Road** - Sign Permit

*Action Signs - Requesting Sign Permit Approval - STAFF APPROVED*

- 0697-APP-01.pdf

**13. 507 Boone Road** - New Office Addition

*Jeremy McMillian - Requesting Approval for New Addition to Office Building - APPROVED, Contingent upon Stormwater In-lieu-of fee being paid*

- 0698-APP-01.pdf

**14. Bryant Schools - Business Office Additions** - 603 School Drive

*Terry Harper - Requesting Approval for Addition to Business Office Building - APPROVED, CONTINGENT UPON STORMWATER IN-LIEU-OF FEE BEING PAID AND FIXING OF CROSSWALK RAMPS AT BOSWELL RD INTERSECTION.*

- Bryant Schools - Business Office New Addition.pdf

## Public Hearing

**15. Butler Center - 1109 N Reynolds** - Rezone from R-E to C-2

*GarNat Engineering - Requesting Approval for Rezoning from R-E to C-2*

- 0686-GRR-01.pdf
- 0686-SignPicture.pdf
- 0686-PNO-01.pdf
- 0686-LTR-01.pdf
- 0686-SRV-01.pdf
- 0686-AFF-01.pdf

**16. Elite Volleyballl Academy - Henry Ave and Christy Ln** - Rezone from R-2 to C-2

*GarNat Engineering - Requesting Approval for Rezoning from R-2 to C-2*

- 0694-GRR-02.pdf
- 0694-GRR-01.pdf
- 0694-LST-01.PDF
- 0694-SignPicture.pdf
- 0694-LTR-01.pdf
- 0694-PLT-01.pdf

**17. 3113 Whispering Oak** - Conditional Use Permit

*Kelley Tucker - Requesting Approval for CUP for a duplex*

- 0672-NOT-01.pdf

- 0672-APP-01.pdf

**18. Pikewood Subdivision Lots 89r & 90r** - Conditional Use Permits

*GarNat Engineering - Requesting Approval for Two Conditional Use Permits for Duplexes*

- 0663-PUB-01.pdf
- 0663-AFD-01.pdf
- 0663-PLT-01.pdf
- 0663-NOT-01.pdf
- 0663-LTR-01.pdf

**19. 25300 I-30 N** - Conditional Use Permit

*Hope Consulting - Requesting Approval for Condtional Use Permit for Self-Storage Facility*

- 0687-PLN-02.pdf
- 0687-APP-02.pdf
- 0687-APP-01.pdf

## Old Business

## New Business

**20. Home 2 Outparcel - Replat** - The Sullivan Place Subdivision Lots 4 & 1

*Charlie Best - Requesting Approval for Replat*

- 0699-RPLT-01.pdf

**21. Butler Center - 1109 N Reynolds Road** - Site Plan

*GarNat Engineering - Requesting Site Plan Approval*

- 0685-ELV-01.pdf
- 0685-PLN-03.pdf
- 0685-SWB-01.pdf
- 0685-MTP-01.pdf
- 0685-SWP-01.pdf
- 0685-SMP-01.pdf
- 0685-LTR-02.pdf
- 0685-LTR-01.pdf
- 0685-AFF-01.pdf

**22. Elite Volleyball Academy - Henry Ave and Christy Ln** - Site Plan

*GarNat Engineering - Requesting Site Plan Approval*

- 0693-LND-02.pdf
- 0693-LND-01.pdf
- 0693-PLN-03.pdf
- 0693-SMP-01.pdf
- 0693-SWP-01.pdf
- 0693-PLT-01.pdf
- 0693-LTR-01.pdf

**23. Springhill Grocery - 2725 Springhill Road** - Commercial Plat

*Ali Hamza - Requesting Plat Approval*

- 0631-PLT-02.pdf

## Adjournments

# Bryant Planning Commission Meeting Minutes

Monday, March 13th, 2023
Boswell Municipal Complex – City Hall Courtroom
6:00 PM

## Agenda

**CALL TO ORDER**

- Chairman Rick Johnson calls the meeting to order.
- Commissioners Present: Johnson, Penfield, Statton, Hooten, Edwards, Arey, Burgess, Erwin
- Commissioners Absent: None

**ANNOUNCEMENTS**

*Birch Street Replat removed from the agenda by applicant, Pikewood subdivision CUP Pulled from agenda due to not meeting public hearing requirements.*

**DIRECTOR'S REPORT**

*No Report*

**APPROVAL OF MINUTES**

1. **Planning Commission Meeting Minutes 02/13/2023**

*Motion to Approve Minutes made by Commissioner Statton, Seconded by Commissioner Penfield. Voice Vote, 8 Yays, 0 nays. None Absent.*

*Vice-chairman Burgess read the DRC Report.*

**DRC REPORT**

2. **Shady Pine Plaza - 2228 Shady Pine Ln**

Richardson Engineering - Requesting Approval for Variance on rear and side setbacks, and Recommendation for Approval of Site Plan. - NO RECOMMENDATION ON VARIANCES, RECOMMENDED APPROVAL OF SITE PLAN

3. **Pikewood Subdivision - Lots 89R & 90R - CUP For Duplexes**

   GarNat Engineering - Requesting Approval for Conditional Use Permits to Build Duplexes - RECOMMENDED APPROVAL

4. **Birch Street Replat - Lots 10-14 of Sherwood Forest Subdivision**

   Hope Consulting - Requesting Approval for Replat - RECOMMENDED APPROVAL, Contingent upon Easement being added to plat

5. **Creekside Addition Phase 1 - Lots 83, 84, & Tract C Replat**

   GarNat Engineering - Requesting Approval for Replat - RECOMMENDED APPROVAL

6. **Marketplace East Subdivision Ph. 1 - Preliminary Plat**

   GarNat Engineering - Requesting Preliminary Plat Approval and Approval on Modification from Master Transportation Plan. - RECOMMENDED APPROVAL, Contingent upon remaining items being met.

7. **Diamond Estates Subdivision - Modification from Subdivision Code**

   GarNat Engineering - Requesting Approval For Modification from Subdivision Code on Sidewalk Requirement for Portion of Street. - NO RECOMMENDATION

8. **Indian Springs Baptist Church - 23581 I-30 - Sign Permit**

   Ace Sign Company - Requesting Sign Permit Approval - APPROVED

9. **Wendy's - 2206 N Reynolds - Remodel**

   LiveCo Construction - Requesting Approval for Remodel - APPROVED, Contingent upon Dumpster Enclosure being built.

10. **Athletico - 3231 Main Street Ste. 3 - Sign Permit**

    Pinnacle Signs - Requesting Sign Permit Approval - STAFF APPROVED

11. **Bryant Schools Admin Building 1511 N Reynolds Road - Parking Lot Addition**

    Minton Engineering - Requesting Site Plan Approval - APPROVED, Contingent upon remaining items being addressed

12. **Scooter's Coffee - 1816 N Reynolds Road - Sign Permit**

    Shawn LaMontia - Requesting Approval of Signage - APPROVED

13. **Aria Oil C-Store - Hwy 5 And Lowery Ln**

    Hope Consulting - Requesting Site Plan Approval - APPROVED, Contingent upon remaining items being met.

14. **Summerwood Sports Gym - 4800 Dallas Dr - Sign Permit**

    Arkansas Sign And Neon - Requesting Sign Permit Approval - STAFF APPROVED

15. **Hibbett Sports - 7319 Alcoa Road - Sign Permit**

    Lumatech - Requesting Sign Permit Approval - STAFF APPROVED

**PUBLIC HEARING**

16. **Pikewood Subdivision - Lots 89R & 90R - CUP for Duplexes**

    GarNat Engineering - Requesting Approval for Conditional Use Permits to Build Duplexes

    *Item pulled from agenda for not meeting Public Hearing requirements.*

**NEW BUSINESS**

17. **Shady Pine Plaza** - 2228 Shady Pine Ln

    Richardson Engineering - Requesting Site Plan Approval

    *After brief discussion on the item, Chairman Johnson Called for a roll call vote to approve. 8 yays, 0 nays, None absent.*

18. **Birch Street Replat** - Lots 10-14 of Sherwood Forest Subdivision

    Hope Consulting - Requesting Approval for Replat

    *Item pulled from agenda by request of applicant.*

19. **Creekside Addition Phase 1** - Lots 83, 84, Tract C - Replat

    GarNat Engineering - Requesting Approval for Replat

    *After brief discussion on the item, Chairman Johnson Called for a roll call vote to approve. 8 yays, 0 nays, None Absent.*

20. **Marketplace East Subdivision Phase 1** - Preliminary Plat

    GarNat Engineering - Requesting Preliminary Plat Approval and Approval on Modification from Master Transportation Plan

    *After brief discussion on the item, Chairman Johnson Called for a roll call vote to approve. 7 yays, 0 nays, None Absent. Commissioner Penfield Abstained from the Vote.*

21. **Diamond Estates Subdivision** - Modification from Subdivision Code

    GarNat Engineering - Requesting Approval For Modification from Subdivision Code on Sidewalk Requirement for Portion of Street and cul-de-sac length

*After brief discussion on the item, Chairman Johnson Called for a roll call vote to approve the Modification on the sidewalk. 8 yays, 0 nays, None Absent. He then called for a vote on the modification for length of cul-de-sac. 7 yays, 1 nay, None Absent.*
*Both requests pass.*

*Commissioner Penfield made a motion to add the Diamond Estates Subdivison Preliminary Plat to the Agenda. Seconded by Commissioner Arey. Voice Vote, 8 yays, 0 Nays.*

22. **Diamond Estates Subdivision** - Preliminary Plat
GarNat Engineering - Requesting Preliminary Plat Approval

*After a brief discussion, Chairman Johnson Called for a roll call vote to approve. 8 yays, 0 nays, None Absent.*

**ADJOURNMENT**

*Motion to Adjourn made by Commissioner Burgess, Seconded by Commissioner Penfield. Voice Vote, 8 Yays, 0 nays. None Absent.*

_____ _____

*Chairman, Rick Johnson* *Date*

_____ _____

*Secretary, Tracy Picanco* *Date*

**City of Bryant, Arkansas**
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0943

# SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at www.cityofbryant.com under the Planning and Community Development tab.

Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.

Date: 2.17.2023

**Sign Co. or Sign Owner**

Name Action Signs
Address 2700 John Harden Dr
City, State, Zip Jacksonville, AR 72076
Phone 501.457.7391
Email Address tim@actionsignandneon.com

**Property Owner**

Name Wendy's
Address 2206 N Reynolds Road
City, State, Zip Bryant, AR 72022
Phone 501.229.9361
Email Address nsimpson@livecoteam.com

## GENERAL INFORMATION

Name of Business Wendy's

Address/Location of sign 2206 N Reynolds Road Bryant, AR 72022

Zoning Classification _____

**Please use following page to provide details on the signs requesting approval.** Along with information provided on this application, **a Site Plan showing placement of sign(s) and any existing sign(s) on the property is required** to be submitted. **Renderings of the sign(s) showing the correct dimensions is also required** to be submitted with the application. A thirty-five dollar ($35) per sign payment will be collected at the time of permit issuance. According to the Sign Ordinance a fee for and sign variance or special sign permit request shall be one hundred dollars ($100). Additional documentation may be required by Sign Administrator.


## READ CAREFULLY BEFORE SIGNING

I _____, do hereby certify that all information contained within this application is true and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand


that no sign may be placed in public right of way. I understand that I must comply with all Building and Electrical Codes and that it is my responsibility to obtain all necessary permits.

**Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering.**


| SIGN | Type (Façade, Pole, Monument, other) | Dimensions (Height, Length, Width) | Sqft (Measured in whole as rectangle) | Height of Sign (Measured from lot surface) | | Column for Admin Certifying Approval |
|---|---|---|---|---|---|---|
| | | | | Top of Sign | Bottom of Sign | |
| A | Wall Sign (Left) | 3'x11' | 33' | 16' | 13 | |
| B | Wall Sign (Right) | 3'x11' | 33' | 13.5' | 10.5' | |
| C | Wall Sign (Front) | 3'x11' | 33' | 17' | 14' | |
| E | Wall Sign (Front) | 9"x12' | 9' | 11' | 10' | |
| F | Pole Sign Faces | 16'x19' | 304' | | | |
| G | Readerboard Pole Faces | 5'x9' | 45' | | | |





**04** LEFT SIDE ELEVATION
SCALE: 1/4" = 1'-0"




**03** RIGHT SIDE ELEVATION
SCALE: 1/4" = 1'-0"




**02** REAR ELEVATION
SCALE: 1/4" = 1'-0"




**01** FRONT ELEVATION
SCALE: 1/4" = 1'-0"

SITE NUMBER:
BUILDING TYPE:
ASSET TYPE: FREESTA
CLASSIFICATION: RE
OWNER: COMPANY/FRAN
BASE VERSION: 2022 S
UPGRADE CLASSIFICATION:
PROJECT YEAR:
DESIGN TYPE: (2.0) UM B
DRAWING RELEASE: 2022 S

McIntos

The McIntosh Group
1850 South Boulder
Tulsa, Oklahoma 74
Telephone 918.585.
Telefax 918.583.72

PROJECT TYPE: 30
REFRES

Wendy's

2206 N REYNOLDS RD
BRYANT AR 72022

| REV. | DATE | DESCRIPTION |
|---|---|---|

ISSUE DATE: 01/28/2022
PROJECT NUMBER: T.B.D.
DRAWN BY: XXX
CHECKED BY: XXX

SEAL
REGISTERED ARCHITECT
ALFRED PAGANO
No. 3987
STATE OF ARKANSAS
LICENSE NUMBER: 1004
EXPIRATION: 12/31/

SHEET NAME
EXTERIOR ELEVATIONS

SHEET NUMBER
A2.1

**Folder Name**
L:\Service and Install\PICTURES\WENDYS - BRYANT\2.17.23

**Designer**

**File Name**
2206 N reynolds rd bryant AR 72022 quote 2.2.23.fs

**Job Number**







**Description**

**ARTWORK IS PROPERTY OF ACTION SIGN & NEON AND SHALL NOT BE DUPLICATED OR COPIED IN ANY MANNER.**

ACTION SIGNS
SIGNS WITH DIRECTION

P. O. Box 188
Jacksonville, AR 72076
2700 John Harden Dr.
Jacksonville, AR 72076

Ph 501-457-7391
Ph/Text 501-712-0012
Fax 501-457-7393

ARTWORK APPROVAL **MUST** BE MADE IN WRITING.
THIS CAN BE DONE BY A SIMPLE EMAIL, TEXT, OR FAX
WITH THE APPROVED ARTWORK ATTACHED.
**PRODUCTION WILL NOT START OTHERWISE.**


| Customer | Name | Design Time | Design Time Pricing |
|---|---|---|---|
| Phone | Email | Date 2/17/2023 | Minutes |

**Design time is at a rate of $60 per hour, in 15 minute increments. Your first 15 minutes is *FREE*.**

**COLORS SHOWN ARE FOR REFERENCE ONLY. COLORS MAY VARY.**

READER BOARD &
FEATUREBOARD REPLACEMENT

6′ x 9′
NSS#: 81008512







## MATERIALS & SPECS

1. 1¾" deep pan formed ³⁄₁₆" modified acrylic with ½" deep embossed copy
2. 3 lines of 8" copy

- PMS 186c - Background
- White (letters)

rev 6/17

National Sign Systems®
4200 Lyman Court
Hilliard Ohio, 43026
800.544.6726
614.850.2540
sales@natsignsys.com
nationalsignsystems.com

BBB ACCREDITED BUSINESS
made in USA

HI-RISE FACE REPLACEMENT

# WHR 220

NSS#: 81007533




## MATERIALS & SPECS

Actual: 214 ft² | Nearest Rectangle: 280 ft²

1. Face - (2) translucent vinyl flex faces decorated first surface

- PMS 186c - hair, freckles
- PMS 201c - hair, outline
- PMS 698c - face, neck
- PMS 299c - bow, shirt, brooch
- PMS 439c - outline
- White

rev 6/17

National Sign Systems®
4200 Lyman Court
Hilliard Ohio, 43026
800.544.6726
614.850.2540
sales@natsignsys.com
nationalsignsystems.com

BBB ACCREDITED BUSINESS
made in USA

**City of Bryant, Arkansas**
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0943 Colton –
Cleonard@cityofbryant.com

# SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at www.cityofbryant.com under the Planning and Community Development tab.

Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.

Date: 2/15/23

**Sign Co. or Sign Owner**

Name Aero Signs LLC
Address 3308 PIKE AVE
City, State, Zip NLR, AR 72118
Phone 501-246-4952
Email Address sales@aero-signs.com

**Property Owner**

Name Pecan Tree Co.
Address 219 Brown Lane
City, State, Zip Bryant, AR 72022
Phone 501.607.3188 / 501.847.7077
Email Addres. judy@masalaenterprises.biz

**GENERAL INFORMATION**

Name of Business Alliance Technical Group
Address/Location of sign 219 Brown Lane Bryant, AR 72022
Zoning Classification _____

**Please use following page to provide details on the signs requesting approval.** Along with information provided on this application, a **Site Plan showing placement of sign(s) and any existing sign(s) on the property is required** to be submitted. **Renderings of the sign(s) showing the correct dimensions is also required** to be submitted with the application. A thirty-five dollar ($35) per sign payment will be collected at the time of permit issuance. According to the Sign Ordinance a fee for and sign variance or special sign permit request shall be one hundred dollars ($100). Additional documentation may be required by Sign Administrator.

**READ CAREFULLY BEFORE SIGNING**

I _____, do hereby certify that all information contained within this application is true and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand


Alliance
TECHNICAL GROUP
38"X96
101 VYM


30"X72
Alliance
TECHNICAL GROUP

ARKANSAS SIGN & NEON
8525 DISTRIBUTION DR.
LITTLE ROCK, AR 72209
501-562-3942 P
501-562-6651 F
UL Listed

ALL IDEAS, DESIGNS AND ARRANGEMENTS INDICATED OR REPRESENTED BY THIS DRAWING (EXCEPT FOR REGISTERED TRADEMARKS) ARE OWNED BY AND ARE THE PROPERTY OF ARKANSAS SIGN & NEON. USE OF THIS DOCUMENT IS PROHIBITED UNLESS WRITTEN AUTHORIZATION IS OTHERWISE GIVEN.
CUSTOMERS IS RESPONSIBLE TO OBTAIN ANY/ALL LANDLORD APPROVALS IF APPLICABLE.
DELIVERY TIMES VARY PER SCOPE OF WORK. TYPICAL DELIVERY TIME FROM ACCEPTANCE AND PERMITTING ARE 4-8 WEEKS. OUR GOALS IS TO DELIVER IN A TIMELY MANOR BARRING UNFORSEEN CIRCUMSTANCES.

**REPRESENTATIVE:** KEVIN HONEA
**DATE/DWG:** 02/09/2023 - DWG1
**DESIGNER:** LORA RAND


**CLIENT:** ELYSIAN EVENT
**LOCATION:** 2101 BRANDON RD STE 7 BRYANT AR 72022

SIGNATURE OF APPROVAL REQUIRED FOR PRODUCTION

REV1-GREEN




**side view**





***(1) 47” x 118” channel cloud sign with l.e.d illumination***
***black returns, white faces and black vinyl applied***







***NOTE: ANY NEEDED WALL REPAIRS ARE NOT ASN RESPONSIBILITY. ANY VIEWS SHOWING REPAIRS ARE FOR VIEWING ONLY.***


2101 Brandon Rd #7, Bryant, AR
Regroup Staffing
5.0 ★★★★★ 6 reviews
Recruiter
Directions
Save
Nearby
Send to phone
Share
Ad · Regroup Staffing, Bryant AR - Now Hiring
Our versatile staffing solutions bring the talent and characteristics to fit your team.
www.regroupstaffing.com/
22000 I-30 Frontage Rd Suite 6, Bryant, AR 72022
Open · Closes 4 PM
Updated by this business 4 weeks ago
regroupstaffing.com
(501) 943-8015
JF7P+9P Bryant, Arkansas
Send to your phone
Identifies as veteran-owned
Add a label
Brandon Rd
Regroup Staffing
Luigis Pizza & Pasta
Salvation Army
The Rowdy Rooster Boutique
Mashburn Mustang Center
Mobile Home and Supplies
Campbell Acoustical & Drywall
I-30 Frontage Rd
U.S. Hwy 70
Layers
Google
37°F Sunny
11:05 AM
3/14/2023

**City of Bryant, Arkansas**
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0943

# SIGN PERMIT APPLICATION

Applicants are advised to read the Sign Ordinance prior to completing and signing this form. The Sign Ordinance is available at www.cityofbryant.com under the Planning and Community Development tab.

Note: Electrical Permits may be Required, Please contact the Community Development Office for more information.

Date: 3.8.23

**Sign Co. or Sign Owner**

Name Action Signs
Address 2700 John Harden DR
City, State, Zip Jacksonville, AR 72076
Phone 501.457.7391
Email Address tim@actionsignandneon.com

**Property Owner**

Name Auto Glass Now
Address 1810 North Reynolds Rd
City, State, Zip Bryant, AR 72022
Phone 610.334.0018
Email Address hannah.martin@egansign.com

## GENERAL INFORMATION

Name of Business Auto Glass Now

Address/Location of sign 1810 North Reynolds Rd Bryant, AR 72022

Zoning Classification _____

**Please use following page to provide details on the signs requesting approval.** Along with information provided on this application, **a Site Plan showing placement of sign(s) and any existing sign(s) on the property is required** to be submitted**. Renderings of the sign(s) showing the correct dimensions is also required** to be submitted with the application. A thirty-five dollar ($35) per sign payment will be collected at the time of permit issuance. According to the Sign Ordinance a fee for and sign variance or special sign permit request shall be one hundred dollars ($100). Additional documentation may be required by Sign Administrator.

## READ CAREFULLY BEFORE SIGNING

I _____, do hereby certify that all information contained within this application is true and correct. I fully understand that the terms of the Sign Ordinance supersede the Sign Administrator's approval and that all signs must fully comply with all terms of the Sign Ordinance regardless of approval. I further certify that the proposed sign is authorized by the owner of the property and that I am authorized by the property owner to make this application. I understand

that no sign may be placed in public right of way. I understand that I must comply with all Building and Electrical Codes and that it is my responsibility to obtain all necessary permits.

**Use table below to enter information regarding each sign for approval. Please use each letter to reference each sign rendering.**

| SIGN | **Type** (Façade, Pole, Monument, other) | **Dimensions** (Height, Length, Width) | **Sqft** (Measured in whole as rectangle) | **Height of Sign** (Measured from lot surface) | | Column for Admin Certifying Approval |
|---|---|---|---|---|---|---|
| | | | | Top of Sign | Bottom of Sign | |
| A | Lit Channel Letters | 32"x200" | 45 SQ FT | 129.75" | 97.75" | |
| B | Road Sign Pylon Face Replacements | 48"x72" | 24 SQ FT | 16' | 12' | |
| C | Awning | 3'x30' | 90 SQ FT | 10' | 81" | |
| E | Door Vinyl | 30"x34" | 7 SQ FT | 72" | 38" | |
| F | | | | | | |
| G | | | | | | |




VICINITY MAP:




D

Repair · Replace · Calibrate

B

AGN AutoGlassNow
Repair · Replace · Calibrate

A

AutoGlassNow

**NOTES**
- Replace cabinet panels and LED bulbs (retrofit as needed)
- Existing poles and cabinets to be painted black
- Existing conditions vary & may affect cost due to size, material, quantity, installation, scope, etc.
- If electrical line/j-box is within 6' of electrical, connection to be handled by installer. If not, electrical handled by GC/owner.
- If roof penetrations are necessary, they are to be sealed by a roofer. Handled by GC/owner.
- Removal and disposal of existing wall signs and painting handled by GC/owner before installation.

# SP Site & Sign Location Plan

222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

EGAN SIGN

Sign Management Made Simple

AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
Site Plan

**Color Key:**

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

File Name:
30425_Bryant.pdf
Project Number: 30425

## PRE-PERMIT SIGN INFO — Property ID: AGN

| | | | |
|---|---|---|---|
| A.) Project Name: | Auto Glass Now | Date Completed: | 1/26/23 |
| B.) Street Address: | 1810 North Reynolds Road | | |
| C.) City, State Zip: | Bryant, AR 72022 | | |
| D.) Municipal Contact: | Colton Leonard | | |
| E.) Contact Phone: | 501-943-0301 | Email: | cleonard@cityofbryant.com |
| F.) Address, City, ST Zip: | 210 SW 3rd St., Bryant, AR 72022 | | |
| G.) Jurisdiction: | City/Town of: Bryant | Fax: | None |

| | | Yes/No |
|---|---|---|
| H.) Zone/Category/Class: | C-2 Highway Commercial | |
| I.) Overlay/MSP: | No overlay | |
| J.) Permit app fee: | $35 minimum | |
| K.) Permit Process time: | 1-3 wks | |
| L.) Permit required if only refacing? | | No |
| M.) Property Owner approval needed? | | Yes |
| N.) Temp./coming-soon Banners allowed? | | Yes |
| O.) Temporary freestanding Signs allowed? | | Yes |
| P.) Permit required for Temp Signs? Time allowed: | No permit required if less than 7 days | No |
| Q.) Can app. be mailed or must it be submitted in person? | Yes. Mailed or emailed | |

Note:

### ATTACHED SIGNS

1.) Formula(Max- Main ID & Secondary): 2sf/lf bldg façade fronting a public street. 300sf aggregate for all signs. No single sign may use more than 50% of the total max aggregate surface footage.

2.) Bldg sides/rear: Per formula if corner lot, facing frontage

3.) Transferrable? No

4.) Does Each elevation have own calc, or is it based on Main Elevation? Each elevation has own calc if facing street

5.) # allowed: 1 per façade per frontage on corner lot — Illumination: Int/Ext per Note 1

6.) Max.Overall Height: Roofline

7.) Calculation Method: Box Entire letter set/Cabinet, including Backer Panel

8.) Exposed raceway for Channel Ltrs allowed? Yes

9.) Special Wall sign codes: None stipulated.

10.) Storefront Bldg colors: None stipulated.

### FREESTANDING SIGNS

1.) Formula(Max- Main ID & Secondary): 300sf aggregate for all signs. No single sign may use more than 50% of the total max aggregate surface footage.

2.) # allowed: 1 — Illumination: Int/Ext per Note 1

3.) Height Max: 25' or height of bldg, whichever is less — Grade-to-sign Clearance: 10'

4.) Set-back: 10' back of curb/edge of roadway surface/st ROW, whichever greater. — Calc. Method: Count only largest sign face

### DIRECTIONAL SIGNS

1.) # Allowed: Not regulated — Illumination: May required permit. Submit for review.

2.) Max. SqFt: 6sf — Max. Height: Not regulated

3.) Permit: Not required 6' or less — Custom Logo: Not restricted in code

### DOOR/WINDOW VINYL

1.) # Allowed: Not regulated — Max Sq Ft: Not regulated

2.) Logos counted in sign area? N/A

3.) Included in wall signs? No — Permit? No

Note:

**Sign criteria** is reported as presented to us as of the "Date Completed". This provider is not responsible for changes in local sign code after the completion date, nor for the review process, interpretations, calculations or fees of local authorities. Where required by local authority, it is understood a permit will be obtained prior to manufacture.

## PRE-PERMIT SIGN INFO - Additional Notes — Property ID: AGN

### VARIANCE

| | | | |
|---|---|---|---|
| 1. Variance Meeting: | 2nd Mondays | App. Deadline: | 30 days |
| 2. Processing Time: | 2-3 months | Est. Fees: | $100 |
| 3. Attorney or expeditor required? | ☐ Yes ☑ No | Waiting Period after approval & how Long? | 15 days |
| 4. Documents Required: # sets: | 1 | | |
| 5. Probability of approval? | Unlikely | | |

☑ Sign Details ☑ Engineering Seal ☑ UL Number
☑ Building Elevations ☑ Owner Auth. Ltr. ☐ Property ID#
☑ Site Plan ☑ Legal Description ☐ Addl Prof Seals

Note:

### NOTES

**Note 1: Illumination**

1) Unless otherwise prohibited by this Ordinance, all signs may be illuminated. No illuminated sign shall be permitted which faces the front, side or rear lot lines of any residential lot regardless of zoning district and is located within fifty (50) feet thereof.
2) Every part of the light source of any illuminated sign shall be concealed from view from vehicular traffic in the public right-of-way or adjacent property. The light shall not travel from the light source directly to vehicular traffic in the public right-of-way or adjacent property, but instead shall be visible only from a reflecting or diffusing surface.
3) This provision shall not apply to neon tube lighting or electronic message centers operating in accordance with this ordinance.
4) Backlit Illuminated Awnings - Unless expressly provided otherwise in this ordinance, awning signs may be illuminated, including without limitation by backlighting.
5) Electronic message centers shall be illuminated in accordance with Section 2.05 of this Ordinance.

**Note 2: Additional Questions- Per contact, no special color regs for painting bldg/canopies.**

AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
Sign Code Information

**Color Key:**

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

# Site & Sign Location Plan

EGAN SIGN
222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name: 30425_Bryant.pdf
Project Number: 30425





Proposed




Existing 72"x96"

**Square Footage Calculation:**

Code: Aggregate of all signs NTE 300 sf;
signs are NTE 2sf per lf of facade that sign is on
One sign allowed per frontage
No one sign may exceed 50% of allowed sf
Calculation: 2 * 42' = 84
**Allowed: 84 sf**
**Used: 44.4 sf**
Existing: 48 sf
**Allowed Total: 300 sf**
**Used Total: 241.4 sf**
Sign A: 44.4 sf
Sign B: 36 sf
Sign C: 7.1 sf
Sign D: 90 sf




## A Illuminated Channel Letters & ACM Panel

Scale: 3/16" = 1'-0'

222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
**AGN-FML-21**
Illuminated Channel Letters
(44.4 Sq Ft)

Remove existing signage. Fill holes with clear, paintable caulk.


**Color Key:**
- White
- Black
- SW 6958 "Dynamic Blue"

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

File Name:
30425_Bryant.pdf
Project Number: 30425

NOT FOR PRODUCTION




NIGHT RENDERING





| Illuminated Channel Letters (Linear) | X | X1 | Y | Total Square Feet: |
|---|---|---|---|---|
| AGN-FML-15 | 22.8 | 15 | 142.8 | 22.6 |
| AGN-FML-18 | 27.4 | 18 | 171.3 | 32.6 |
| AGN-FML-21 | 32 | 21 | 200 | 44.4 |
| AGN-FML-24 | 36.5 | 24 | 228.4 | 57.9 |
| AGN-FML-27 | 41 | 27 | 257 | 73.2 |
| AGN-FML-30 | 45.6 | 30 | 285.6 | 90.4 |
| AGN-FML-33 | 50.2 | 33 | 314.1 | 109.5 |
| AGN-FML-36 | 54.7 | 36 | 342.7 | 130.2 |
| AGN-FML-39 | 59.3 | 39 | 371.2 | 152.9 |
| AGN-FML-42 | 63.8 | 42 | 399.8 | 177.1 |

NOT FOR PRODUCTION

## CROSS SECTION OF UL LISTED CHANNEL LETTERS w/ LEDS

(1) 1" PLASTIC TRIM CAP PAINTED BLACK
(2) 3/16 POLYCARBONATE FACE
(3) .040 ALUMINUM RETURN (.063 BACK) PAINTED BLACK
(4) 1/4" DRAIN HOLES (Min. 2 per letter)
(5) LED ILLUMINATION
(6) LED POWER SUPPLY
(7) FACADE
(8) LOW VOLTAGE CLASS 2 POWER LINE
(9) MOUNTING HARDWARE (3/8"x5" Bolts)
(10) EXISTING 120 VOLT SERVICE

This sign is intended to be installed in accordance with the requirements of Article 600 of the National Electrical Code and/or other applicable local codes.
This includes proper grounding and bonding of the sign.




## A Illuminated Channel Letters

Scale: NTS

AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
**AGN-FML-21**
Illuminated Channel Letters
(44.4 Sq Ft)

Qty: 1

Provide LED illuminated channel letters per detail; flush mounted to facade.

**Color Key:**
White
Black

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

EGAN SIGN
222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name:
30425_Bryant.pdf
Project Number: 30425




Proposed 32




Existing 72"x72"

**Square Footage Calculation:**

Code: Aggregate of all signs NTE 300 sf;
signs are NTE 2sf per lf of facade that sign is on
One sign allowed per frontage
No one sign may exceed 50% of allowed sf
Calculation: 2 * 42' = 84
**Allowed: 84 sf**
**Used: 44.4 sf**
Existing: 48 sf
**Allowed Total: 300 sf**
**Used Total: 241.4 sf**
Sign A: 44.4 sf
Sign B: 36 sf
Sign C: 7.1 sf
Sign D: 90 sf




B

## Pylon - Face Replacement

Scale: 3/4" = 1'-0"

NOT FOR PRODUCTION

AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
Pylon - Face Replacement
(24 Sq Ft)

Qty: 2 (1 per side)

Provide 3/16"thk polycarbonate replacement faces w/ surface applied digitally printed graphics to match color key.

Repaint existing sign cabinet and pole black.

**Color Key:**
- White
- PMS 3538 C
- Black

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

EGAN SIGN
222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com


This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name:
30425_Bryant.pdf
Project Number: 30425




Proposed 16



NOT FOR PRODUCTION





## C Door Vinyl

Scale: 1 ½" = 1'-0"

**Square Footage Calculation:**

Code: Aggregate of all signs NTE 300 sf;
signs are NTE 2sf per lf of facade that sign is on
One sign allowed per frontage
No one sign may exceed 50% of allowed sf
Calculation: 2 * 42' = 84
**Allowed: 84 sf**
**Used: 44.4 sf**
Existing: 48 sf
**Allowed Total: 300 sf**
**Used Total: 241.4 sf**
Sign A: 44.4 sf
Sign B: 36 sf
Sign C: 7.1 sf
Sign D: 90 sf




**LOCATION LAYOUT:**
SCALE: 3/4" = 1'-0"

AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
**AGN-DV**
Door Vinyl
(7.1 Sq Ft)

Qty: 1

Provide computer cut vinyl to match color key; surface applied to door.

Remove existing graphics.

**Color Key:**
- White
- Black
- PMS 3538 C

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

EGAN SIGN

222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name:
30425_Bryant.pdf
Project Number: 30425




Proposed 96





Existing

NOT FOR PRODUCTION

**Square Footage Calculation:**

Code: Aggregate of all signs NTE 300 sf;
signs are NTE 2sf per lf of facade that sign is on
One sign allowed per frontage
No one sign may exceed 50% of allowed sf
Calculation: 2 * 42' = 84
**Allowed: 84 sf**
**Used: 44.4 sf**
Existing: 48 sf
**Allowed Total: 300 sf**
**Used Total: 241.4 sf**
Sign A: 44.4 sf
Sign B: 36 sf
Sign C: 7.1 sf
Sign D: 90 sf







## D Awning

Scale: 1/4" = 1'-0"

AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**
Awning
(90 Sq Ft)

Qty: 1

Provide new Sunbrella awning fabric per color key.

**Color Key:**
Sunbrella Azure #6069-0000

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

EGAN SIGN
222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name:
30425_Bryant.pdf
Project Number: 30425






AGN AutoGlassNow

**Client:**
Auto Glass Now
440 S. Church Street
Suite 700
Charlotte NC, 28202

**Location Address:**
Auto Glass Now
1810 North Reynolds Road
Bryant, AR 72022

**Description:**

**Color Key:**
- SW 6002 "Essential Gray"
- Black
- SW 6958 "Dynamic Blue"

**Layout Date:**
01/31/2023 - SK/AR

**Revision Date:**
02/21/2023 - JG

P Painting

EGAN SIGN

222 North Kenhorst Boulevard, Reading, PA 19607 | (Toll Free): 844.460.6631 | (Fax): 610.478.1332 | www.egansign.com

This design/engineering proposal will remain the exclusive property of Egan Sign until approved and accepted through purchase by client named directly on drawing and may not be duplicated by other parties or design fee will apply @ $95 per hour.

Sign Management Made Simple

File Name:
30425_Bryant.pdf
Project Number: 30425

**City of Bryant, Arkansas**
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0488, Comdev@cityofbryant.com

# General – Permit Application

*Please complete both pages of this application and submit to the City of Bryant Permitting office, located at the address above.*

*Completed applications can also be scanned and emailed to Comdev@cityofbryant.com.*

Date: 3-20-23

## Permit Type:

| | | |
|---|---|---|
| X Electrical Permit | X Remodel Permit/Addition | _____ Burn Permit |
| _____ Plumbing Permit | _____ Demolition Permit | _____ Site Clearance Permit |
| _____ Mechanical Permit | _____ Accessory Building Permit | _____ Mobile Home Permit |

Other if not listed above I want to add An Addition on to my Existig Office

## Contractor Information:

Contractor/Owner Kt Mac Enterprises LLC

Physical Address of Business 507 Boone Rd

City, State, Zip code Bryant AR 72022

Mailing Address (If different from Above) _____

City, State, Zip code _____

Email Address Kt-Mac@Ktmacenterprises.Co

Business Phone 501-766-7777 Cell Phone 501-366-0841 Fax _____

## Project Information:


Project Address/Location 507 Boone Rd Bryant AR 72022

Project Cost $14,500 Commercial or Residential? Comm

Square footage (If Applicable) 336

If new addition, will foam insulation be used? No ✓ Yes ____ If "Yes", provide technical evaluation report on foam insulation type, and a copy of installer's certification. (Attach to application when submitted)

Additional Project Information Install Sub Floor Structure to South Side of Office 21'x16 Create New Walls & Roof to match Existg Structure Brick New Addition to match, Paint Brick to match, New windows




| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| APPROVED BY: | | | DESIGNED BY: | REV | DESCRIPTION | BY | DATE | NORTH: | SCALE: 0' ' ' GRAPHIC SCALE | NAME: Kt Mac | STRUCTURE TYPE: Office |
| TITLE | SIGNATURE | DATE | DRAWN BY: | | | | | INDICATE NORTH ABOVE | INDICATE SCALE OF GRID ABOVE IN 1" PER FEET EXAMPLE 1" = 50' | ADDRESS: 507 Boone Rd | SQUARE FT: 336 |
| TITLE | SIGNATURE | DATE | CHECKED BY: | | | | | | | STREET: Bryant | LOT SIZE: 4 Acres |
| TITLE | SIGNATURE | DATE | | | | | | | | PHONE: 501-366-0841 | |
| | | | | | | | | | | BRYANT, ARKANSAS 72022 | |


CITY OF BRYANT ARKANSAS Est. 1892

SUBMITTAL DATE:

WORK ORDER NO.:

SHEET NO.: OF

XXX####XXX.DWG




PLACE ELECTRICAL

MARK BLOCKING
DEAD WOOD FOR
R/R

PUT BOX UP

2 1/2 months


School Dr
School Dr

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Patricia and Dr. William Guthrie
Street and Apt. No., or PO Box No.: 1109 B N Reynolds Rd.
City, State, ZIP+4®: Bryant, Ar 72019

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4265

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Benton, AR 72019

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Brenda Johnson
Street and Apt. No., or PO Box No.: 1901 Hidden Valley Dr.
City, State, ZIP+4®: Benton, Ar 72019

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4272

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Kathy Lewallen
Street and Apt. No., or PO Box No.: 307 NW 4th St.
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4289

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Pearcy, AR 71964

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: S & S Smith's Storage, LLC
Street and Apt. No., or PO Box No.: 3020 Airport Rd
City, State, ZIP+4®: Pearcy, Ar 71964

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4296

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Jimmy and Linda Rogers
Street and Apt. No., or PO Box No.: 1000 N Richardson Place Dr.
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4302

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Zachary and Brenda Price
Street and Apt. No., or PO Box No.: 115 Dogwood Place Dr.
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4326

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Stacey and Rodney Barefield
Street and Apt. No., or PO Box No.: 111 Dogwood Place Dr.
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4319

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Bryant, AR 72022

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Andrew and Jessica Wibbelsman
Street and Apt. No., or PO Box No.: 119 Dogwood Place
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4333

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Jonesboro, AR 72401

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Arkansas Early Learning, Inc.
Street and Apt. No., or PO Box No.: 1901 Woodsprings Rd., Suite B
City, State, ZIP+4®: Jonesboro, Ar 72401

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4340

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Benton, AR 72015

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Secured Storage, LLC
Street and Apt. No., or PO Box No.: 2515 Military Rd.
City, State, ZIP+4®: Benton, Ar 72015

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4357

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Little Rock, AR 72204

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Tami Koeneman
Street and Apt. No., or PO Box No.: 4102 Western Hills Ave
City, State, ZIP+4®: Little Rock, Ar 72204

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4364

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Benton, AR 72015

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $4.78 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: Robert and Sheila Rhoades
Street and Apt. No., or PO Box No.: 2515 Military Rd.
City, State, ZIP+4®: Benton, Ar 72015

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4371

---

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Boca Raton, FL 33487

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 20

Postmark Here

MAR 13 2023 USPS 72015

03/13/2023

Sent To: SBA Properties Inc. Attn: Tax Dept.
Street and Apt. No., or PO Box No.: 8051 Congress Ave
City, State, ZIP+4®: Boca Raton, FL 33487

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4388


1109A
CITY OF BRYANT
HEARING
NOTICE

RE-ZONING PETITION

The property located at 1109-A North Reynolds Road in Bryant is being considered for re-zoning from R-E to C-2. The property is more particularly described as follows:

PART OF THE NORTH HALF OF THE SOUTHWEST QUARTER (N1/2 SW1/4) OF SECTION 27, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **BEGINNING** AT A COMPUTED POINT IN THE CENTERLINE OF HIGHWAY #183 (NORTH REYNOLDS ROAD), WHICH IS 480 WEST AND 225 FEET SOUTH OF THE NORTHEAST CORNER OF THE SAID N1/2 SW1/4; THENCE S14°37'49"E - 207.85 FEET ALONG SAID CENTERLINE OF HIGHWAY #183 TO A COMPUTED POINT; THENCE LEAVING SAID CENTERLINE OF HIGHWAY #183, N88°10'53"W - 399.64 FEET TO A FOUND 5/8" REBAR; THENCE N1°41'58"E - 198.93 FEET TO A FOUND BENT 1/2" REBAR; THENCE S88°15'00"E - 341.20 FEET TO THE **POINT OF BEGINNING**, CONTAINING 1.69 ACRES, MORE OR LESS. SUBJECT TO A RIGHT OF WAY FOR (HIGHWAY #183) REYNOLDS ROAD AND UTILITY EASEMENT ALONG EAST LINE. ALSO SUBJECT TO A 10 FOOT EASEMENT FOR A DRIVEWAY.

A petition has been filed with the City of Bryant Planning Commission to re-zone the property. As part of this process a public hearing will be held April 10th, 2023 at 6:00 p.m. in the Bryant City Office Complex, 210 Southwest 3rd Street, Bryant, Arkansas 72022.

Public comments will be accepted at that time regarding this re-zoning. Since you own property within 300 feet of the tract in consideration, you have been sent this notice via certified mail as required by city ordinance.

Should you have any questions regarding this matter you may contact the City of Bryant at 501-943-0301 and ask for Truett Smith or by contacting me at the information listed below.

Vernon Williams, P.E.
GarNat Engineering, LLC
501-408-4650
garnatengineering@gmail.com

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018

March 8, 2023

Mr. Truett Smith
Bryant Planning Coordinator/Planning Commission Secretary
210 SW 3rd Street
Bryant, AR 72022

Re: Rezone Application – 1109-A North Reynolds Road Parcel Number 840-14297-000

Dear Mr. Smith:

Please allow this letter and following list of enclosures to serve as my application for rezone of the referenced property located at 1109-A North Reynolds Road. We are seeking a rezone from R-E to C-2 to build chiropractic center on the property. It is my desire that this matter be included on the agenda for your April 2023 City of Bryant Planning Commission Meeting.

List of Enclosures

- Affidavit
- Rezone Application
- Rezone – Public Notice
- Property Survey

If you have questions or need any additional information, please do not hesitate to contact me.

Sincerely,
GarNat Engineering, LLC

Vernon J. Williams

Vernon J. Williams, P.E., President

**LEGEND**

- Computed point
- Found monument
- Set #4 RB/Plas. Cap
- (M)-Measured
- (R)-Recorded Survey
- (P)-Platted
- -Power Pole
- -Sanitary Sewer
- -Water Valve
- -Storm Drain
- -Telephone Ped.
- -Water Meter
- -Gas Meter
- -Asphalt
- -Gravel
- -Concrete


PART OF THE NORTH HALF OF THE SOUTHWEST QUARTER (N1/2 SW1/4) OF SECTION 27, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **BEGINNING** AT A COMPUTED POINT IN THE CENTERLINE OF HIGHWAY #183 (NORTH REYNOLDS ROAD), WHICH IS 480 WEST AND 225 FEET SOUTH OF THE NORTHEAST CORNER OF THE SAID N1/2 SW1/4; THENCE S14°37'49"E - 207.85 FEET ALONG SAID CENTERLINE OF HIGHWAY #183 TO A COMPUTED POINT; THENCE LEAVING SAID CENTERLINE OF HIGHWAY #183, N88°10'53"W - 399.64 FEET TO A FOUND 5/8" REBAR; THENCE N1°41'58"E - 198.93 FEET TO A FOUND BENT 1/2" REBAR; THENCE S88°15'00"E - 341.20 FEET TO THE **POINT OF BEGINNING**, CONTAINING 1.69 ACRES, MORE OR LESS. SUBJECT TO A RIGHT OF WAY FOR (HIGHWAY #183) REYNOLDS ROAD AND UTILITY EASEMENT ALONG EAST LINE. ALSO SUBJECT TO A 10 FOOT EASEMENT FOR A DRIVEWAY.







12-12-22




**DOCUMENTS USED FOR THE PREPARATION OF THIS SURVEY:**

- PREVIOUS SURVEY BY HOPE CONSULTING DATED 10/24/95

**CERTIFICATIONS:**

BY AFFIXING MY SEAL AND SIGNATURE, I GEORGE P. WOODEN, PS NO.1573, HEREBY CERTIFY THAT THIS DRAWING CORRECTLY DEPICTS A SURVEY COMPILED UNDER MY SUPERVISION ON AUG 16, 2020.

THIS SURVEY WAS BASED ON LEGAL DESCRIPTIONS AND TITLE WORK FURNISHED BY OTHERS AND DOES NOT REPRESENT A TITLE SEARCH.

THIS PROPERTY IS NOT LOCATED IN THE 100 YEAR FLOOD PLAIN. THE PROPERTY SHOWN ON THIS PLAT IS LOCATED IN ZONE "X" OF THE F.E.M.A. MAP PANEL 05125C0380D EFFECTIVE DATE JUNE 19, 2012.

**BASIS OF BEARINGS:**

BEARINGS ARE BASED UPON NORTH AMERICAN DATUM 1983, ARKANSAS SOUTH ZONE, US SURVEY FEET, GRID COORDINATES. COORDINATES WERE ESTABLISHED USING GPS AND WERE PROCESSED USING THE NATIONAL GEODETIC SURVEY'S "ONLINE POSITIONING USER SERVICE" (OPUS).

BOUNDARY/
TOPOGRAPHIC
SURVEY

1109 N REYNOLDS ROAD
BRYANT, ARKANSAS
72202
SALINE COUNTY

FOR THE USE &
BENEFIT OF:

KENNY WHITFIELD


**GNE** Designing our client's success

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018
Ph (501) 408-4650

3825 Mt. Carmel Rd
Bryant, AR 72022
garnatengineering@gmail.com


PROJECT NO:
22203

DATE:
DEC. 12, 2022

# AFFIDAVIT

I, Michael Butler, Butler Wealth Capital, LLC certify by my signature below that I hereby authorize Vernon Williams of GarNat Engineering, LLC to act as Butler Wealth Capital, LLC's agent regarding the Planning Commission Approval of the proposed development at 1109 N Reynolds Road.

Michael Butler
Butler Wealth Capital, LLC

03/07/2023
Date

Subscribed and sworn to me a Notary Public on this 7TH day of MARCH, 2023.

Notary Public

My Commission Expires:

02-05-2031

GEORGE P. WOODEN
Notary Public-Arkansas
Saline County
My Commission Expires 02-05-2031
Commission # 12714343

7022 2410 0002 8609 4791

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bentonville, AR 72712

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $1.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

MAR 17 2023 USPS POST OFFICE 72015

03/18/2023

Sent To: LCL Properties, LLC
Street and Apt. No., or PO Box No.: 3525 Highway 5 N, Suite 100
City, State, ZIP+4®: Bryant, Ar 72019

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4814

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $0.00 |
| Postage | |
| Total Postage and Fees | |

0315 8

Postmark Here

MAR 17 2023 BENTON POST OFFICE 72015

Sent To: Bryant School District 25
Street and Apt. No., or PO Box No.: 200 NW 4rth St
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4784

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Alexander, AR 72002

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

MAR 17 2023 BENTON POST OFFICE 72015

03/18/2023

Sent To: Jouce Hillard
Street and Apt. No., or PO Box No.: 410 Hilldale Rd
City, State, ZIP+4®: Alexander, Ar 72002

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4807

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

MAR 17 2023 BENTON POST OFFICE 72015

03/18/2023

Sent To: City of Bryant
Street and Apt. No., or PO Box No.: 210 Southwest 3rd St
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4760

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Alexander, AR 72002

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

MAR 17 2023 BENTON POST OFFICE 72015 USPS

03/18/2023

Sent To: David Bullock
Street and Apt. No., or PO Box No.: 2207 Hilltop Rd
City, State, ZIP+4®: Alexander, Ar 72007

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4777

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Alexander, AR 72002

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | |
| ☐ Return Receipt (hardcopy) | $3.35 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

MAR 17 2023 USPS

03/18/2023

Sent To: Ricky and Glennie Castleberry
Street and Apt. No., or PO Box No.: 350 Hilldale Rd
City, State, ZIP+4®: Alexander, Ar 72002

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4739

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Benton, AR 72019

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: Neil and Amy Arnold
Street and Apt. No., or PO Box No.: 3754 Quail Ln
City, State, ZIP+4®: Benton, Ar 72019

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4753

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: Prosper Properties, LLC
Street and Apt. No., or PO Box No.: 612 W. Commerce Suite 2
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4722

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: Joseph and Joan Brack
Street and Apt. No., or PO Box No.: 1995 Henry Ave
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4746

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: AF Partners, LLC
Street and Apt. No., or PO Box No.: 1511 N. Reynolds Rd.
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4708

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: James and Melaina Whitley
Street and Apt. No., or PO Box No.: 1983 Henry Ave
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4715

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Cave Springs, AR 72718

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| Extra Services & Fees (check box, add fee as appropriate) | $3.35 |
| ☐ Return Receipt (hardcopy) | $0.00 |
| ☐ Return Receipt (electronic) | $0.00 |
| ☐ Certified Mail Restricted Delivery | $0.00 |
| ☐ Adult Signature Required | $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| Total Postage and Fees | $8.13 |

0315 8

Postmark Here

BENTON POST OFFICE MAR 17 2023 USPS

03/18/2023

Sent To: Stephen and Sheryl Brack
Street and Apt. No., or PO Box No.: 209 Deere Run Dr.
City, State, ZIP+4®: Cave Springs, Ar 72718

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4678

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

Postmark Here

BENTON POST OFFICE 72015 MAR 17 2023 USPS

03/18/2023

Sent To: Christopher and Holly Sory
Street and Apt. No., or PO Box No.: 2103 Magna Carta Ln
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4692

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Little Rock, AR 72223

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

BENTON POST OFFICE 72015 MAR 17 2023 USPS

Postmark Here

03/18/2023

Sent To: Rock Town Realty Group, LLC
Street and Apt. No., or PO Box No.: 8816 Ranch Blvd
City, State, ZIP+4®: Little Rock, Ar 72223

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4654

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

BENTON POST OFFICE 72015 MAR 17 2023 USPS

Postmark Here

03/18/2023

Sent To: Cathy Hensley
Street and Apt. No., or PO Box No.: 5405 William Ln
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4661

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

MAR 17 2023

Postmark Here

USPS

03/18/2023

Sent To: Rodney Fortner
Street and Apt. No., or PO Box No.: 5401 William Ln
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4647

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

BENTON POST OFFICE 72015 MAR 17 2023 USPS

Postmark Here

03/18/2023

Sent To: Ruqin Zhu
Street and Apt. No., or PO Box No.: 5409 William Ln
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

7022 2410 0002 8609 4685

**U.S. Postal Service™**
**CERTIFIED MAIL® RECEIPT**
*Domestic Mail Only*

For delivery information, visit our website at *www.usps.com®*.

Bryant, AR 72022

OFFICIAL USE

| | |
|---|---|
| Certified Mail Fee | $4.15 |
| $ | $3.35 |
| Extra Services & Fees *(check box, add fee as appropriate)* | |
| ☐ Return Receipt (hardcopy) | $ $0.00 |
| ☐ Return Receipt (electronic) | $ $0.00 |
| ☐ Certified Mail Restricted Delivery | $ $0.00 |
| ☐ Adult Signature Required | $ $0.00 |
| ☐ Adult Signature Restricted Delivery | $ |
| Postage | $0.63 |
| $ | |
| Total Postage and Fees | $8.13 |
| $ | |

0315 8

BENTON POST OFFICE 72015 MAR 17 2023 USPS

Postmark Here

03/18/2023

Sent To: Nicholas and Tequila Quarles
Street and Apt. No., or PO Box No.: 1998 Henry Ave
City, State, ZIP+4®: Bryant, Ar 72022

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Nicholas and Tequila Quarles
1998 Henry Ave
Bryant, Ar 72022

9590 9402 5082 9092 2114 76

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4685

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature
X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* T Quarles — C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

BENTONVILLE POST OFFICE 2015
MAR 25 2023
USPS

3. Service Type
- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 — Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

LCL Properties, LLC
3525 Highway 5 N
Suite 100
Bryant, Ar 72019

9590 9402 5082 9092 2115 82

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4791

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature
X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* — C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type
- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 — Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Rodney Fortner
5401 William Ln
Bryant, Ar 72022

9590 9402 5082 9092 2114 52

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4661

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature
X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* RD Fortner — C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

BENTONVILLE POST OFFICE 2015
MAR 21 2023
USPS

3. Service Type
- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 — Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Stephen and Sheryl Brack
209 Deere Run Dr.
Cave Springs, Ar 72718

9590 9402 5082 9092 2115 06

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4715

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* | C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery
- 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

AF Partners, LLC
1511 N. Reynolds Rd
Bryant, Ar 72022

9590 9402 5082 9092 2115 37

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4746

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* Bobby Gabbard | C. Date of Delivery 3/20/23

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery
- 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Cathy Hensley
5405 William Ln
Bryant, Ar 72022

9590 9402 5082 9092 2114 45

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4654

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X Cathy J. Hensley ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* Cathy J. Hensley | C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- ☐ Mail Restricted Delivery
- 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

City of Bryant
210 SW 3rd St
Bryant, Ar 72022

9590 9402 5082 9092 2115 99

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4807

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* | C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Insured Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

James and Melaina Whitley
1983 Henry Ave
Bryant, Ar 72022

9590 9402 5082 9092 2114 90

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4708

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X Melaina Whitley ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* Melaina Whitley | C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Insured Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Joseph and Joan Brack
1995 Henry Ave
Bryant, Ar 72022

9590 9402 5082 9092 2115 13

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4722

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

X [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* JOAN BRACK | C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

BRYANT POST OFFICE 72015 MAR 23 2023 USPS

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Insured Mail
- ☐ Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Re

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

David Bullock
2207 Hilltop Rd
Alexander, Ar 72007

9590 9402 5082 9092 2115 51

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4760

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

x [signature] ☐ Agent ☒ Addressee

B. Received by *(Printed Name)* JD Bullock

C. Date of Delivery 3/22/2023

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☒ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt

**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Ruqin Zhu
5409 William Ln
Bryant, Ar 72022

9590 9402 5082 9092 2114 38

2. Article Number *(Transfer from service label)*

7022 2410 0002 8609 4647

**COMPLETE THIS SECTION ON DELIVERY**

A. Signature

x [signature] ☐ Agent ☐ Addressee

B. Received by *(Printed Name)* RUQIN ZHU

C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

BENTONVILLE POST OFFICE 2015 MAR 22 2023 USPS

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ■ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery
- ☐ Mail
- Mail Restricted Delivery 00)
- ☐ Priority Mail Express®
- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

PS Form 3811, July 2015 PSN 7530-02-000-9053 Domestic Return Receipt


CHRISTY LN
CITY OF BRYANT
HEARING
NOTICE

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018

March 10, 2023

Mr. Truett Smith
Bryant Planning Coordinator/Planning Commission Secretary
210 SW 3rd Street
Bryant, AR 72022

Re: Rezone Application – A New Elite Volleyball Academy Gym
Parcel Number 840-11661-034

Dear Mr. Smith:

Please allow this letter and following list of enclosures to serve as my application for rezone of the referenced property located near intersection of Bryant Pkwy & Henry Ave. We are seeking a rezone from R-2 to C-2 to build a volleyball academy. It is my desire that this matter be included on the agenda for your April 2023 City of Bryant Planning Commission Meeting.

List of Enclosures


- Affidavit
- Rezone Application
- Rezone – Public Notice
- Property Survey

If you have questions or need any additional information, please do not hesitate to contact me.

Sincerely,
GarNat Engineering, LLC

Vernon J. Williams

Vernon J. Williams, P.E., President




SURVEY LEGEND
- △ - Computed point
- ● - Found monument
- ⊙ - Set #4 RB/Plas. Cap
- (M)-Measured
- (R)-Record
- (P)-Platted

# VERNIA PARK NORTHEAST SUBDIVISION PHASE 1 FINAL PLAT

## PLAT CERTIFICATES:

**OWNER:**
**Name:** EVA Real Estate, LLC
**Address:** P.O. Box 241273, Little Rock, AR 72223

**DEVELOPER:**
**Name:** EVA Real Estate, LLC
**Address:** P.O. Box 241273, Little Rock, AR 72223

**CERTIFICATE OF RECORDING:**

**CERTIFICATE OF OWNER:**
We, the undersigned, owners of the real estate shown and described herein do hereby certify that we have laid off, platted and subdivided, and do hereby lay off, plat and subdivide said real estate in accordance with the within plat.

Date: _____ Signed: _____
Tanja Eckart
EVA Real Estate, LLC

Source of Title: SALINE COUNTY, ARKANSAS
Saline County Document# _____

**CERTIFICATE OF ENGINEERING ACCURACY:**

I, Vernon J. Williams, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their locations, size, type, and material are correctly shown; and that all requirements of the City of Bryant Subdivision Rules and Regulations have been fully complied with.

Date: _____ Signed: _____
Vernon J. Williams
Registered Professional Engineer
No. 9551, Arkansas

**CERTIFICATE OF SURVEYING ACCURACY:**

I, George P. Wooden, hereby certify that this plat correctly represents a boundary survey made by me or under my supervision; that the boundary lines shown hereon correspond with the description in the deeds cited in the above Source of Title; and that all monuments which were found or placed on the property are correctly described and located.

Date: _____ Signed: _____
George P. Wooden
Registered Land Surveyor
No. 1573, Arkansas

**CERTIFICATE OF FINAL PLAT APPROVAL:**

Pursuant to the City of Bryant Subdivision Rules and Regulations, this document was given approval by the Bryant Planning Commission. All of the document is hereby accepted, and this certificate executed under the authority of said rules and regulations.

Date: _____ Signed: _____
Rick Johnson, Chairman
Bryant Planning Commission


30' 15' 0 30'

SURVEY PLAT CODE:
500-01S-14W-0-14-410-62-1573

STATE OF ARKANSAS
REGISTERED PROFESSIONAL ENGINEER
VERNON J. WILLIAMS
NO. 9551

GarNat Engineering, LLC
No. 2174
CERTIFICATE OF AUTHORIZATION
ARKANSAS

## VICINITY MAP




## PROPERTY DESCRIPTION:

**LOT 1 - 2.12 ACRES (92,562 SQUARE FEET)**
PART OF THE SOUTHEAST QUARTER OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER (SE1/4 NE1/4 NW1/4) AND PART OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER (NE1/4 NE1/4 NW1/4) ALL IN SECTION 14, TOWNSHIP 01 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **BEGINNING** AT A FOUND 5/8" REBAR FOR THE NORTHEAST CORNER OF THE SAID SE1/4 NE1/4 NW1/4; THENCE S 02°48'16" W, ALONG THE EAST LINE OF SAID SE1/4 NE1/4 NW1/4, FOR A DISTANCE OF 285.27 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE N 87°17'45" W, LEAVING SAID EAST LINE, A DISTANCE OF 256.91 FEET TO A SET 1/2" REBAR WITH CAP #1573 LOCATED ON THE EAST RIGHT OF WAY LINE OF CHRISTY LANE; THENCE ALONG THE SAID EAST RIGHT OF WAY THE FOLLOWING CALLS: THENCE ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 170 FEET AND A LENGTH OF 131.23 FEET, WHOSE CHORD BEARS N 02°06'14" E - 128.00 FEET, THENCE N 24°13'08" E - 50.00 FEET, THENCE ALONG A CURVE TO THE LEFT WITH A RADIUS OF 180 FEET AND A LENGTH OF 89.20 FEET, WHOSE CHORD BEARS N 10°01'23" E - 88.29 FEET, THENCE N 04°10'22" W - 31.53 FEET TO A SET 1/2" REBAR WITH CAP #1573 LOCATED AT THE INTERSECTION WITH THE SOUTH RIGHT OF WAY OF HENRY AVENUE; THENCE ALONG THE SAID SOUTH RIGHT OF WAY THE FOLLOWING CALLS: THENCE ALONG A CURVE TO THE LEFT WITH A RADIUS OF 185.26 FEET AND A LENGTH OF 35.40 FEET, WHOSE CHORD BEARS N 67°21'34"E - 35.35 FEET, THENCE N 53°12'17" E - 42.41 FEET, THENCE N 41°44'12" E - 35.22 FEET, THENCE ALONG A CURVE TO THE RIGHT WITH A RADIUS OF 181.54 FEET AND A LENGTH OF 140.23 FEET, WHOSE CHORD BEARS N 64°03'28" E - 136.77 FEET, THENCE S 86°48'21" E - 26.60 FEET TO A FOUND 1/2" REBAR LOCATED ON THE EAST LINE OF THE SAID NE1/4 NE1/4 NW1/4; THENCE S 02°55'14" W, LEAVING SAID SOUTH RIGHT OF WAY OF HENRY AVENUE AND ALONG THE EAST LINE OF THE SAID NE1/4 NE1/4 NW1/4 FOR A DISTANCE OF 142.90 FEET TO THE **POINT OF BEGINNING**, CONTAINING 2.12 ACRES, MORE OR LESS. SUBJECT TO ANY EASEMENTS OF RECORD AND THE RIGHTS OF WAY OF HENRY AVENUE AND CHRISTY LANE. LESS AND EXCEPT RIGHT OF WAY DEDICATION BELOW.

**RIGHT OF WAY DEDICATION - 0.004 ACRES (187 SQUARE FEET)**
PART OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF THE NORTHWEST QUARTER (NE1/4 NE1/4 NW1/4) SECTION 14, TOWNSHIP 01 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS: **COMMENCING** AT A FOUND 5/8" REBAR FOR THE SOUTHEAST CORNER OF THE SAID NE1/4 NE1/4 NW1/4; THENCE N 87°44'28" W, ALONG THE SOUTH LINE OF SAID NE1/4 NE1/4 NW1/4, FOR A DISTANCE OF 231.75 FEET TO A COMPUTED POINT ON THE EAST RIGHT OF WAY OF CHRISTY LANE FOR THE **POINT OF BEGINNING**; THENCE CONTINUING N 87°44'28" W, ALONG SAID SOUTH LINE, A DISTANCE OF 47.39 FEET TO A POINT OF INTERSECTION WITH THE SOUTH RIGHT OF WAY OF HENRY AVENUE; THENCE ALONG SAID SOUTH RIGHT OF WAY AND A CURVE TO THE LEFT WITH A RADIUS OF 185.26 FEET AND A LENGTH OF 47.46 FEET, WHOSE CHORD BEARS N 80°10'21" E - 47.33 FEET TO A SET 1/2" REBAR WITH CAP #1573; THENCE S 04°10'22" E, LEAVING SAID SOUTH RIGHT OF WAY OF HENRY AVENUE FOR A DISTANCE OF 9.97 FEET TO THE **POINT OF BEGINNING**, CONTAINING 0.004 ACRES (187 SQUARE FEET), MORE OR LESS.

## PROPERTY SPECIFICATIONS:

ZONING CLASSIFICATION: C-2

SOURCE OF WATER: CITY OF BRYANT
SOURCE OF SEWER: CITY OF BRYANT

BUILDING SETBACKS (SB):
FRONT - 15'
REAR - 25'
INTERIOR (SIDE) - 15' UNLESS OTHERWISE NOTED
EXTERIOR - 15'

LOT CORNERS: SET #4 REBAR WITH CAP

## DOCUMENTS USED:

- VERNIA PARK SUBDIVISION PHASE 1 FINAL PLAT BY ZANE ROBBINS PLS #1853

## BASIS OF BEARINGS:

BENCHMARK(S) PROVIDED ARE REBAR AND COORDINATES ON BENCHMARKS ARE NORTH AMERICAN DATUM 1983, ARKANSAS SOUTH ZONE, US SURVEY FEET, GRID COORDINATES AND ELEVATIONS ARE NAVD 1988. COORDINATES AND ELEVATIONS WERE ESTABLISHED USING GPS AND WERE PROCESSED USING THE NATIONAL GEODETIC SURVEY'S "ONLINE POSITIONING USER SERVICE" (OPUS).

## CERTIFICATIONS:

BY AFFIXING MY SEAL AND SIGNATURE, I GEORGE P. WOODEN, PS NO.1573, HEREBY CERTIFY THAT THIS DRAWING CORRECTLY DEPICTS A SURVEY COMPILED UNDER MY SUPERVISION ON MARCH 10, 2023.

THIS SURVEY WAS BASED ON LEGAL DESCRIPTIONS AND TITLE WORK FURNISHED BY OTHERS AND DOES NOT REPRESENT A TITLE SEARCH.

THIS PROPERTY IS NOT LOCATED IN THE 100 YEAR FLOOD PLAIN. THE PROPERTY SHOWN ON THIS PLAT IS LOCATED IN ZONE "X" OF THE F.E.M.A. MAP PANEL 05125C0240E EFFECTIVE DATE JUNE 05, 2020.

| BY | REVISION | DATE |
|---|---|---|
| | | |

GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com

VERNIA PARK NORTHEAST
SUBDIVISION PHASE 1
HENRY AVENUE
BRYANT, ARKANSAS 72019

STATE OF ARKANSAS
REGISTERED PROFESSIONAL SURVEYOR
NO. 1573
SIGNATURE
GEORGE P. WOODEN
DRAFT

CONTENTS:
FINAL PLAT

PROJECT NO:
22140

DATE:
MARCH 10, 2023

SHEET NO:
V1.0

a:\Projects\2022 Projects\22140 Vernia Office Park\Drawings\Survey\22140-John Eckert-New Lot-Subdivision-030323.dwg

**NOTICE OF PUBLIC HEARING**

A public hearing will be held on Monday, 4/10/2023 at 6:00 P.M. at the Bryant City Complex, 210 Southwest 3 Street. City of Bryant. Saline County, for the purpose of public comment on a conditional use request at the site of 3113 Whispering Oak Bryant, AR 72022. A legal description of the property can be obtained by contacting the Bryant Department of Community Development.

Rick Johnson
Chairman Board of Zoning Adjustment
City of Bryant

**City of Bryant, Arkansas**
Community Development
210 SW 3rd Street Bryant, AR 72022
501-943-0943

# Conditional Use Permit Application

Applicants are advised to read the Conditional Use Permit section of Bryant Zoning Code prior to completing and signing this form. The Zoning Code is available at www.cityofbryant.com under the Planning and Community Development tab.

Date: 12/6/2022

**Applicant or Designee:**

Name Kelly Tucker
Address 9020 Chicot Road
Phone (501)912-7964
Email Address: kellytucker50@gmail.com

**Project Location:**

Property Address 3113 Whispering Oak Street Bryant, AR 72022
Parcel Number 840-08686-000
Zoning Classification _____

**Property Owner (If different from Applicant):**

Name Kelly Tucker
Phone (501)912-7964
Address 9020 Chicot Road, Little Rock, AR 72209
Email Address kellytucker50@gmail.com

**Additional Information:**

Legal Description (Attach description if necessary)
Lot 17, Block 3, Sherwood Estates in the City of Bryant

Description of Conditional Use Request (Attach any necessary drawings or images)
Duplex

Proposed/Current Use of Property vacant lot

# Application Checklist

**Requirements for Submission**

- ☐ Letter stating request of Conditional Use and reasoning for request
- ☐ Completed Conditional Use Permit Application
- ☐ Submit Conditional Use Permit Application Fee ($125)
- ☐ Submit Copy of completed Public Notice
- ☐ Publication: Public Notice shall be published at least one (1) time fifteen (15) days prior to the public hearing at which the variance will be heard. Once published please provide a proof of publication to the Community Development office.
- ☐ Posting of Property: The city shall provide a sign to post on the property involved for the fifteen (15) consecutive days leading up to Public hearing. One (1) sign is required for every two hundred (200) feet of street frontage.
- ☐ Submit eight (8) Copies of the Development Plan (Site Plan) showing:
  - Location, size, and use of buildings/signs/land or improvements
  - Location, size, and arrangement of driveways and parking. Ingress/Egress
  - Existing topography and proposed grading
  - Proposed and existing lighting
  - Proposed landscaping and screening
  - Use of adjacent properties
  - Scale, North Arrow, Vicinity Map
  - Additional information that may be requested by the administrative official due to unique conditions of the site.

**Once the application is received, the material will be reviewed to make sure all the required information is provided. The applicant will be notified if additional information is required. The application will then go before the Development and Review Committee (DRC) for a recommendation to the Planning Commission. A public hearing will be held at this meeting for comments on the Conditional Use. After the public hearing, the Planning Commission will make a decision on the use.**

**Note: that this is not an exhaustive guideline regarding the Conditional Use Permit Process. Additional information is available in the Bryant Zoning Ordinance.**

**READ CAREFULLY BEFORE SIGNING**

I Kelly Tucker, do hereby certify that all information contained within this application is true and correct. I further certify that the owner of the property authorizes this proposed application. I understand that I must comply with all City Codes and that it is my responsibility to obtain all necessary permits required.

Kelly Tucker

9020 Chicot Road

Little Rock, AR 72209

To: Bryant Development and Review Committee

We are requesting a Conditional Use Permit at the Property located at 3113 Whispering Oak Drive in Bryant Arkansas. We are going to build a 3 bedroom 2 bath duplex at that location. If you need any other information, please call me at 501-912-7964.

Sincerely,



Kelly Tucker

Kellytucker50@gmail.com

# NOTICE OF PUBLIC HEARING

A public hearing will be held on Monday, 6/10/2023 at 6:00 P.M. at the Bryant City Complex, 210 Southwest 3 Street. City of Bryant. Saline County, for the purpose of public comment on a conditional use request at the site of 3113 Whispering Oak Bryant, AR 72022. A legal description of the property can be obtained by contacting the Bryant Department of Community Development.

Rick Johnson
Chairman Board of Zoning Adjustment
City of Bryant

**LAHA ENGINEERS, INC.**
6602 Baseline Road Suite E
P. O. Box 190251
Little Rock, Arkansas 72219
501-565-7384
Fax 501-562-5467
e-mail: lahaengrls@sbcglobal.net



LEGAL DESCRIPTION: LOT 11 BLOCK 3 SHERWOOD ESTATES
BRYANT, SALINE COUNTY, ARKANSAS

This area is in zone AE and not in the 100 year flood zone per Community-Panel No. 050448 0250 B effective date of November xx 19xx.

Propoesed improvements are as shown.
The Concrete Slab encroaches over the South Line. No other visible encroachments noted.

For use and Benefit of: Kelly Tucker
Address of Property: 3113 Whispering Oaks Street, Bryant, AR
Date of Survey: October 5, 2022
Scale: 1" = 20'

This is to certify that the property described hereon has been surveyed and corners set in accordance with located and accepted monuments in the area. This certification limited to the parties shown hereon.




CERTIFICATION OF AUTHORIZATION
LAHA ENGINEERS INC
#727
ARKANSAS ENGINEER

REGISTERED
STATE OF ARKANSAS
NO. 284
SIGNATURE
TROY D. LAHA
PROFESSIONAL LAND SURVEYOR

NOTE:
Finished floor of building should be 2' above existing grade.
Slope away from building at 10%.

FILE: DesignCAD 2D 2021 64-bit [kellytp:main]

# Order Receipt

**Saline Courier**

321 N. Market St.
Benton, AR 72015

Phone: 501-315-8228

URL: https://www.bentoncourier.com/

GarNat Engineering LLC (28)
PO Box 116
Benton, AR 72018

| | |
|---|---|
| Acct #: | 01118778 |
| Phone: | (501)408-4650 |
| Date: | 03/15/2023 |
| Ad #: | 00158612 |
| Salesperson: | SCL |
| Ad Taker: | SC5 |

Class: 101

Ad Notes:

Sort Line: NOTICE OF PUBLIC HEARING A pu

| Description | Amount |
|---|---|
| AVDT LEGAL AFFIDAVIT | 4.50 |
| 28 Saline Courier 2023-03-18 | 39.00 |

Ad Text:

NOTICE OF PUBLIC HEARING

A public hearing will be held on Monday, April 10, 2023 at 6:00 P.M. at the Bryant City Office Complex, 210 Southwest 3rd Street, City of Bryant, Saline County, for the purpose of public comment on a conditional use request at 520 and 522 Valley View Drive. A legal description of this property can be obtained by contacting the Bryant Department of Community Development.

Rick Johnson
Chairman Board of Zoning Adjustment
City of Bryant

Payment Reference:

| | |
|---|---|
| Total: | 43.50 |
| Tax: | 0.00 |
| Net: | 43.50 |
| Prepaid: | 0.00 |
| Total Due | **43.50** |

# AFFIDAVIT

I, Bobby G. Wright, Trustee of the Bobby G. Wright and Mary L. Wright Trust, dated April 9, 1999 certify by my signature below that I hereby authorize Vernon Williams of GarNat Engineering, LLC to act as the Bobby G. Wright and Mary L. Wright Trust's agent regarding the Conditional Use Application for Lots 89R and 90R of Pikewood Subdivision to Saline County, Arkansas.

Bobby G. Wright
Trustee
Bobby G. Wright and Mary L. Wright Trust

2/8/23
Date

Subscribed and sworn to me a Notary Public on this 8TH day of FEBRUARY, 2023.


George P. Wooden
Notary Public

My Commission Expires:

GEORGE P. WOODEN
Notary Public-Arkansas
Saline County
My Commission Expires 02-05-2031
Commission # 12714343

LEGEND

△ - Computed point
● - Found monument
⊙ - Set #4 RB/Plas. Cap
(M)-Measured
(R)-Record
(P)-Platted




SURVEY PLAT CODE:
500-01S-15W-0-18-440-62-1573

100' 50' 0 100'

| DOCUMENTS USED FOR THE PREPARATION OF THIS SURVEY: | PROPERTY DESCRIPTION: |
|---|---|
| • REPLAT OF LOTS 88, 89, 90, AND 91, PIKEWOOD SUBDIVISION | • LOTS 89-R AND 90-R OF THE JANUARY 1991 REPLAT OF LOTS 88, 89, 90, AND 91 AND THE EAST 10 FEET OF LOT 92, PIKEWOOD SUBDIVISION, TO SALINE COUNTY, ARKANSAS |

## CERTIFICATIONS:

BY AFFIXING MY SEAL AND SIGNATURE, I GEORGE P. WOODEN, PS NO.1573, HEREBY CERTIFY THAT THIS DRAWING CORRECTLY DEPICTS A SURVEY COMPILED UNDER MY SUPERVISION ON FEB 03, 2023.

THIS SURVEY WAS BASED ON LEGAL DESCRIPTIONS AND TITLE WORK FURNISHED BY OTHERS AND DOES NOT REPRESENT A TITLE SEARCH.

THIS PROPERTY IS NOT LOCATED IN THE 100 YEAR FLOOD PLAIN. THE PROPERTY SHOWN ON THIS PLAT IS LOCATED IN ZONE "X" OF THE F.E.M.A. MAP PANEL 05125C0380E EFFECTIVE DATE JUNE 05, 2020.

## BASIS OF BEARINGS:

BEARINGS ARE BASED UPON NORTH AMERICAN DATUM 1983, ARKANSAS SOUTH ZONE, US SURVEY FEET, GRID COORDINATES. COORDINATES WERE ESTABLISHED USING GPS AND WERE PROCESSED USING THE NATIONAL GEODETIC SURVEY'S "ONLINE POSITIONING USER SERVICE" (OPUS).

CERTIFICATE OF AUTHORIZATION
GarNat Engineering, LLC.
No. 2174
ARKANSAS

REGISTERED PROFESSIONAL SURVEYOR
STATE OF ARKANSAS
NO. 1573
SIGNATURE
GEORGE P. WOODEN

2-3-23


**GNE** Designing our client's success

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018
Ph (501) 408-4650

3825 Mt Carmel Rd
Bryant, AR 72022
garnatengineering@gmail.com


CONTENTS: LOT SURVEY

520 & 522
VALLEY VIEW DRIVE
BRYANT, ARKANSAS
72022
SALINE COUNTY

FOR THE USE & BENEFIT OF:

BOBBY WRIGHT

PROJECT NO: 23016

DATE: FEB. 03, 2023

# NOTICE OF PUBLIC HEARING

A public hearing will be held on Monday, March 13, 2023 at 6:00 P.M. at the Bryant City Office Complex, 210 Southwest 3rd Street, City of Bryant, Saline County, for the purpose of public comment on a conditional use request at 520 and 522 Valley View Drive. A legal description of this property can be obtained by contacting the Bryant Department of Community Development.

Rick Johnson

Chairman Board of Zoning Adjustment

City of Bryant

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018

February 8, 2023

Mr. Truett Smith
Bryant Planning Coordinator/Planning Commission Secretary
210 SW 3rd Street
Bryant, AR 72022

Re: Conditional Use Application – Lots 89R and 90R of Pikewood Subdivision

Dear Mr. Smith:

Please allow this letter and following list of enclosures to serve as my application for conditional use of the referenced lots located at 520 and 522 Valley View Drive. We are seeking conditional use to build duplexes on the property. It is my desire that this matter be included on the agenda for your March 2023 City of Bryant Planning Commission Meeting.

List of Enclosures

- Affidavit
- Conditional Use Application
- Conditional Use Application Fees $250.00
- Conditional Use – Public Notice
- Property Survey

If you have questions or need any additional information, please do not hesitate to contact me.

Sincerely,
GarNat Engineering, LLC

Vernon J. Williams

Vernon J. Williams, P.E., President

PH: (501)408-4650 FX: (888) 900-3068 www.garnatengineering.com

CURRENT ZONING R-1

CURRENT ZONING C-2

CURRENT ZONING R-E

CURRENT ZONING C-3

LIGHT POST WITH T4 OPTICS WITH DIRECTIONAL TOWARD DRIVEWAYS

EXISTING TREE BUFFER

75' BUILDING SETBACK LINE

25' BUILDING SETBACK LINE

15' BUILDING SETBACK LINE

DETENTION AREA

21.61 ACRES
941185 Sq. Ft.

2.71 ACRES
8078 Sq. Ft.

10577 Sq. Ft.
11920 Sq. Ft.
8640 Sq. Ft.
11340 Sq. Ft.
11960 Sq. Ft.
11960 Sq. Ft.
11920 Sq. Ft.
11700 Sq. Ft.
11340 Sq. Ft.
11920 Sq. Ft.
11920 Sq. Ft.
11700 Sq. Ft.
11340 Sq. Ft.
11920 Sq. Ft.
11950 Sq. Ft.
11920 Sq. Ft.
11520 Sq. Ft.
10080 Sq. Ft.
11965 Sq. Ft.
11920 Sq. Ft.
11520 Sq. Ft.
2400 Sq. Ft.
10720 Sq. Ft.
11520 Sq. Ft.
11920 Sq. Ft.
11950 Sq. Ft.

75' BUILDING SETBACK LINE

EXISTING TREE BUFFER

ADVERTISEMENT SIGN EASEMENT

50' BUILDING SETBACK LINE

EXISTING DRIVEWAY

LIGHT POST WITH T4 OPTICS WITH DIRECTIONAL TOWARD DRIVEWAYS

Interstate 30 N

Interstate 30 S

67

70

30


**TOTAL BUILDING SQ.FT. = 291,302 SQ. FT.**

N

BASIS OF BEARING:
GRID NORTH AS PER ARKANSAS
COORDINATE SYSTEM, SOUTH ZONE
BY GPS OBSERVATION

60' 50' 0 60'

VICINITY MAP:





HOPE CONSULTING
ENGINEERS - SURVEYORS

117 S. Market Street,
Benton, Arkansas 72015
PH. (501)315-2626
FAX (501) 315-0024
www.hopeconsulting.com


FOR USE AND BENEFIT OF:


STUART FINLEY

I-30 SELF STORAGE

| | | | |
|---|---|---|---|
| DATE: | 02-08-2023 | C.A.D. BY: B.JOHNSON | DRAWING NUMBER: |
| REVISED: | | CHECKED BY: | 22-0800 |
| SHEET: | | SCALE: 1" = 60' | |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| 500 | 01S | 14W | 0 | 21 | 300 | 62 | 1762 |


All Rights Reserved ©2023 Hope Consulting, Inc. | Hope Consulting, Inc. | 501-315-2626







BASIS OF BEARING
IS GRID NORTH
AR SOUTH ZONE
NAD83
GPS DATA
CF 0.9998954439
-0°16'47"

SOURCE OF TITLE: 2020-9437, 2020-25476

OWNER OF RECORD: BRYANT HOTEL INVESTMENTS, LLC
6733 AUSTIN BAY COURT
NLR, AR.

NAME OF SUBDIVIDER: BRYANT HOTEL INVESTMENTS, LLC
6733 AUSTIN BAY COURT
NLR, AR.

CURRENT ZONING: C2

CERTIFICATE OF OWNER

WE, THE UNDERSIGNED, OWNERS OF THE REAL ESTATE SHOWN AND DESCRIBED HEREIN DO HEREBY CERTIFY THAT WE HAVE LAID OFF, PLATTED AND SUBDIVIDED, AND DO HEREBY LAY OFF, PLAT AND SUBDIVIDE SAID REAL ESTATE IN ACCORDANCE WITH THE PLAT.

_____ _____
DATE OF EXECUTION BRYANT HOTEL INVESTMENTS, LLC

CERTIFICATE OF SURVEYING ACCURACY:

I, KERRY D. LANE, HEREBY CERTIFY THAT THIS PROPOSED PLAT CORRECTLY PRESENTS A SURVEY COMPLETED BY ME, OR UNDER MY SUPERVISION ON MARCH 16, 2023; THAT THE BOUNDARY LINE SHOWN HEREON CORRESPOND WITH THE DESCRIPTION IN THE DEEDS CITED IN THE ABOVE SOURCE OF TITLE; AND THAT ALL MONUMENTS WHICH WERE FOUND OR PLACED ON THE PROPERTY ARE CORRECTLY DESCRIBED AND LOCATED.

BY: _____, ARKANSAS PROFESSIONAL SURVEYOR NO. 1141,

DATE _____

CERTIFICATE OF FINAL PLAT APPROVAL:

PURSUANT TO THE CITY OF BRYANT SUBDIVISION RULES AND REGULATIONS, THIS DOCUMENT WAS GIVEN APPROVAL BY THE BRYANT PLANNING COMMISSION AT A METTING HELD_____ 20_____. ALL OF THE DOCUMENT IS HEREBY ACCEPTED, AND THIS CERTIFICATE EXECUTED UNDER THE AUTHORITY OF SAID RULES AND REGULATIONS.

DATE OF EXECUTION BRYANT PLANNING COMMISSION

_____ _____


CERTIFICATE OF RECORDING

THIS DOCUMENT, NUMBER_____, FILED FOR RECORD_____, 20_____

IN PLAT BOOK_____ PAGE_____

CLERK

_____





DESCRIPTION
THAT PORTION OF LOT ONE OF THE SULLIVAN PLACE, PHASE I, AND THE THAT PORTION OF LOT 4 OF THE SULLIVAN PLACE, PHASE III, BEING A REPLAT OF LOT 2 OF THE SULLIVAN PLACE PHASE II, A SUBDIVISION OF A PART OF THE NORTHEAST QUARTER OF THE SOUTHEAST QUARTER, SECTION 21, TOWNSHIP 1 SOUTH, RANGE 14 WEST, SALINE COUNTY, BRYANT, ARKANSAS, AS SHOWN ON PLAT FILED FOR RECORD OCTOBER 16, 2002 AS SALINE COUNTY DOCUMENT NUMBER 2002 71604, DESCRIBED AS FOLLOWS: BEGINNING AT THE NORTHWEST CORNER OF SAID LOT ONE, THENCE SOUTH 88°50'44" EAST, A DISTANCE OF 25.00 FEET; THENCE SOUTH 03°37'26" WEST, A DISTANCE OF 125.00 FEET; THENCE NORTH 88°50'44" WEST, A DISTANCE OF 123.24 FEET; THENCE NORTH 03°55'46" EAST, A DISTANCE OF 124.97 FEET; THENCE SOUTH 88°52'57" EAST, A DISTANCE OF 97.62 FEET TO THE POINT OF BEGINNING, CONTAINING 0.3524 ACRES, MORE OR LESS.

SURVEYORS CERTIFICATION
UNLESS SPECIFICALLY STATED OR SHOWN, THIS BOUNDARY SURVEY IS MADE SUBJECT TO AND DOES NOT DELINEATE: BUILDING SETBACK LINES, ZONING REGULATIONS, RESTRICTIONS, OR OTHER ITEMS WHICH MAY AFFECT DEVELOPMENT. NO STATEMENT IS MADE CONCERNING SUBSURFACE CONDITIONS, OR THE EXISTANCE OF UNDERGROUND OR OVERHEAD CONTAINERS OR FACILITIES, UNLESS SPECIFICALLY SHOWN, WHICH MAY AFFECT THE USE OR DEVELOPMENT OF THE TRACT. TRACT MAY BE SUBJECT TO EASEMENTS, RESTRICTIVE COVENANTS, SUBDIVISION RESTRICTIONS, AND PLANNING AND ZONING REGULATIONS OF RECORD, IF ANY, AND IS SUBJECT TO SUCH FACTS WHICH A CURRENT TITLE SEARCH MAY DISCLOSE. I HEREBY CERTIFY THAT THE ABOVE PLAT REPRESENTS A BOUNDARY SURVEY PERFORMED BY ME OR UNDER MY SUPERVISION ON THIS DAY.

DATE: 3-23-2023


GRAPHIC SCALE 1"=20'

0 20 40 60





| | |
|---|---|
| DRAWING NO. 020-23 | REAL ESTATE SERVICES OF SALINE COUNTY,INC. 501-315-8866 lanesurveylng@gmail.com |
| REVISIONS BY | REPLAT OF PART LOT ONE AND LOT 4, SULLIVAN PLACE |
| DATE | 1200 FERGUSON DR., SUITE 5, BENTON, AR., 72015 |
| | 500-015-14W-0-21-210-62-1141 |


DRAWN BY
CHECKED BY
APPROVED BY



SCHEME #1



SCHEME #2




SCHEME #3

PARKING SPACES:

50 CUSTOMER PARKING SPACES
4 HANDICAP PARKING SPACES
54 PARKING SPACES TOTAL

NOTES:

1. CONSTRUCT AHTD TYPE 'A' CURB & GUTTER IN ALL AREAS EXCEPT AS NOTED ON PLANS.




LEGEND:

- PROPOSED CONCRETE
- PROPOSED ASPHALT
- EXISTING ASPHALT

** BUILDING CONSTRUCTION/FACADE WILL COMPLY WITH CITY OF BRYANT COMMERCIAL BUILDING CODE REQUIREMENTS.

N

20' 10' 0 20'

| BY | REVISION | DATE |
|---|---|---|
| | | |


GNE Designing our client's success

GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
Ph (501) 408-4650
3825 Mt Carmel Rd
Bryant, AR 72022
garnatengineering@gmail.com


NEW FACILITY FOR:
BUTLER CENTER
CITY OF BRYANT, AR

STATE OF ARKANSAS
Vernon W. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON J. WILLIAMS

03-06-2023

CONTENTS:
SITE PLAN

PROJECT NO: 22203

DATE: FEB 2023

SHEET NO: C1.0


A:\Projects\2022 Projects\22203 Butler Center 1150 North Reynolds Road Kenny #Skilled\Drawings\CAD\Drawings\22203 1150 N Reynolds Rd Design - R2.dwg

## *City of Bryant Stormwater Department*

**1019 SW 2nd St.**
**Bryant, Arkansas 72022**
**Office (501) 943-0453; Fax (501) 943-0851**


# WARRANTY BOND PROCEDURES

## For Stormwater Infrastructure Public & Private

These procedures are applicable to Stormwater Infrastructure that is to be dedicated to the public and maintained by the City of Bryant and for Private Stormwater Infrastructure that will be connected to overall City of Bryant Stormwater Infrastructure.

In accordance with Ordinance No. 2019-32 Article V., The City of Bryant Stormwater Department will require a Maintenance Warranty Bond as part of the process for approving Stormwater Infrastructure. The purpose of the bond is to cover the cost of correcting deficiencies not addressed by the developer during the warranty period and to insure no adverse effects will occur to the overall function of the City of Bryant Stormwater Infrastructure.

**ORDINANCE 2019-32 ARTICLE V. STORMWATER INFRASTRUCTURE WARRANTY BOND.**

1. **Stormwater Infrastructure Warranty Bond.** A one year maintenance bond against defects in workmanship shall be required by the Administrative Authority for any portion of the stormwater management facilities privately owned or stormwater management improvements dedicated to the city, said maintenance bond is to be provide by cashier's check, irrevocable letter of credit or acceptable surety authorized to do business in the State of Arkansas. All forms of maintenance bonds shall be subject to approval by the Administrative Authority. The value of the bond shall be an amount equal to 100% of the value of the privately owned stormwater management facilities or stormwater system improvements being privately owned or dedicated to the city. A cost list must be provide to prove and verify the amount of the maintenance bond. The cost list shall include cost of stormwater infrastructure construction and components (piping, weirs, spillway structures, junction boxes, trickle channels, inlets, grates, riprap and site stabilization).

2. **Procedurals.** These procedures are applicable to Stormwater Infrastructure that is to be dedicated to the public and maintained by the City of Bryant and for Private Stormwater Infrastructure that will be connected to overall City of Bryant Stormwater Infrastructure.

   In accordance with Ordinance No. 2019-32 Article V., City of Bryant Stormwater Department will require a Maintenance Warranty Bond as part of the process for approving Stormwater Infrastructure. The bond will be equal to 100% of the cost of construction of the Stormwater Infrastructure System at the time of completion of the Stormwater Infrastructure System. The purpose of the bond is to cover the cost of correcting deficiencies not addressed by the developer during the warranty period and to insure no adverse effects will occur to the overall function of the City of Bryant Stormwater Infrastructure.

3. **Determining the Maintenance Warranty Bond Amount.** During the final inspection process, the City of Bryant Stormwater Department will verify and approve the Warranty Bond estimate for all Stormwater Infrastructure within the proposed unit using:

(a) The Warranty Bond cost list estimate shall be presented to the City of Bryant Stormwater Department by formal letter. The formal letter shall include project name, developer contact information and "Cost List for Construction of Stormwater Infrastructure Components" including but not limited to piping, weirs, spillway structures, junction boxes, trickle channels, riprap, inlets, grates, weirs and site stabilization;

(b) The Bond amount will need to be re-evaluated if more than 18 months have passed from the time of the estimate review to the time of providing the bond to the City of Bryant Stormwater Department;

4. **Submitting the bond to the city.** After requesting a final inspection of the Stormwater Infrastructure and approval of completion by the City of Bryant Stormwater Department, the developer must provide the City of Bryant Stormwater Department with a bond equal to amount determined in Article V. Section 3. of this document. The Bond must be for a period of 12 months and be a financial guarantee in the form of a bond, letter of credit, or trust agreement executed by a surety company authorized to do business in the State of Arkansas. The Bond must be payable to the City of Bryant Public Works Department, conditioned that the developer will maintain the Stormwater Infrastructure in accordance with the Stormwater Management Manual Ordinance No. 2019-31 and the Stormwater Management Ordinance No. 2019-32.

5. **Warranty period.** After the Stormwater Infrastructure construction passes the final inspection and the one year warranty bond is received, the one year maintenance warranty period will begin. The one-year warranty period will start on the date the Maintenance Warranty Bond is received and accepted. There shall be no separate warranty period start dates for Stormwater Infrastructure within a single unit.

6. **Follow-up inspection.** The City of Bryant Stormwater Department will conduct a follow-up inspection within the tenth month of the warranty period but in no event any later than two months prior to the bond expiring. The City of Bryant Stormwater Department will issue a punch list of deficiencies that will be sent to the developer or contractor for the unit. If no deficiencies are found and camera video passes inspection, release of the bond will proceed as set out and as listed in Article V. Section 10 of this document.

7. **Correcting Deficiencies and Camera Video.** The developer must contact the City of Bryant Stormwater Department at least 24 hours before correcting any decencies or performing camera video. The developer shall also camera all stormwater infrastructure to ensure that there is no sediment laden infrastructure. Upon notification by the developer that all deficiencies have been corrected and camera video has been completed, the City of Bryant Stormwater Department will re-inspect to verify compliance with correction of deficiencies and reviewing the camera video to assure the stormwater infrastructure is not sediment laden or defective.

8. **Calling in the bond.** If the developer does not contact the City of Bryant Stormwater Department, deficiencies have not been corrected and the stormwater infrastructures has not been camera videoed by the end of the 11th month or one (1) month prior to the expiration of the Bond, the City of Bryant Stormwater Department will prepare an estimate and list of work to be done to bring the stormwater infrastructure into compliance. The City of Bryant Stormwater Department will contact the bonding agency to submit the cost estimates for correcting the deficiencies.

9. **Requesting Acceptance.** Once all deficiencies have been corrected, the City of Bryant Stormwater Department will prepare the paperwork for the Stormwater Infrastructure within the unit accepted for maintenance by the City of Bryant 'if dedicated', or paperwork will be prepared to release the bond if infrastructure is a private unit.

10. **Bond Release.** The Bond will be released once the City of Bryant has accepted the Stormwater Infrastructure for maintenance 'if dedicated', and an acceptance letter has been written by the City of Bryant Public Works. If all compliance has been met with a private Stormwater Infrastructure Unit(s) then the City of Bryant Stormwater Department shall contact the developer by formal letter and release the bond. No partial release of the Bond will be allowed at any time.

**ATTENTION: DO NOT FILL OUT INFORMATION BELOW UNTIL YOU ARE PRESENT WITH A NOTARY PUBLIC. (THIS DOCUMENT MUST BE NOTARIZED)**

By filling out the information below, signing and dating, you are hereby acknowledging that you have read, understand and agree to adhere to the Stormwater Infrastructure Warranty Bond Procedures and Processes listed in this document. You the applicant are hereby responsible for upholding, without limitation, the Stormwater Infrastructure Warranty Bond Procedures.

Butler Center
Name of Project Site/Addition

Michael Butler
Applicant Name
(Print)

Applicant Name
(Signature)

Butler Wealth Capital, LLC
Applicant Business Name

6, Creekwood Court, Little Rock, AR 72223
Applicant Mailing Address

***Notarization***

**State of** ARKANSAS

**County of** SALINE

**Subscribed and sworn before me, a Notary Public, on this** 17TH **day of** MARCH, 2023.

George P. Wooden
**Signature of Notary**

02-05-2031
**My commission expires:**

**Notary Seal Stamp Here:**

GEORGE P. WOODEN
Notary Public-Arkansas
Saline County
My Commission Expires 02-05-2031
Commission # 12714343

# New Facility For:
# Butler Center
# 1109 N Reynolds Road
# Bryant, AR 72022

## STORM WATER MAINTENANCE PLAN

The Butler Center owner will be responsible for the inspection and maintenance of the stormwater detention pond located on its.

Inspections are to be scheduled as directed in this document. All documentation on scheduled inspections, dates of inspections, and maintenance completed shall be retained by the Butler Center owner for a period of three years.

**DETENTION PIPES**

Annual Maintenance (as applicable):

[ ] Check pipes for sediment in-fill, clean when necessary

[ ] Check outlets for clogging with trash or dead vegetation, clean when necessary


Michael Butler
Butler Wealth Capital, LLC

3-17-23
date

# INSPECTION REPORT

**DATE: / /**

**BUTLER CENTER**




OUTLET

DETENTION PIPE

**COMMENT**

# SITE WITH AUTOMATIC COVERAGE (LESS THAN 5 ACRES) CONSTRUCTION SITE NOTICE

FOR THE
Arkansas Department of Environmental Quality (ADEQ)
Storm Water Program

## NPDES GENERAL PERMIT NO. ARR150000

The following information is posted in compliance with **Part I.B.8.A** of the ADEQ General Permit Number **ARR150000** for discharges of stormwater runoff from sites with automatic coverage. Additional information regarding the ADEQ stormwater program may be found on the internet at:

*www.adeq.state.ar.us/water/branch_npdes/stormwater*

| | |
|---|---|
| Permit Number | ARR150000 |
| Contact Name:<br>Phone Number: | Michael Butler<br>870-703-3807 |
| Project Description (Name, Location, etc.):<br>Start Date:<br>End Date:<br>Total Acres: | New Facility for Butler Center, Bryant, AR<br><br><br>1.69 |
| Location of Stormwater Pollution Prevention Plan: | Mailbox on Site |

For Construction Sites Authorized under **Part I.B.6.A** (Automatic Coverage) the following certification must be completed:

I _____ (Typed or Printed Name of Person Completing this Certification) certify under penalty of law that I have read and understand the eligibility requirements for claiming an authorization under Part I.B.2. of the ADEQ General Permit Number ARR150000. A stormwater pollution prevention plan has been developed and implemented according to the requirements contained in Part II.A.2.B & D of the permit. I am aware there are significant penalties for providing false information or for conducted unauthorized discharges, including the possibility of fine and imprisonment for knowing violations.

_____ _____

Signature and Title Date

# Stormwater Pollution Prevention Plan (SWPPP) for Construction Activity for Small Construction Sites

National Pollutant Discharge Elimination System (NPDES)
General Permit # ARR150000

Prepared for:
New Facility For
Butler Center

Date:
03/17/2023

Prepared by:
GarNat Engineering, LLC

Revised date: 10/20/2016

**Table of Contents**
**New Facility for: Butler Center**
**Bryant, Arkansas**

SWPPP for Construction Activity for Small Construction Sites

Appendix A- ARR150000 Inspection Form

SWPPP Figures

New Facility for: Butler Center Erosion Control Plan

AHTD Standard Drawings:

TEC-1 – Temporary Erosion Control Devices

TEC-4 – Temporary Erosion Control Devices

NPDES ARR150000

Project Name and Location: New Facility for Butler Center, 1109 N Reynolds Rd, Bryant, AR.

Property Parcel Number (*Optional*): 840-14297-000

Operator Name and Address: _____

A. Site Description

a. Project description, intended use after NOI is filed: Commercial development of a Chiropractic Clinic and parking lot.

b. Sequence of major activities which disturb soils: clearing & grubbing, earthwork, drainage structure, utilities

c. Total Area: 1.69 Ac. Disturbed Area: 1.51 Ac.

B. Responsible Parties

*Be sure to assign all SWPPP related activities to an individual or position; even if the specific individual is not yet known (i.e. contractor has not been chosen).*

| Individual/Company | Phone Number | Service Provided for SWPPP (i.e., Inspector, SWPPP revisions, Stabilization Activities, BMP Maintenance, etc.) |
|---|---|---|
| Michael Butler | 870-703-3807 | |
| | | |
| | | |
| | | |
| | | |

C. Receiving Waters

a. The following waterbody (or waterbodies) receives stormwater from this construction site: Unnamed tributaries of Hurricane Creek

b. Is the project located within the jurisdiction of an MS4? ☒ Yes ☐ No

i. If yes, Name of MS4: Bryant

c. Ultimate Receiving Water:

☐ Red River
☐ Ouachita River
☒ Arkansas River
☐ White River
☐ St. Francis River
☐ Mississippi River

D. Site Map Requirements (Attach Site Map):

a. Pre-construction topographic view;

b. Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
c. Delineate on the site map areas of soil disturbance and areas that will not be disturbed under the coverage of this permit;
d. Location of major structural and nonstructural controls identified in the plan;
e. Location of main construction entrance and exit;
f. Location where stabilization practices are expected to occur;
g. Locations of off-site materials, waste, borrow area, or equipment storage area;
h. Location of areas used for concrete wash-out;
i. Location of all surface water bodies (including wetlands) with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
j. Locations where stormwater is discharged to a surface water and/or municipal separate storm sewer system if applicable,
k. Locations where stormwater is discharged off-site (should be continuously updated);
l. Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
m. A legend that identifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
n. Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

E. Stormwater Controls

a. Initial Site Stabilization, Erosion and Sediment Controls, and Best Management Practices:

i. Initial Site Stabilization: Prior to starting clearing activities, the BMP's shown on the Erosion Control Plan will be installed.

ii. Erosion and Sediment Controls: Erosion and sediment controls are shown on the erosion control plan. They will be constructed per AHTD standard details

iii. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the operator will replace or modify the control for site situations: ☒ Yes ☐ No

If No, explain: _____

_____

iv. Off-site accumulations of sediment will be removed at a frequency sufficient to minimize off-site impacts: ☒ Yes ☐ No

If No, explain: _____

_____

v. Sediment will be removed from sediment traps or sedimentation ponds when design capacity has been reduced by 50%: ☒ Yes ☐ No

If No, explain: _____

_____

vi. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges: ☒ Yes ☐ No

If No, explain: _____

_____

vii. Off-site material storage areas used solely by the permitted project are being covered by this SWPPP: ☐ Yes ☒ No (there are no such sites)

If Yes, explain additional BMPs implemented at off-site material storage area: _____

_____

b. Stabilization Practices

i. Description and Schedule: As soon as practical, the contractor will spread topsoil and seed the disturbed area with a perennial vegetation. Vegetation will be reseeded as required to establish the 80% coverage of perennial vegetation.

ii. Are buffer areas required? ☐ Yes ☒ No

If Yes, are buffer areas being used? ☐ Yes ☐ No

If No, explain why not: _____

_____

If Yes, describe natural buffer areas: _____

_____

iii. A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included with the plan. ☒ Yes ☐ No

If No, explain: _____

_____

iv. Deadlines for stabilization:

1. Stabilization procedures will be initiated 14 days after construction activity temporarily ceases on a portion of the site.
2. Stabilization procedures will be initiated immediately in portions of the site where construction activities have permanently ceased.

c. Structural Practices

i. Describe any structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site: BMPs shown on the erosion control plan will be used to limit sediment from leaving the site

ii. Describe Velocity Dissipation Devices: _____

iii. Sediment Basins:

Are 10 or more acres draining to a common point? ☐ Yes ☒ No

Is a sediment basin included in the project? ☐ Yes ☒ No

If Yes, what is the designed capacity for the storage?

☐ 3600 cubic feet per acre = : _____

or

☐ 10 year, 24 hour storm = : _____

☐ Other criteria were used to design basin: _____

If No, explain why no sedimentation basin was included and describe required natural buffer areas and other controls implemented instead: Not appropriate for this project.

F. Other Controls

a. Solid materials, including building materials, shall be prevented from being discharged to Waters of the State: ☒ Yes ☐ No

b. Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of:

☒ A stabilized construction entrance and exit

☐ Vehicle tire washing

☒ Other controls, describe: * see below

c. Temporary Sanitary Facilities: A portable toilet will be provided. The location is shown on the Erosion Control Plan.

* The road adjacent to the property will be swept to remove offside vehicle tracks. Disturbed areas will be watered during construction.

d. Concrete Waste Area Provided:
☒ Yes
☐ No. Concrete is used on the site, but no concrete washout is provided.
Explain why: _____
_____
☐ N/A, no concrete will be used with this project

e. Fuel Storage Areas, Hazardous Waste Storage, and Truck Wash Areas: _____
_____

G. Non-Stormwater Discharges

a. The following allowable non-stormwater discharges comingled with stormwater are present or anticipated at the site:
☒ Fire-fighting activities;
☒ Fire hydrant flushings;
☒ Water used to wash vehicles (where detergents or other chemicals are not used) or control dust in accordance with Part II.A.4.H.2;
☒ Potable water sources including uncontaminated waterline flushings;
☒ Landscape Irrigation;
☒ Routine external building wash down which does not use detergents or other chemicals;
☒ Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents or other chemicals are not used;
☒ Uncontaminated air conditioning, compressor condensate (See Part I.B.12.C of the permit);,
☒ Uncontaminated springs, excavation dewatering and groundwater (See Part I.B.13.C of the permit);
☒ Foundation or footing drains where flows are not contaminated with process materials such as solvents (See Part I.B.13.C of the permit);

b. Describe any controls associated with non-stormwater discharges present at the site: BMP's shown on the Erosion Control plan will also be utilized to prevent sedimentation from leaving site during construction.

H. Applicable State or Local Programs: The SWPPP will be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site. ☒ Yes ☐ No

I. Inspections

a. Inspection frequency:
☒ Every 7 calendar days
or
☐ At least once every 14 calendar days and within 24 hours of the end of a storm even 0.25 inches or greater (a rain gauge must be maintained on-site)

b. Inspections:

Completed inspection forms will be kept with the SWPPP.

☒ ADEQ's inspection form will be used (See Appendix B)

or

☐ A form other than ADEQ's inspection form will be used and is attached (See inspection form requirements Part II.A.4.L.2)

c. Inspection records will be retained as part of the SWPPP for at least 3 years from the date of termination.

d. It is understood that the following sections describe waivers of site inspection requirements. All applicable documentation requirements will be followed in accordance with the referenced sections.

i. Winter Conditions (Part II.A.4.L.4)

ii. Adverse Weather Conditions (Part II.A.4.L.5)

J. Maintenance:

The following procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition will be followed: See below*

Any necessary repairs will be completed, when practicable, before the next storm event, but not to exceed a period of 3 business days of discovery, or as otherwise directed by state or local officials.

K. Employee Training:

The following is a description of the training plan for personnel (including contractors and subcontractors) on this project: Operator will submit proof of training to engineer. Engineer will provide additional training as required to ensure that SWPPP is properly implemented.

**Note, Formal training classes given by Universities or other third-party organizations are not required, but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.

* Built up sediment will be removed from silt fencing when it has reached 1/3 of the height of the fence. Silt fences will be inspected for the depth of sediment, tears, fabric attachment to the fence posts, and to see that the fence posts are firmly in the ground. Temporary and permanent seeding will be inspected for bare spots, washouts, and healthy growth. Entrance will be inspected for sediment tracked on roads.

Certification

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official: _____

Title: _____ Date: _____

## ARR150000 Inspection Form

Appendix A

Inspector Name: _____ Date of Inspection: _____

Inspector Title: _____

Date of Rainfall: _____ Duration of Rainfall: _____

Days Since Last Rain Event: _____ days Rainfall Since Last Rain Event: _____ inches

Description of any Discharges During Inspection: _____

Location of Discharges of Sediment/Other Pollutant (specify pollutant & location): _____

_____

Locations in Need of Additional BMPs: _____

Information on Location of Construction Activities

| Location | Activity Begin Date | Activity Occuring Now (y/n)? | Activity Ceased Date | Stabilization Initiated Date | Stabilization Complete Date |
|---|---|---|---|---|---|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Information on BMPs in Need of Maintenance

| Location | In Working Order? | Maintenance Scheduled Date | Maintenance Completed Date | Maintenance to be Performed By |
|---|---|---|---|---|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Changes required to the SWPPP: _____ Reasons for changes: _____

_____ _____


_____ _____

SWPPP changes completed (date): _____

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official: _____ Date: _____

Title: _____




BMP NOTES:

1. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.

2. DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.

3. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIAL SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORMWATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.

4. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS STOPPED FOR AT LEAST 14 DAYS, SHALL BE TEMPORARILY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.

5. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE GRADING PLAN AND/OR LANDSCAPE PLAN.

6. IF THE ACTION OF VEHICLES TRAVELING OVER THE SITE IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF OF THE SITE.

7. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.


8. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.

9. ON-SITE & OFF SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.


10. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.

TOTAL SITE: 1.69 ACRES (INCLUDES R-0-W)

TOTAL DISTURBED AREA: 1.51 ACRES (INCLUDES R-O-W)




SECTION A




STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE

LEGEND:

500 EXISTING CONTOURS

DIRECTION OF OVERLAND FLOW

SF SILT FENCING

N

30' 15' 0 30'

| BY | REVISION | DATE |
|---|---|---|
| | | |

GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com

NEW FACILITY FOR:
BUTLER CENTER
CITY OF BRYANT, AR

STATE OF ARKANSAS
Vernon W. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON J. WILLIAMS

03-06-2023

CONTENTS:

EROSION CONTROL PLAN

PROJECT NO: 22203


DATE: FEB 2023

SHEET NO: C4.0


J:\Projects\2022 Projects\22203 Butler Center 1109 North Reynolds Road Kenny Whitfield\Drawings\GRAD\Grading\22203 1109 N Reynolds Rd Grading.dwg

GENERAL NOTES


INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.




## WATTLE DITCH CHECK (E-1)




## DROP INLET SILT FENCE (E-7)





## SILT FENCE ON R/W FENCE (E-4)

GENERAL NOTES

GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST, OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.


GENERAL NOTES

1. STRAW BALES SHALL BE INSTALLED SO THAT THE BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES. THE BALES SHALL BE A MINIMUM OF 30 INCHES IN LENGTH.
2. NO GAPS SHALL BE LEFT BETWEEN BALES.
3. BALED STRAW FILTER BARRIERS COMPLETED AND ACCEPTED WILL BE MEASURED BY THE BALE IN PLACE AS AUTHORIZED BY THE ENGINEER AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER BALE FOR BALED STRAW DITCH CHECKS.





## BALED STRAW FILTER BARRIER (E-2)


NUMBER OF SAND BAGS AND ARRANGEMENT VARIABLE WITH ON-SITE CONDITIONS.





PLACE SAND BAGS AT BASE OF DITCH CHECK IN AREA OF OVERFLOW




## SAND BAG DITCH CHECK (E-5)




## ROCK DITCH CHECK (E-6)




## SILT FENCE (E-11)

GENERAL NOTES

GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.


PER CITY OF BRYANT REQUIREMENTS, REQUIRES WIRED BACK FENCE.

| DATE | REVISION | FILMED |
|---|---|---|
| 12-15-11 | DELETED BALED STRAW DITCH CHECK & ADDED WATTLE DITCH CHECK | |
| 11-18-98 | ADDED NOTES | |
| 7-02-98 | ADDED BALED STRAW FILTER BARRIER (E-2) | |
| 7-20-95 | REVISED SILT FENCE E-4 AND E-11 | 7-20-95 |
| 7-15-94 | REV. E-4 & E-11 MIN. 13" BURIED END OF FABRIC | |
| 6-2-94 | REVISED E-1,4,7 & 11; DELETED E-2 & 3 | 6-2-94 |
| 4-1-93 | REDRAWN | |
| 10-1-92 | REDRAWN | |
| 8-2-76 | ISSUED R.D.M. | 298-7-28-76 |


ARKANSAS STATE HIGHWAY COMMISSION

# TEMPORARY EROSION CONTROL DEVICES

STANDARD DRAWING TEC-1





TRIANGULAR SILT DIKE INSTALLATION
FOR
DIVERSION DITCH AND/OR DITCH LINER





TRIANGULAR SILT DIKE INSTALLATION
FOR
ROADWAY DITCH OR DRAINAGE DITCH

○ POINT "1" MUST BE HIGHER THAN POINT "2" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.


⊖ STAPLES SHALL BE PLACED WHERE THE UNITS OVERLAP AND IN THE CENTER OF THE UNIT AS SHOWN ON THE DIAGRAM.




TRIANGULAR SILT DIKE INSTALLATION
FOR
CONTINUOUS BARRIER




TRIANGULAR SILT DIKE INSTALLATION
FOR
DROP INLETS




TRIANGULAR SILT DIKE INSTALLATION
FOR
TEMPORARY DITCH LINER

## GENERAL NOTES

1. THIS WORK SHALL CONSIST OF FURNISHING, INSTALLING, AND MAINTAINING THE TRIANGULAR SILT DIKE. THE DIKES SHALL BE USED AS A CONTINUOUS LINE BARRIER AT THE TOE OF SLOPE OR ACROSS THE ROADWAY DITCH TO CONTAIN SEDIMENT AND MINIMIZE EROSION, OR AS DIRECTED BY THE ENGINEER. THESE DIKES SHALL BE INSTALLED AND LOCATED AS SOON AS CONSTRUCTION WILL ALLOW OR AS DIRECTED BY THE ENGINEER.

2. TRIANGULAR SILT DIKE SHALL BE TRIANGULAR SHAPED HAVING A HEIGHT OF AT LEAST 8" TO 10" IN THE CENTER WITH EQUAL SIDES AND A 16" TO 20" BASE. THE TRIANGULAR SHAPED INNER MATERIAL SHALL BE URETHANE FOAM. THE OUTER COVER SHALL BE A WOVEN GEOTEXTILE FABRIC PLACED AROUND THE INNER MATERIAL & ALLOWED TO EXTEND BEYOND BOTH SIDES OF THE TRIANGLE 24" TO 36". THIS FABRIC SHOULD BE MILDEW RESISTANT, ROT-PROOF AND RESISTANT TO HEAT AND ULTRAVIOLET RADIATION MEETING REQUIREMENTS FOR SEDIMENT CONTROL IN AASHTO M288. THE DIKES SHALL BE ATTACHED TO THE GROUND WITH WIRE STAPLES. THE STAPLES SHALL BE NO. 11 GAUGE WIRE AND BE AT LEAST 6" TO 8" LONG. STAPLES SHALL BE PLACED AS SHOWN ON THESE DETAILS.

   THE CONTRACTOR SHALL INSPECT ALL DIKES AFTER EACH RAINFALL EVENT OF AT LEAST 0.5" OR GREATER. ANY DEFICIENCIES OR DAMAGE SHALL BE REPAIRED BY THE CONTRACTOR. ACCUMULATED SILT OR DEBRIS SHALL BE REMOVED AND RELOCATED AS DIRECTED BY THE ENGINEER. IF THE DIKES ARE DAMAGED OR INADVERTENTLY MOVED DURING THE SILT REMOVAL PROCESS, THE CONTRACTOR SHALL IMMEDIATELY REPLACE AFTER DAMAGE OCCURS.

3. ACCEPTED TRIANGULAR SILT DIKE, MEASURED AS PROVIDED ABOVE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID FOR TRIANGULAR SILT DIKE. PRICE BID WILL INCLUDE THE COST OF FURNISHING THE DIKES, INSTALLING, MAINTAINING AND REMOVAL WHEN DIRECTED BY THE ENGINEER.

SYMBOLOGY
SYMBOL TO BE USED TO DENOTE DEVICE ON PLANS

**NOTE:** SILT DIKE SHOULD ONLY BE USED FOR DROP INLETS IN SUMP LOCATIONS.

| DATE | REVISION | FILMED |
|---|---|---|
| 7-26-12 | REVISED GENERAL NOTE 2. | |
| 12-15-11 | ISSUED | |

ARKANSAS STATE HIGHWAY COMMISSION

# TEMPORARY EROSION CONTROL DEVICES

STANDARD DRAWING TEC-4

# AUTHORIZATION TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM AND THE ARKANSAS WATER AND AIR POLLUTION CONTROL ACT

In accordance with the provisions of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.), and the Clean Water Act (33 U.S.C. 1251 et seq.), an

**Operator of Facilities with Stormwater Discharges Associated with Construction Activity**

is authorized to discharge to all receiving waters except as stated in Part I.B.11 (Exclusions).

For large construction sites that are eligible for coverage under this General Permit (GP), the Arkansas Department of Energy and Environment - Division of Environmental Quality (DEQ), Office of Water Quality will provide a Notice of Coverage (NOC) with tracking permit number which starts with ARR15 and a copy of the permit to the facility. The cover letter includes the DEQ's determination that a facility is covered under the GP and may specify alternate requirements outlined in the permit.

Small construction sites that are eligible for coverage under this GP will be considered to have automatic coverage under this GP and must follow the permit requirements outlined in Condition 6 of Part I.

Effective Date: November 1, 2021

Expiration Date: October 31, 2026

Digitally signed by Alan J. York
DN: cn=Alan J. York, o, ou, email=alan.york@adeq.state.ar.us, c=US
Date: 2021.05.04 09:13:53 -05'00'

Alan J. York
Associate Director, Office of Water Quality
Division of Environmental Quality

05/04/2021
Issue Date

# PART I
# PERMIT REQUIREMENTS

Information in **Part I** is organized as follows:

**Section A:** Definitions with Included Commentary
**Section B:** Coverage Under this Permit:

1. Permitted Area
2. Eligibility
3. Responsibilities of the Operator
4. Where to Submit
5. Requirements for Qualifying Local Program (QLP)
6. Requirements for Coverage
7. Notice of Intent (NOI) Requirements
8. Posting Notice of Coverage (NOC)
9. Applicable Federal, State or Local Requirements
10. Allowable Non-Stormwater Discharges
11. Limitations on Coverage (Exclusions)
12. Short Term Activity Authorization (STAA)
13. Effluent Limitation Guidelines (ELG)
14. Natural Buffer Zones
15. Waivers from Permit Coverage
16. Notice of Termination (NOT)
17. Responsibilities of the Operator of a Larger Common Plan of Development for a Subdivision
18. Change in Operator
19. Late Notifications
20. Failure to Notify
21. Maintenance
22. Releases in Excess of Reportable Quantities
23. Attainment of Water Quality Standards
24. Requiring an Individual Permit

## SECTION A: DEFINITIONS WITH INCLUDED COMMENTARY

**1.** **"Arkansas Pollution Control and Ecology Commission"** shall be referred to as APC&EC throughout this permit.

**2.** **"Automatic Coverage"** is a term used to define the method of coverage for a small construction site.

**3.** **"Best Management Practices (BMPs)"** schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to waters of the State. BMPs also include treatment requirements, operating procedures, and practices to control construction site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage. According to the EPA BMP manual, the use of hay-bales in concentrated flow areas is not recommended as a BMP.

**4.** **"Cognizant Official" is** a duly authorized representative, as defined in Part II.B.9.B.

**5.** **"Commencement of Construction"** is the initial disturbance of soils (or breaking ground) associated with clearing, grading, or excavating activities or other construction-related activities (e.g., stockpiling of fill material; placement of raw materials at the site).

**6.** **"Contaminated"** is a substance the entry of which into the MS4, waters of the State, or Waters of the United States may cause or contribute to a violation of Arkansas water quality standards.

**7.** **"Control Measure"** as used in this permit, refers to any Best Management Practice or other method used to prevent or reduce the discharge of pollutants to waters of the State.

**8.** **"Construction Activity"** earth-disturbing activities, such as the clearing, grading, and excavation of land, and other construction–related activities (e.g., stockpiling of fill material; placement of raw materials at the site) that could lead to the generation of pollutants.

**9.** **"Construction Site"** is an area upon which one or more land disturbing construction activities occur that in total will disturb one acre or more of land, including areas that are part of a larger common plan of development or sale that may be less than one acre where multiple separate and distinct land disturbing construction activities may be taking place at different times on different schedules but under one plan such that the total disturbed area is one acre or more.

**10.** **"Construction Support Activity"** a construction-related activity that specifically supports the construction activity and involves earth disturbance of pollutant-generating activities of its own, and can include, but not limited to, activities associated with concrete or asphalt batch plants, equipment staging yards, materials storage areas, excavated material disposal areas, and burrow areas.

**11.** **"CWA"** is the Clean Water Act or the Federal Water Pollution Control Act.

**12.** **"Department"** is referencing the Department of Energy and Environment.

**13.** **"DEQ"** or **"Division"** is referencing the Division of Environmental Quality. The Division is the governing authority for the National Pollutant Discharge Elimination System program in the state of Arkansas.

**14.** **"Detention Basin"** is an area where excess stormwater is stored or held temporarily and then slowly drains when water levels in the receiving channel recede. In essence, the water in a detention basin is temporarily detained until additional room becomes available in the receiving channel.

**15.** **"Director"** is the Director of the Division of Environmental Quality, or a designated representative.

**16.** **"Discharge"** is when used without qualification means the "discharge of a pollutant".

**17.** **"Disturbed area"** is the total area of the site where any construction activity is expected to disturb the ground surface. This includes any activity that could increase the rate of erosion, including, but not limited to, clearing, grubbing, grading, excavation, demolition activities, haul roads, and areas used for staging. Also included are stockpiles of topsoil, fill material and any other stockpiles with a potential to create additional runoff.

**18.** **"Drainageway"** is an open linear depression, whether constructed or natural, that functions for the collection and drainage of surface water.

**19.** **"Duly Authorized Representative"** is a representative of the Responsible Official meeting the requirements specified in Part II.B.9.B.

**20.** **"Eligible"** refers to being qualified for authorization to discharge stormwater under this general permit.

**21.** **"Erosion"** is the process by which the land's surface is worn away by the action of wind, water, ice or gravity.

**22.** **"ERW"** Extraordinary Resource Water, in accordance with Rule 2.

**23.** **"ESW"** Ecologically Sensitive Waterbodies, in accordance with Rule 2.

**24.** **"Facility" or "Activity"** is any NPDES "point source" or any other facility or activity (including land or appurtenances thereto) that is subject to regulation under the NPDES program.

**25.** **"Final Stabilization"**:

A. All soil disturbing activities at the site have been completed and either of the two following criteria are met:

   1) A uniform (e.g., evenly distributed, without large bare areas) perennial vegetative cover with a density of 80% or more of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or
   2) Equivalent permanent stabilization measures (such as the use of riprap, gabions, or geotextiles) have been employed.

B. When background native vegetation will cover less than 100% of the ground (e.g., arid areas, beaches), the 80% coverage criteria is adjusted as follows: if the native vegetation covers 50% of the ground, 80% of 50% (0.80 x 0.50 = 0.40) would require 40% total cover for final stabilization. On a beach with no natural vegetation, no stabilization is required.

C. For individual lots in residential construction, final stabilization means that either:

   1) The homebuilder has completed final stabilization as specified above, or

2) The homebuilder has established temporary stabilization including perimeter controls for an individual lot prior to occupation of the home by the homeowner and informing the homeowner of the need for, and benefits of, final stabilization.

D. For construction projects on land used for agricultural purposes (e.g., pipelines across crop or range land, staging areas for highway construction, etc.), final stabilization may be accomplished by returning the disturbed land to its pre-construction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to "waters of the State", and areas which are not being returned to their pre-construction agricultural use shall meet the final stabilization criteria in A, B**,** or C above.

**26.** **"Grading Activities"** as used in this permit are those actions that disturb the surface layer of the ground to change the contouring, surface drainage pattern, or any other slope characteristics of the land without significantly adding or removing on-site rock, soil, and other materials. This can include demolition, excavation, and filling.

**27.** **"Impaired Water"** is a waterbody listed in the current, approved Arkansas 303(d) list.

**28.** **"Infrastructure"** refers to streets, drainage, curbs, utilities, etc.

**29.** **"Landscaping"** is improving the natural beauty of a piece of land (i.e. entrance of subdivision) through plantings or altering the contours of the ground.

**30.** **"Large Construction Site"** is a construction site in which construction activity including clearing, grading and excavation. Construction activity also includes the disturbance of less than five acres of total land area that is a part of a larger common plan of development or sale if the larger common plan will ultimately disturb five acres or greater. (Please see Part I.B.15 for partial waivers.)

**31.** **"Larger Common Plan of Development or Sale"** is a contiguous (sharing a boundary or edge; adjacent; touching) area where multiple and distinct construction activities may be taking place at different times on different schedules under one plan. Such a plan might consist of many small projects (e.g. a common plan of development for a residential subdivision might lay out the streets, house lots, and areas for parks, schools and commercial development that the developer plans to build or sell to others for development). All these areas would remain part of the common plan of development or sale. The following items can be used as guidance for deciding what might or might not be considered a "Common Plan of Development or Sale." The ''plan'' in a common plan of development or sale is broadly defined as any announcement or piece of documentation (including a sign, public notice or hearing, sales pitch, advertisement, drawing, permit application, zoning request, computer design, etc.) or physical demarcation (including boundary signs, lot stakes, surveyor markings, etc.) indicating construction activities may occur on a specific plot. The applicant shall still meet the definition of operator in order to be required to get permit coverage, regardless of the acreage that is personally disturbed.

If a smaller project (i.e., less than 1 acre) is part of a larger common plan of development or sale (e.g., you are building a residential home on a ½ acre lot in a 40 acre subdivision or are putting in a fast food restaurant on a ¾ acre pad that is part of a 20 acre retail center), permit coverage is required.

**32.** **"Losing Stream Segment"** a stream segment which, beginning at the point of existing or proposed discharge and extending two (2) miles downstream, contribute thirty percent (30%) or more of its flow at a 7Q10 flow or one (1) cfs, whichever is greater, through natural processes such as permeable subsoil or cavernous bedrock into an aquifer.

**33.** **"Natural Buffer"** for purposes of this permit, an area of undisturbed natural cover surrounding waters of the State. Natural cover includes vegetation, exposed rock, or barren ground that exists prior to commencement of construction activities

at the site.

**34.** **"NOC"** Notice of Coverage.

**35.** **"NOI"** Notice of Intent to be covered by this permit.

**36.** **"NOT"** Notice of Termination.

**37.** **"NSW"** Natural and Scenic Waterways, in accordance with Rule 2.

**38.** **"Operator"/"Permittee"** for the purpose of this permit and in the context of stormwater associated with construction activity, means any person(s),an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has financial and operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; additionally, the Division may require any person(s), an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions can be named as a co-permittee.

In addition, for purposes of this permit and determining who is an operator, ''owner'' refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline or a landowner who allows a mining company to remove dirt, shale, clay, sand, gravel, etc. from a portion of his property). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g., having a house built by a residential homebuilder).

**39.** **"Outfall"** a point source where stormwater leaves the construction site.

**40.** **"Owner"** refers to the owner or operator of any "facility or activity" subject to regulation under the NPDES program. In addition, for purposes of this permit and determining who is an operator, ''owner'' refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g. having a house built by a residential homebuilder).

**41.** **"Physically Interconnected"** means that one municipal separate storm sewer system is connected to a second municipal separate storm sewer system in such a way that it allows for direct discharges into the second system.

**42.** **"Point Source"** is any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural stormwater runoff.

**43.** **"Qualified Local Program"** is a municipal program for stormwater discharges associated with construction sites that has been formally approved by DEQ.

**44.** **"Qualified personnel"** a person knowledgeable in the principles and practice of erosion and sediment controls who possesses the skills to assess conditions at the construction site that could impact stormwater quality and to assess the effectiveness of any sediment and erosion control measures selected to control the quality of stormwater discharges from the

construction activity.

**45.** **"Regulated Small Municipal Separate Storm Sewer System"** are all municipal separate storm sewer systems that are either:

A. Located within the boundaries of an "urbanized area" with a population of 50,000 or more as determined by the latest Decennial Census by the Bureau of Census; or
B. Owned or operated by a municipality other than those described in paragraph A and that serve a jurisdiction with a population of at least 10,000 and a population density of at least 1,000 people per square mile; or
C. Owned or operated by a municipality other than those described in paragraphs A and B and that contributes substantially to the pollutant loadings of a "physically interconnected" municipal separate storm sewer system.

**46.** **"Responsible Official"** is the authorized representative, as defined in Part II.B.9.A.

**47.** **"Retention Basin"** a basin that is designed to hold the stormwater from a rain event and allow the water to infiltrate through the bottom of the basin. A retention basin also stores stormwater, but the storage of the stormwater would be on a more permanent basis. In fact, water often remains in a retention basin indefinitely, with the exception of the volume lost to evaporation and the volume absorbed into the soils. This differs greatly from a detention basin, which typically drains after the peak of the storm flow has passed, sometimes while it is still raining.

**48.** **"Runoff Coefficient"** is the fraction of total rainfall that will appear at the conveyance as runoff.

**49.** **"Sediment"** is material that settles to the bottom of a liquid.

**50.** **"Sediment Basin"** is a basin that is designed to maintain a 10 year-24 hour storm event for a minimum of 24-hours in order to allow sediment to settle out of the water.

**51.** **"Small Construction Site"** is a construction site in which construction activities including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre and less than five acres. Small construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one and less than five acres. Small construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility.

**52.** **"Stormwater"** is stormwater runoff from rainfall, snow melt runoff, and surface runoff and drainage.

**53.** **"Stormwater Discharge Associated with Construction Activity"** refers to the discharge of runoff from any conveyance which is used for collecting and conveying stormwater and which is directly related to construction activity.

**54.** **"Stormwater Pollution Prevention Plan (SWPPP or SWP3)"** is a plan that includes site map(s), an identification of construction/contractor, activities that could cause pollutants in the stormwater, and a description of measures or practices to control these pollutants.

**55.** **"Temporary Sediment Controls"** are controls that are installed to control sediment runoff from the site during construction activity. These could be silt fencing, rock check dams, etc.

**56.** **"Total Maximum Daily Load" or "TMDL"** is the sum of the individual wasteload allocations (WLAs) for point sources and load allocations (LAs) for non-point sources and natural background. If the receiving water has only one point

source discharger, the TMDL is the sum of that point source WLA plus the LAs for any non-point sources of pollution and natural background sources, tributaries, or adjacent segments. TMDLs can be expressed in terms of mass per time, toxicity, or other appropriate measure.

**57. "Uncontaminated"** means that the water will not exceed the water quality standards as set forth in APC&EC Rule 2; also not containing a harmful quantity of any substance.

**58. "Urbanized Area"** means the areas of urban population density delineated by the Bureau of the Census for statistical purposes and generally consisting of the land area comprising one or more central place(s) and the adjacent densely settled surrounding area that together have a residential population of at least 50,000 and an overall population density of at least 1,000 people per square mile as determined by the latest Decennial Census by the Bureau of Census.

**59. "Waters of the State"** waters of the State means all streams, lakes, marshes, ponds, watercourses, waterways, wells, springs, irrigation systems, drainage systems, and all other bodies or accumulations of water, surface and underground, natural or artificial, public or private, which are contained within, flow through, or border upon this state or any portion of the state.

## SECTION B: COVERAGE UNDER THIS PERMIT

### Introduction

This Construction General Permit (CGP) authorizes stormwater discharges from large and small construction activities that result in a total land disturbance of equal to or greater than one acre or less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one acre. This permit also authorizes stormwater discharges from any other construction activity designated by DEQ where DEQ makes that designation based on the potential for contribution to an excursion of a water quality standard or for significant contribution of pollutants to waters of the State. This permit replaces the permit issued in 2016. The goal of this permit is to minimize the discharge of stormwater pollutants from construction activity into waters of the State. The operator shall read and understand the conditions of the permit. A copy of the CGP is available on the DEQ web site at https://www.adeq.state.ar.us/water/permits/npdes/stormwater/. A hard copy may be obtained by contacting the DEQ's General Permits Section at (501) 682-0623.

**1. Permitted Area.** If a large or small construction activity is located within the State of Arkansas, the operator may be eligible to obtain coverage under this permit.

**2. Eligibility.** Permit eligibility is limited to discharges from "large" and "small" construction activity, or as otherwise designated by DEQ. This general permit contains eligibility restrictions, as well as permit conditions and requirements. Operators shall meet the requirements of Part I.B.6.A or Part I.B.6.B to be eligible for coverage under this permit. In such cases, operators shall continue to satisfy those eligibility provisions to maintain permit authorization. If operators do not meet the requirements that are a pre-condition to eligibility, then resulting discharges constitute unpermitted discharges. By contrast, if operators are eligible for coverage under this permit and do not comply with the requirements of the general permit, they may be in violation of the general permit for otherwise eligible discharges.

A. This general permit authorizes discharges from construction activities as defined in 40 C.F.R. §122.26(a), 40 C.F.R. §122.26(b)(14)(x), 40 C.F.R. §122.26(b)(15)(i)-(ii) and 40 C.F.R. §450.

B. This permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, concrete truck washout, fueling, equipment staging yards, materials storage areas, excavated material disposal areas, stockpiles of top soil, borrow areas) provided:

1) The support activity is directly related to a specific construction site that is required to have NPDES permit coverage for discharges of stormwater associated with the construction activity;
2) The support activity is not a commercial operation, nor does it serve multiple unrelated construction projects; and does not continue to operate beyond the completion of the construction activity at the project it supports;
3) Pollutant discharges from support activity areas are minimized in compliance with conditions of this permit; and
4) Discharges from the support activity areas shall be identified in a Stormwater Pollution Prevention Plan (SWPPP) stating appropriate controls and measures for the areas off the construction site.

C. Other activities may be considered for this permit at the discretion of the Director as defined in 40 C.F.R. §122.26(b)(15)(ii).

3. **Responsibilities of the Operator.** Permittees with operational control are responsible for compliance with all applicable terms and conditions of this permit as it relates to their activities on the construction site including construction support activities off site, including protection of endangered species and implementation of BMPs and other controls required by the SWPPP. Receipt of this general permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance or regulation.

4. **Where to Submit.** The operator shall submit a complete and signed Notice of Intent (NOI) and SWPPP to DEQ through ePortal, unless the operator receives a waiver from DEQ, which can be found on the following website:

   https://eportal.adeq.state.ar.us/

   A. The operator shall submit the application fee to DEQ through ePortal (when available), submit an email requesting an invoice to be created to pay online, or mail in invoice from ePortal with a check (listing the invoice number on the check) to the follow address:

      Division of Environmental Quality
      ATTN: Fiscal
      5301 Northshore Drive
      North Little Rock, AR 72118-5317

   NOTE: Notice of Coverage (NOC) will **NOT** be issued until payment has been received by DEQ.

   B. Waivers from electronic reporting may be granted based on one of the following conditions:

      1) If the operational headquarters is physically located in a geographic area (i.e. Zip code or census tract) that is identified as under-served for broadcast internet access in the most recent report from the Federal Communications Commission;
      2) If available computer access or computer capability is limited; or
      3) If the operator is a religious community that choose not to use certain modern technologies pursuant to 40 C.F.R. §127.15(c)(1).

   C. In order to apply for a waiver from the electronic reporting, the operator must submit the required information outlined in 40 C.F.R. §127.15(b)(2).

   D. If DEQ grants a waiver approval to use a paper NOI, and operator elects to use it, the operator **must** use the approved form developed by DEQ.

5. **Requirements for Qualifying Local Program (QLP).** DEQ reviews and approves the QLPs to ensure that they meet or supersede both state and federal requirements outlined in this permit and 40 C.F.R. §122.44(s). DEQ will review the QLP at least every 5 years for recertification. If DEQ approves a QLP, then the QLP requirements shall at the minimum meet the DEQ's requirements. This includes all templates and forms. This permit may be modified to add new QLPs or modify existing QLPs at DEQ's discretion. All public notice and other applicable costs incurred by the modification of the permit for the addition or modification of a QLP will be paid by the QLP.

   If a small construction site is within the jurisdiction of a QLP, the operator of the small construction site is authorized to discharge stormwater associated with construction activity under QLP permit requirements only.

   At the time of issuance of this permit, only the City of Hot Springs is meeting the DEQ minimum requirements.

## 6. Requirements for Coverage.

A. *Small Construction Sites*. An operator of a small construction site will be considered to have automatic coverage under this general permit and may discharge without submitting a NOI, SWPPP or fee if the following conditions are met:

1) A completed Notice of Coverage (NOC) must be posted at the site prior to commencing construction and remain posted until final stabilization is completed;
2) A Stormwater Pollution Prevention Plan must be prepared in accordance with good engineering practice as described in Rule 6.203(B), completed prior to posting the NOC, implemented upon commencement of construction activities, and the latest copy must be maintained at the construction site;
3) All permit conditions set forth in this general permit must be followed; and
4) The operator is responsible for ensuring that the site is in compliance with any changes or updates of this general permit, by either contacting DEQ or reviewing the DEQ website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

B. *Large Construction Sites.* An operator of a large construction site discharging under this general permit shall submit the following items at least ten (10) business days prior to the commencement of construction activities:

1) A complete NOI in accordance with the requirements of Part I.B.7 of this permit.
2) A complete SWPPP in accordance with the requirements of Part II.A of this permit.
3) An initial permit fee shall accompany the NOI under the provisions of APC&EC Rule 9. Subsequent annual fees will be billed by DEQ until the operator has requested a termination of coverage by submitting a Notice of Termination (NOT). Failure to remit the required initial permit fee shall be grounds for the Director to deny coverage under this general permit. Failure to remit the required annual fees shall be grounds for the Director to revoke coverage under this permit.

C. Modification of Permit Coverage to Include Additional Acreage. Any request to increase the total acreage of a construction site shall be accompanied by a $200 permit modification fee and an updated SWPPP. Any request to only increase the disturbed acreage without changing the total acreage shall be accompanied by an updated SWPPP. A $200 permit modification fee is not required with an increase in disturbed acreage. The operator shall submit a complete and signed Additional Acreage Request Form to DEQ through ePortal, which can be found on the following website:

https://eportal.adeq.state.ar.us/

## 7. Notice of Intent (NOI) Requirements.

A. *NOI Form*. Large construction site operators who intend to seek coverage for a stormwater discharge under this general permit shall submit a complete and accurate DEQ NOI form through the ePortal system (at https://eportal.adeq.state.ar.us/) at least ten (10) business days prior to the date coverage under this permit is desired, unless granted a waiver in accordance with Part I.B.4.D. The NOI form completed **must** be the current version obtained from ePortal.

If the NOI is deemed incomplete, DEQ will notify the applicant with regard to the deficiencies by a letter, email, or phone within ten (10) business days of the receipt of the NOI. If the operator does not receive a notification of deficiencies from DEQ's receipt of the NOI, the NOI is deemed complete. If the applicant does not provide DEQ with the requested deficiencies within the deadline set by DEQ, then DEQ will return the NOI, fee and SWPPP back to the

applicant.

B. *Contents of the NOI*. The NOI form contains, at a minimum, the following information:

1) Operator (Permittee) information (name, mailing address, telephone, and E-mail address)
2) Whether the operator is a federal, state, private, public, corporation, or other entity
3) Invoice mailing information (name, address, and telephone and fax numbers)
4) Project Construction site information (name, county, address, contact person, directions to the site, latitude and longitude for the entrance of the site or the endpoints for linear project (in degrees, minutes, and seconds), estimated construction start date and completion date through site final stabilization, the total project acreage and the acreage to be disturbed by the operator submitting the NOI, type of the project (subdivision, school, etc), whether the project is part of a larger common plan of development or sale.)
5) Discharge information (name of the receiving stream, ultimate receiving stream, name of municipal storm sewer system)
6) List of current permits
7) The Certification statement and signature of a qualified signatory person in accordance with 40 CFR 122.22, as adopted by reference in APC&EC Rule 6
8) The certification of the facility corporation
9) Other information (location of the SWPPP)
10) And the SIC Code.

C. *Notice of Coverage (NOC)*. Unless notified by the Director to the contrary, operators who submit a complete NOI and SWPPP in accordance with the requirements of this permit are authorized to discharge stormwater from the construction sites under the terms and conditions of this permit ten (10) business days after the date the NOI is deemed complete (which may not be the original submission date if revisions or additions were necessary) by DEQ. If the NOC has not been received by the permittee ten (10) business days after the date the NOI is deemed complete by DEQ, the NOI may be posted until the NOC is received. Upon review of the NOI and other available information, the Director may deny coverage under this permit and require submittal of an application for an individual NPDES permit.

**8. Posting Notice of Coverage (NOC).**

A. *Automatic Coverage Sites*. The NOC for small sites, as defined in Part I.A.51, shall be obtained from the DEQ's Stormwater website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/ .

The NOC must be posted at the site prior to commencing construction. In addition, a copy of the latest signed and certified SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

B. *Large Sites: NOC Posting for Large Construction Sites*. The posting for large construction sites shall be obtained from DEQ only after the permittee has submitted the required NOI, permit fee and complete SWPPP to DEQ for the coverage.

C. *Linear Projects*. If the construction project is a linear construction project (e.g., pipeline, highway, etc.), the notice shall be placed in a publicly accessible location near where construction is actively underway and moved as necessary.

Please note, this permit does not provide the public with any right to trespass on a construction site for any reason, including inspection of a site; nor does this permit require that the permittee allow members of the public access to a construction site.

**9. Applicable Federal, State or Local Requirements.** The operator shall ensure that the stormwater controls implemented at the site are consistent with all applicable federal, state, or local requirements. Additionally, an operator who is operating under approved local erosion and sediment plans, grading plans, local stormwater permits, or stormwater management plans shall submit signed copies of the NOI to the local agency (or authority) upon the local agency's request.

**10. Allowable Non-Stormwater Discharges.**

A. The following non-stormwater discharges as part of the construction activity may be authorized by this permit through appropriate controls. Non-stormwater discharges shall be addressed in the stormwater pollution prevention plan and measures to minimize or eliminate non-stormwater discharge should be taken if reasonably possible.
   1) Fire-fighting activities;
   2) Fire hydrant flushings;
   3) Water used to wash vehicles and equipment (where detergents, soaps, solvents or other chemicals are not used) or to control dust in accordance with Part II.A.4.J.2;
   4) Potable water sources including uncontaminated waterline flushings;
   5) Uncontaminated landscape irrigation;
   6) Uncontaminated routine external building wash down which does not use detergents, soaps, solvents or other chemicals;
   7) Uncontaminated pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents, soaps. solvents or other chemicals are not used);
   8) Uncontaminated air conditioning compressor condensate (See Part I.B.13.C of this permit);
   9) Uncontaminated springs, excavation dewatering and uncontaminated groundwater (See Part I.B.13.C of this permit);
   10) Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated groundwater (See Part I.B.13.C of this permit).

**11. Limitations on Coverage (Exclusions).** The following stormwater discharges associated with construction activity are not covered by this permit:

A. *Post Construction Discharge.* Stormwater discharges associated with construction activities that originate from the site, as well as construction support activities located off site, after construction activities have been completed, the site has undergone final stabilization, and the permit has been terminated.

B. *Discharges Mixed with Non-Stormwater.* Stormwater discharges that are mixed with sources of non-stormwater other than those identified in Part I.B.10.

C. *Discharges Covered by another Permit.* Stormwater discharges associated with construction activity that are covered under an individual or an alternative general permit may be authorized by this permit after an existing permit expires, provided the expired permit did not establish numeric effluent limitations for such discharges.

D. *Discharges into Receiving Waters with an Approved TMDL.* Discharges from a site into receiving waters for which there is an established total maximum daily load (TMDL) allocation (https://www.adeq.state.ar.us/water/planning/integrated/tmdl/) are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that is consistent with the assumptions and requirements in the EPA approved TMDL. To be eligible for coverage under this general permit, operators shall incorporate into their SWPPP all conditions applicable to their discharges necessary for consistency with the assumptions and requirements of the TMDL within the timeframes established in the TMDL. If a specific numeric allocation has been established that

applies to the project's discharges, the operator shall incorporate that allocation into its SWPPP and implement necessary steps to meet that allocation. If a numeric limit has been assigned to the facility, quarterly monitoring shall be submitted to DEQ demonstrating compliance with the assigned Waste Load Allocation established in the TMDL. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge into a receiving stream with a TMDL, then DEQ may require additional BMPs.

E. *Discharges into Impaired Receiving Waters (303(d) List).* If stormwater discharges from a construction site enters the receiving water listed as impaired under Section 303(d) of the Clean Water Act (https://www.adeq.state.ar.us/water/planning/integrated/), the permittee shall incorporate into the SWPPP the additional BMPs needed to sufficiently protect water quality. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge to an impaired water body, then DEQ may require additional BMPs.

F. *Discharges into an Extraordinary Resource Water (ERW), Natural and Scenic Waterway (NSW), or Ecologically Sensitive Waterbody (ESW).* Discharges from a construction site located within the watershed of any water body or waterway designated as an Outstanding Resource Water as defined in the APC&EC Rule 2.203, including ERWs, NSWs, or ESWs are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. For the purposes of this permit, the watershed of an Outstanding Resource Water will be identified by the United States Geological Survey's twelve (12) digit Hydrological Unit Code (HUC). Please note that DEQ will be reviewing this information. If the site will discharge to an ERW, NSW, or ESW, then DEQ may determine that additional requirements are necessary.

G. *Discharges into an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas.* Discharges from a construction site located within the watershed of any potential losing stream and/or sensitive aquatic species native to the area are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. In accordance with Part I.B.3, it is the responsibility of the permittee to prevent activity which may take or otherwise risk harm to endangered species. Please note that DEQ will be reviewing this information. If the site will discharge to an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas, then DEQ may determine that additional requirements are necessary.

**12. Short Term Activity Authorization (STAA).** Any work being conducted in waters of the State will require a STAA from DEQ in accordance with Rule 2.305. An STAA is necessary for any in-stream activity that has the potential to exceed the water quality standards, including, but not limited to: gravel removal, bridge or crossing repair/maintenance, bank stabilization, debris removal, culvert replacement, flood control projects, and stream relocation. Any work being conducted in Waters of the United States may require a Section 404 permit from the U.S. Army Corps of Engineers. This permit does not authorize any activity under an STAA, Individual 401 Certification, or Section 404 permit. The necessary forms to apply for coverage under an STAA or Individual 401 Certification can be found on the following website:

https://www.adeq.state.ar.us/water/planning/instream/

The SWPPP shall be updated to include a copy of the STAA letter (and Individual 401 Certification if needed) upon receipt. Re-submittal of the SWPPP is not required unless specifically requested by DEQ.

**13. Effluent Limitation Guidelines (ELG).** All permittees shall comply with the following effluent limits:

A. *Erosion and Sediment Controls.* Design, install, and maintain effective erosion controls and sediment controls to minimize the discharge of pollutants. At a minimum, such controls shall be designed, installed and maintained to:

1) Control stormwater volume and velocity to minimize soil erosion in order to minimize pollutant discharges;
2) Control stormwater discharges, including both peak flowrates and total stormwater volume, to minimize channel and streambank erosion and scour in the immediate vicinity of discharge points;
3) Minimize the amount of soil exposed during construction activity;
4) Minimize the disturbance of steep slopes;
5) Minimize sediment discharges from the site. The design, installation and maintenance of erosion and sediment controls shall address factors such as the amount, frequency, intensity and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site;
6) Provide and maintain natural buffers around waters of the State, direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible;
7) Minimize soil compaction. Minimizing soil compaction is not required where the intended function of a specific area of the site dictates that it be compacted; and
8) Unless infeasible, preserve topsoil. Preserving topsoil is not required where the intended function of a specific area of the site dictates that the topsoil be disturbed or removed.

B. *Soil Stabilization.* Stabilization of disturbed areas must, at a minimum, be initiated immediately (unless weather conditions do not allow immediate initiation) whenever any clearing, grading, excavating or other earth disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and will not resume for a period exceeding fourteen (14) calendar days. In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures must be employed as specified by the permitting authority. Stabilization must be completed within fourteen (14) calendar days. In limited circumstances, stabilization may not be required if the intended function of a specific area of the site necessitates that it remain disturbed.

C. *Dewatering.* Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, are prohibited unless managed by appropriate controls. There shall be no turbid discharges to waters of the State resulting from dewatering activities. If trench or ground waters contain sediment, it shall pass through a sediment settling pond or other equally effective sediment control device, prior to being discharged from the construction site. Alternatively, sediment may be removed by settling in place or by dewatering into a sump pit, filter bag, or comparable practice. Ground water dewatering which does not contain sediment or other pollutants is not required to be treated prior to discharge. However, care shall be taken when discharging ground water to ensure that it does not become pollutant-laden by traversing over disturbed soils or other pollutant sources.

D. *Pollution Prevention Measures.* Design, install, implement, and maintain effective pollution prevention measures to minimize the discharge of pollutants. At a minimum, such measures shall be designed, installed, implemented and maintained to:

1) Minimize the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other wash waters. Wash waters shall be treated in a sediment basin or BMP control that provides equivalent or better treatment prior to discharge;
2) Minimize the exposure of building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site to precipitation and to stormwater. Minimization of exposure is not required in cases where the exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use); and
3) Minimize the discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures.

E. *Prohibited discharges.* The following discharges are prohibited:

1) Wastewater from washout of concrete, unless managed by an appropriate control;
2) Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds and other construction materials;
3) Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance; and
4) Soaps, solvents, or detergents used in vehicle, equipment washing, or external building washdown.
5) Toxic or hazardous substances from a spill or release.

F. *Surface Outlets.* When discharging from basins and impoundments, utilize outlet structures that withdraw water from the surface, unless infeasible.

**14. Natural Buffer Zones.** A natural buffer zone as stated below shall be maintained at all times and direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law.

A. For construction projects where construction activities or construction support activities occur, the SWPPP shall provide at least twenty-five (25) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from any waters of the State.

B. DEQ will require at least fifty (50) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from established TMDL water bodies, streams listed on the 303(d) list, an Extraordinary Resource Water (ERW), Ecologically Sensitive Waterbody (ESW), Natural and Scenic Waterway (NSW), or any other uses at the discretion of the Director.

C. Linear projects will be evaluated individually by DEQ to determine natural buffer zone setbacks.

**15. Waivers from Permit Coverage.** The Director may waive the otherwise applicable requirements of this general permit for stormwater discharges from construction activities under the terms and conditions described in this section.

A. *Waiver Applicability and Coverage*. Based upon 40 C.F.R. §122.26.b.15.i.A, operators of small construction activities may apply for and receive a waiver from the requirements to obtain this permit.

B. *No Stormwater Leaving the Site.* If all of the stormwater from the construction activity is captured on-site under any size storm event and allowed to evaporate, soak into the ground on-site, or is used for irrigation, a permit is not needed.

C. *TMDL Waivers.* This waiver is available for sites with automatic coverage if the DEQ has established or approved a TMDL that addresses the pollutant(s) of concern and has determined that controls on stormwater discharges from small construction activity are not needed to protect water quality. The pollutant(s) of concern include sediment (such as total suspended solids, turbidity or siltation) and any other pollutant that has been identified as a cause of impairment of any water body that will receive a discharge from the construction activity. The operator must certify to the Director that construction activity will take place, and storm water discharges will occur within the drainage area addressed by the TMDL or equivalent analysis. Information on approved TMDLs is available on DEQ's website:

https://www.adeq.state.ar.us/water/planning/integrated/tmdl/.

**16. Notice of Termination (NOT).** When all construction activities that disturbed soil are complete, the site has reached final stabilization (100% stabilization with 80% density or greater, or as defined in Part I.A.25.B for sites where background native vegetation will cover less than 100% of the ground), all stormwater discharges from construction activities authorized by this permit are eliminated and all temporary sediment controls are removed and properly disposed, the operator of the facility may submit a complete Notice of Termination (NOT) to the Director. Along with the NOT, pictures that represent the entire site shall be submitted for review. Final stabilization is not required if the land is returned to its pre-construction agriculture use. Operators of small construction sites are not required to submit NOTs for their construction sites. However, final stabilization is required on all sites. If a NOT is not submitted when the project is completed, the operator will be responsible for annual fees.

**17. Responsibilities of the Operator of a Larger Common Plan of Development or Sale.**

A. The operator is ultimately responsible for the runoff from the perimeter of the entire development. Regardless of the reason for the runoff, the operator is responsible for ensuring sufficient overall controls of the development.

B. The operator shall not terminate the permit coverage until the following conditions have been met:

1) After all construction activities including landscaping and lot development has been completed; and
2) All lots are sold and developed.

The following exceptions to this requirement may apply:

a. Less than 100% sold and developed at the discretion of the Director, or
b. Separation of the larger common plan if twenty-four (24) months have passed with no construction activity, or
c. All lots are developed and there are no temporary common controls for subdivision outfalls, i.e. sediment basins, large sediment traps, check dams, etc.

3) If lots are sold and then re-sold to a third party, permit coverage shall be obtained by each of the operators while they have ownership of the lots. The second owner is responsible for obtaining the same certification from the third owner (i.e. the certification shall pass from owner to owner).

C. The operator shall not terminate permit coverage until the operators of all of the individual lots within the larger common plan of development or sale are notified of their permitting requirements under this general permit. In this case, the signed certification statements from each operator of individual lots shall be maintained in the stormwater pollution prevention plan for the larger common plan of development or sale. A copy of the signed certifications shall be submitted to DEQ with the NOT. The certification shall be as follows:

"I, _____, operator of an individual lot #_____, block #_____ of _____ subdivision, certify under penalty of law that I was notified by the operator of the larger common plan of the stormwater permitting requirements for my construction site(s). I understand prior to commencement of any construction activity I have to prepare and comply with a SWPPP and post the Construction Site Notice . I understand that prior to the sale of this lot to another party; I must notify the new owner of DEQ requirements and obtain this certification from the new owner."

Signature _____

D. The following examples are provided as clarification:

1) If a small portion of the original common plan of development remains undeveloped and there has been a period of time (i.e., more than 24 months) where there are no ongoing construction activities (i.e., all areas are either undisturbed or have been finally stabilized), operators may re-evaluate the original project based on the acreage remaining from the original "larger common plan of development or sale." If less than five (5) but more than one (1) acre remains to build out the original "common plan", coverage under the large permit may not be required. However, operators will need to comply with the terms and conditions for Small Construction Sites in the Construction General Permit. If less than one acre remains of the original common plan, the individual project may be treated as a part of a less than one acre development and no permit would be required.
2) If operators have a long-range master plan of development or sale where some portions of the master plan are conceptual rather than a specific plan of future development and the future construction activities would, if they occur at all, happen over an extended period of time (i.e., more than 24 months), operators may consider the "conceptual" phases of development to be separate "common plans" provided the periods of construction for the physically interconnected phases will not overlap.
3) Where discrete construction projects within a larger common plan of development or sale are located ¼ mile or more apart and the area between the projects is not being disturbed, each individual project can be treated as a separate plan of development or sale provided any interconnecting road, pipeline or utility project that is part of the same "common plan" is not concurrently being disturbed. For example, if an interconnecting access road or pipeline were under construction at the same time, they would generally be considered as a part of a single "common plan" for permitting purposes.
4) If the operator sells all the lots in the subdivision to one or more multi-lot homebuilder(s), provisions shall be made to obtain stormwater permit coverage by one of the following options:
   a. The permit may be transferred from the first "operator" to the new/second "operator".
   b. A new, separate permit coverage may be obtained by the second "operator".
   NOTE: If a new permit coverage is to be obtained, then it shall be obtained before the first/original permit is terminated.
5) If the operator retains ownership of any lots in the subdivision, the operator shall maintain permit coverage for those lots under the original permit coverage. The operator shall modify the SWPPP by stating which lots are owned and marking the lots on the site map. If there are one (1) or two (2) lots remaining and the total acreage is less than five (5) acres, the original permit coverage could be terminated and those lots could be covered as a small site.

**18. <u>Change in Operator</u>.** For stormwater discharges from large construction sites where the operator changes, including instances where an operator is added after the initial NOI has been submitted, the new operator shall ensure that a permit transfer form is received by DEQ at least two (2) weeks prior to the new operator beginning work at the site.

**19. <u>Late Notifications</u>.** A discharger is not precluded from submitting an NOI in accordance with the requirements of this part after the dates provided in Part I.B.7 of this permit. In such instances, the Director may bring an enforcement action for failure to submit an NOI in a timely manner or for any unauthorized discharges of stormwater associated with construction activity that have occurred on or after the dates specified in this permit.

**20. <u>Failure to Notify</u>.** The operator of a construction site who fails to notify the Director of their intent to be covered under this permit, and who potentially discharges pollutants (sediment, debris, etc.) to waters of the State without an NPDES permit, is in violation of the Arkansas Water and Air Pollution Control Act.

**21. <u>Maintenance</u>.** Determination of the acreage of disturbance does not typically include disturbance for routine maintenance activities on existing roads where the original line and grade, hydraulic capacity, or original purpose of the road is not being altered, nor does it include the paving of existing roads. Maintenance activities (returning to original conditions) are not

regulated under this permit unless one or more acres of underlying or surrounding soil are cleared, graded, or excavated as part of the operation.

**22. Releases in Excess of Reportable Quantities.**

A. The discharge of hazardous substances or oil in the stormwater discharge(s) from a facility shall be prevented or minimized in accordance with the applicable stormwater pollution prevention plan for the facility. This permit does not relieve the operator of the reporting requirements of 40 C.F.R. §110, §117 and §302. Where a release containing a hazardous substance or oil in an amount equal to or in excess of a reporting quantity established under either 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302, occurs during a twenty-four (24) hour period, the following action shall be taken:

1) Any person in charge of the facility is required to notify the National Response Center (NRC) (800-424-8802) in accordance with the requirements of 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302 as soon as he/she has knowledge of the discharge;
2) The operator shall submit within five (5) calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, and the circumstances leading to the release, and steps to be taken in accordance with Part II.B.17 of this permit to the DEQ.
3) The SWPPP described in Part II.A of this permit shall be modified within fourteen (14) calendar days of knowledge of the release to:

    a. Provide a description of the release and the circumstances leading to the release; and
    b. The date of the release;

4) Additionally, the SWPPP shall be reviewed to identify measures to prevent the reoccurrence of such releases and to respond to such releases, and the plan shall be modified where appropriate.

B. *Spills*. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.

**23. Attainment of Water Quality Standards.**

The operator shall select, install, implement, and maintain control measures at the construction site and construction support activities off site that minimize the discharge of pollutants for which a stream is impaired at the discretion of the Director as necessary to protect water quality. In general, except in situations explained below, the stormwater controls developed, implemented, and updated to be considered stringent enough to ensure that discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.

At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:

A. Develop a supplemental BMP action plan describing SWPPP modifications to address adequately the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

B. Cease discharges of pollutants from construction activity and submit an individual permit application.

All written responses required under this part shall include a signed certification consistent with Part II.B.9.

**24. Requiring an Individual Permit**

The Director may require any person eligible for coverage under the general permit to apply for and obtain an individual permit. In addition, any interested person(s) may submit an application for an individual permit. The Director may consider the issuance of individual permits according to the criteria in 40 C.F.R. §122.28(b)(3).

Coverage of the facility under this general permit is may be terminated by DEQ if the operator fails to submit or respond to the permitting process or requests for information in a timely manner.

Any operator covered under this general permit may request to be excluded from the coverage of this permit by applying for an APC&EC Rule 6 individual permit. The operator shall submit an application for an individual permit with the reasons supporting the application to DEQ. If a final, individual NPDES permit is issued to an operator otherwise subject to this general permit, the operator is required to submit a NOT. Coverage under this general permit will then be terminated no earlier than the effective date of the individual NPDES permit. Otherwise, the applicability of this general permit to the facility remains in full force and effect.

# PART II
# STANDARD CONDITIONS

Information in **Part II** is organized as follows:

**Section A:** Stormwater Pollution Prevention Plans (SWPPP):

1. Deadlines for Plan Preparation and Compliance
2. Signature, SWPPP, Inspection Reports, and Notice of Coverage (NOC)
3. Keeping SWPPP Current
4. Contents of the Stormwater Pollution Prevention Plan
5. Plan Certification

**Section B:** Standard Permit Conditions:

1. Retention of Records
2. Duty to Comply
3. Penalties for Violations of Permit Conditions
4. Continuance of the General Permit
5. Need to Halt or Reduce Activity Not a Defense
6. Duty to Mitigate
7. Duty to Provide Information
8. Other Information
9. Signatory Requirements
10. Certification
11. Penalties for Falsification of Reports
12. Penalties for Tampering
13. Oil and Hazardous Substance Liability
14. Property Rights
15. Severability
16. Transfers
17. Proper Operation and Maintenance
18. Inspection and Entry
19. Permit Actions
20. Re-Opener Clause
21. Local Requirements
22. Applicable Federal, State Requirements

## SECTION A: STORMWATER POLLUTION PREVENTION PLANS (SWPPP)

The operator shall prepare a SWPPP before permit coverage. The SWPPP shall follow the order outlined in Part II.A.4 & 5 below. This basic DEQ format is available through DEQ's website https://www.adeq.state.ar.us/water/permits/npdes/stormwater/. Other formats may be used at the discretion of the Director if the format has been approved by DEQ prior to use. The operator shall implement the SWPPP as written from initial commencement of construction activity until final stabilization is complete, with changes being made as deemed necessary by the permittee, local, state or federal officials. The plan shall be prepared in accordance with good engineering practices, by qualified personnel and shall:

- Identify potential sources of pollution which may reasonably be expected to affect the quality of stormwater discharges from the construction site and construction support activities off site;
- Identify, describe and ensure the implementation of BMPs, with emphasis on initial site stabilization, which are to be used to reduce pollutants in stormwater discharges from the construction site and construction support activities off site;
- Be site specific to what is taking place on a particular construction site;
- Ensure compliance with the terms and conditions of this permit; and
- Identify the responsible party for on-site SWPPP implementation.

### 1. Deadlines for Plan Preparation and Compliance.

A. *Automatic Coverage Sites.*

The plan shall be completed prior to obtaining permit coverage and commencement of construction activities and updated as appropriate. Submittal of the NOI, permit fee and SWPPP is not required. All conditions set forth in Part II.A must be followed, and the NOC must be posted at the site prior to commencing construction activities. In addition, a copy of the SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

B. *Large Construction Sites.*

The plan shall be completed and submitted for review, along with an NOI and initial permit fee ten (10) business days prior to the commencement of construction activities. Submittals of updates to the plan during the construction process are required in accordance with Part I.B.6.C or if requested by the Director.

C. *Existing Permittees.*

Existing permittees that were permitted prior to the issuance of this renewal permit are required to update their plan as appropriate to come into compliance with the requirements contained in Part II.A.4 by the effective date of this permit.

### 2. Signature, SWPPP, Inspection Reports and Notice of Coverage (NOC).

A. The SWPPP and inspection reports shall be signed by the operator (or cognizant official) in accordance with Part II.B.9 and be retained at the construction site during normal business hours (8:00 A.M. – 5:00 P.M.). The inspections frequency shall be conducted in accordance with Part II.A.4.N.1.

B. The operator shall make SWPPP and inspection reports available, upon request, to the Director, the EPA, or a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or, in the case of a stormwater discharge associated with construction activity which discharges through a municipal separate storm sewer system with an NPDES permit, to the municipal operator of the system.

C. The Director, or authorized representative, may notify the operator at any time that the plan does not meet one or more of the minimum requirements of this Part. Within seven (7) business days of such notification from the Director (or as otherwise provided by the Director) or authorized representative, the operator shall make the required changes to the plan and submit to the Director a written certification that the requested changes have been made. DEQ may request re-submittal of the SWPPP to confirm that all deficiencies have been adequately addressed. DEQ may also take appropriate enforcement action for the period of time the operator was operating under SWPPP that did not meet the minimum requirements of this permit.

D. The operator shall post the NOC near the main entrance of the construction site and visible to the public. The NOC shall indicate the location of the SWPPP. If the SWPPP location is changed from the initial location, the NOC shall be updated to reflect the correct location of the SWPPP.

**3. Keeping SWPPP Current.** The operator shall amend the SWPPP within seven (7) business days or whenever there is a change in design, construction, operation, or maintenance at the construction site which has or could have a significant effect on the potential for the discharge of pollutants to the waters of the State that has not been previously addressed in the SWPPP. The SWPPP shall also be modified if a determination has been made through inspections, monitoring (if required), ***or*** investigation by the operator, local, state, or federal officials that the discharges are causing or contributing to water quality violation or the plan proves to be ineffective in eliminating or significantly minimizing pollutants from sources identified in stormwater discharges from the construction site.

**4. Contents of the SWPPP.** The SWPPP shall include the following items:

A. *Site Description*. SWPPP shall provide a description of the following:

1) A description of the nature of the construction activity and its intended use after the NOI is filed (i.e., residential subdivision, shopping mall, etc.);
2) A description of the intended sequence of major activities which disturb soils for major portions of the site (e.g. grubbing, excavation, grading, infrastructure installation, etc.);
3) Estimates of the total area of the site including off-site borrow and fill areas and the total area of the site that is expected to be disturbed by excavation, grading or other activities; and
4) An estimate of the runoff coefficient of the site for pre- and post-construction activities and existing data describing the soil or the quality of any discharge from the site.

B. *Responsible Parties*. The SWPPP shall identify (as soon as this information is known) all parties (i.e., General Contractors, Landscapers, Project Designers, and Inspectors) responsible for particular construction activities and services they provide to the operator to comply with the requirements of the SWPPP for the project site and construction support activities off site, and areas over which each party has control. If these parties change over the life of the permit, or new parties are added, the SWPPP shall be updated to reflect these changes.

C. *Receiving Waters*. The SWPPP shall include a clear description of the nearest receiving water(s), or if the discharge is to a MS4, the name of the operator of the municipal system, and the ultimate receiving water(s).

D. *Documentation of Permit Eligibility Related to the 303(d) list and Total Maximum Daily Loads (TMDL)*. The SWPPP shall include information on whether or not the stormwater discharges from the site enter a waterbody that is on the most recent 303(d) list or with an approved TMDL. If the stormwater discharge does enter a waterbody that is on the most recent 303(d) list or with an approved TMDL, then the SWPPP shall address the following items:

1) Identification of the pollutants that the 303(d) list or TMDL addresses, specifically whether the 303(d) list or TMDL addresses sediment or a parameter that addresses sediment (such as total suspended solids, turbidity, or siltation);
2) Identification of whether the operator's discharge is identified, either specifically or generally, on the 303(d) list or

any associated assumptions and allocations identified in the TMDL for the discharge; and

3) Measures taken by the operator to ensure that its discharge of pollutants from the site is consistent with the assumptions and allocations of the TMDL.

If DEQ determines during the review process that the proposed project will be discharging to a receiving water that is on the most recent 303(d) list or with an approved TMDL, then DEQ may notify the applicant to include additional Best Management Practices in the SWPPP.

E. *Documentation of Permit Eligibility Related to Discharges into an ERW, NSW, or ESW*. The SWPPP shall include information whether or not the construction site located within a watershed of an ERW, ESW, or NSW. If the construction site is located within a watershed of an ERW, ESW, or NSW, then the SWPPP should consider using additional BMPs for these areas. The practices shall be considered during the progression of site activities and updates to the construction site SWPPP for continued protection of underground water resources.

F. *Documentation of Permit Eligibility related to potential losing stream and/or sensitive aquatic species native to these areas.* The SWPPP shall include information whether or not the construction site located within a watershed of a potential losing stream, and/or sensitive aquatic species native to these areas. If the construction site is located within a watershed of a potential losing stream and/or sensitive aquatic species native to these areas, then the SWPPP shall consider using BMPs for losing stream areas. The practices should be considered during the progression of site activities and updates to the facility SWPPP for continued protection of underground water resources.

G. *Attainment of Water Quality Standards After Authorization*.

1) The permittee shall select, install, implement, and maintain BMPs at the construction site and at the construction support activities off site that minimize pollutants in the discharge as necessary to meet applicable water quality standards. In general, except in situations explained below, the SWPPP shall be developed, implemented, and updated to be considered as stringent as necessary to ensure that the discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.

2) At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:

   a. Develop a supplemental BMP action plan describing SWPPP modifications to adequately address the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

   b. Cease discharges of pollutants from construction activity and submit an individual permit application.

3) All written responses required under this part shall include a signed certification (Part II.B.9).

H. *Site Map*. The SWPPP shall contain a legible site map (or multiple maps, if necessary) complete to scale, showing the entire site, that identifies, at a minimum, the following:

1) Pre-construction topographic view;
2) Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
3) Delineate on the site map areas of soil disturbance and areas that will not be disturbed with regards to the construction activities and construction support activities off site under the coverage of this permit;
4) Location of major structural and nonstructural controls identified in the plan;
5) Location of main construction entrance and exit;

6) Location where stabilization practices are expected to occur;
7) Locations of all construction support activities off-site (i.e. materials, waste, borrow area, or equipment storage areas);
8) Location of areas used for concrete wash-out;
9) Location of all waters of the State with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
10) Locations where stormwater is discharged to waters of the State or a municipal separate storm sewer system if applicable,
11) Locations where stormwater is discharged off-site (shall be continuously updated);
12) Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
13) A legend that clearly specifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
14) Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

I. *Stormwater Controls*. Each plan shall include a description of appropriate controls and measures that will be installed and implemented at the construction site. The plan shall clearly describe each construction activity identified in the project description control measures associated with the construction activity and the schedule during the construction process that the measures will be implemented. Perimeter controls for the site shall be installed after the clearing and grubbing necessary for installation of the measure, but before the clearing and grubbing for the remaining portions of the site. Perimeter controls shall be actively maintained until final stabilization of those portions of the site upward of the perimeter control. Temporary controls shall be removed and properly disposed of after final stabilization. The description and implementation of controls shall address the following minimum components:

1) Initial Site Stabilization, Erosion, and Sediment Controls and Best Management Practices. Design, install, implement, and maintain effective erosion and sediment controls to minimize the discharge of pollutants. At a minimum the following controls and BMPs shall be designed, installed, implemented, and maintained. Therefore, the SWPPP shall address, at a minimum, the following:

   a. For larger common plans of development or sale, only streets, drainage, utility areas, areas needed for initial construction of streets (e.g., borrow pits, parking areas, etc.) and areas needed for stormwater structures may be disturbed initially. Upon stabilization of the initial areas, additional areas may be disturbed.
   b. The construction-phase erosion (such as site stabilization) and sediment controls (such as check dams) shall be designed to retain sediment on-site to the extent practicable.
   c. All control measures shall be properly selected, installed, and maintained in accordance with the manufacturer's specifications, good engineering, and construction practices. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the permittee shall replace or modify the control for site situations.
   d. If sediment escapes the construction site, off site accumulations of sediment shall be removed before the next business day to minimize off-site impacts (e.g., to prevent fugitive sediment in a street could be washed into storm sewers by the next rain or pose a safety hazard to users of public streets). This permit does not give the authority to trespass onto other property; therefore this condition should be carried out along with the permission of neighboring land owners to remove sediment.
   e. Sediment shall be removed from sediment traps (if used, please specify what type) or sedimentation ponds when design capacity has been reduced by 50%.
   f. Litter, construction debris, and construction chemicals exposed to precipitation and to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls picked up daily).
   g. Construction support activities off site (i.e. material storage areas, overburden and stockpiles of dirt, borrow areas, etc.) used solely by the permitted project are considered a part of the project and shall be addressed in the SWPPP.

2) Stabilization practices. The SWPPP shall include, at a minimum, the following information:

a. Description and Schedule: A description of initial, interim, and permanent stabilization practices, including site-specific scheduling of the implementation of the practices. Site plans shall ensure that existing vegetation is preserved where attainable and that disturbed areas are stabilized. Stabilization practices may include, but not limited to: mulching, temporary seeding, permanent seeding, geotextiles, sod stabilization, natural buffer strips, protection of trees, and preservation of mature vegetation and other appropriate measures.

b. Description of natural buffer areas: DEQ requires that a natural buffer zone be established between the top of stream bank and the disturbed area. The SWPPP shall contain a description of how the site will maintain natural buffer zones. For construction projects where clearing and grading activities will occur, SWPPP shall provide at least twenty-five (25) feet of natural buffer zone from any named or unnamed streams, creeks, rivers, lakes or other water bodies. The plan shall also provide at least fifty (50) feet of natural buffer zone from established TMDL waterbodies, waterbodies listed on the 303(d) list, an ERW, ESW, NSW, or other uses at the discretion of the Director. If the site will be disturbed within the recommended buffer zone, then the buffer zone area shall be stabilized as soon as possible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law. Please note that above-grade clearing that does not disturb the soil in the buffer zone area does not have to comply with buffer zone requirements.

c. Records of Stabilization: A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included in the plan.

d. Deadlines for Stabilization After Construction Activity Temporarily Ceases: Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily ceased, but in no case more than fourteen (14) calendar days after the construction activity in that portion of the site has temporarily ceased, except:

(1) Where the initiation of stabilization measures by the fourteenth ($14^{th}$) calendar day after construction activity temporarily ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.

(2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.

e. Deadline for Stabilization After Construction Activity Permanently Ceases: Stabilization measures shall be initiated immediately in portions of the site where construction activities have permanently ceased, except:

(1) Where the initiation of stabilization measures immediately after construction activity permanently ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.

(2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.

3) Structural Practices. A description of structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site to the degree attainable. Structural practices should be placed on upland soils to the degree attainable. The installation of these devices may

be subject to Section 404 of the Clean Water Act. Such practices may include but are not limited to:

- silt fences (installed and maintained);
- earthen dikes to prevent run-on;
- drainage swales to prevent run-on;
- check dams;
- subsurface drains;
- pipe slope drains;
- storm drain inlet protection;
- rock outlet protection;
- sediment traps;
- reinforced soil retaining systems;
- gabions;
- temporary or permanent sediment basins.

A combination of erosion and sediment control measures is encouraged to achieve maximum pollutant removal. Adequate spillway cross-sectional area and re-enforcement shall be provided for check dams, sediment traps, and sediment basins.

a. Sediment Basins:

(1) For common drainage locations that serve an area with ten (10) or more acres (including run-on from other areas) draining to a common point, a temporary or permanent sediment basin that provides storage based on either the smaller of 3600 cubic feet per acre, or a size based on the runoff volume of a 10 year, 24 hour storm, shall be provided where attainable (so as not to adversely impact water quality) until final stabilization of the site. In determining whether installing a sediment basin is attainable, the operator may consider factors such as site soils, slope, available area on site, etc. Proper hydraulic design of the outlet is critical to achieving the desired performance of the basin. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. If "non-attainability" is claimed, then an explanation of non-attainability shall be included in the SWPPP**.** Where a sediment basin is not attainable, smaller sediment basins or sediment traps shall be used. Where a sediment basin is un-attainable, natural buffer strips or other suitable controls which are effective are required for all side slopes and down slope boundaries of the construction area. The plans for removal or final usage of the sediment basin shall be included with the description of the basin in the SWPPP.

(2) For drainage locations serving an area less than ten (10) acres, sediment traps, silt fences, or equivalent sediment controls are required for all side slope and down slope boundaries of the construction area unless a sediment basin providing storage based on either the smaller of 3600 cubic feet per acre, or a size based on the run off volume of a 10 year, 24 hour storm is provided. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. However, in order to protect the waters of the State, the Director, at their discretion, may require a sediment basin for any drainage areas draining to a common point.

b. Velocity Dissipation Devices:

Velocity dissipation devices shall be placed at discharge locations, within concentrated flow areas serving two

or more acres, and along the length of any outfall channel to provide a non-erosive flow velocity from the structure to a water course so that the natural physical and biological characteristics and functions are maintained and protected (i.e., no significant changes in the hydrological regime of the receiving water). Please note that the use of hay-bales is not recommended in areas of concentrated flow.

J. *Other Controls*.

1) No solid materials identified in Part I.B.13.D shall be discharged to waters of the State or offsite.
2) Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of a stabilized construction entrance and exit or vehicle tire washing.
3) For lots that are less than one (1) acre in size an alternative method may be used in addition to a stabilized construction entrance. An example of an alternative method could be daily street sweeping. This could allow for the shortening of the construction entrance.
4) The plan shall ensure and demonstrate compliance with applicable State or local waste disposal, temporary and permanent sanitary sewer or septic system regulations.
5) No liquid concrete waste shall be discharged to waters of the State. Appropriate controls to prevent the discharge of concrete washout waters shall be implemented if concrete washout will occur on-site.
6) No contaminants from fuel storage areas, hazardous waste storage and truck wash areas shall be discharged to waters of the State or offsite. Methods for protecting these areas shall be identified and implemented. These areas shall not be located near a waterbody, if there is a water body on or near the project.

K. *Non-stormwater discharges*. Sources of non-stormwater listed in Part I.B.10 of this permit that are combined with stormwater discharges associated with construction activity shall be identified in the plan. This list shall be site specific non-stormwater discharges.

L. *Post-Construction Stormwater Management*. The operator is required to provide a description of measures that will be installed during the construction process to control pollutants in stormwater discharges that will occur after construction operations have been completed. Structural measures shall be placed on upland soils to the degree attainable. The installation of these devices may be subject to Section 404 (Corps of Engineers) of the Clean Water Act. This permit only addresses the installation of stormwater management measures, and not the ultimate operation and maintenance of such structures after the construction activities have been completed and the site has undergone final stabilization. However, post-construction stormwater BMPs that discharge pollutants from a point source once construction is completed may need authorization under a separate DEQ NPDES permit. Such practices may include but are not limited to:

- infiltration of runoff onsite;
- flow attenuation by use of open vegetated swales and natural depressions;
- stormwater retention structures;
- stormwater detention structures (including wet ponds);
- sequential systems, which combine several practices.

A goal of at least eighty percent 80 % removal of total suspended solids from these flows which exceed predevelopment levels should be used in designing and installing stormwater management controls (where practicable). Where this goal is not met, the operator shall provide justification for rejecting each practice listed above based on site conditions.

M. *Applicable State or Local Programs*. The SWPPP shall be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site.

N. *Inspections*. Inspections shall be conducted by qualified personnel (provided by the operator). Inspections shall include all areas of the site disturbed by construction activity and construction support activities located off site that are exposed to precipitation and to stormwater. Inspectors shall look for evidence of, or the potential for, pollutants entering

the stormwater conveyance system. All stormwater control measures shall be observed to ensure proper installation, operation, and maintenance. Discharge locations shall be inspected to determine whether all stormwater control measures are effective in preventing significant impacts to waters of the State or offsite, where accessible. Where discharge locations are inaccessible, nearby downstream locations shall be inspected to the extent that such inspections are practicable. Locations where vehicles enter or exit the site shall be inspected for evidence of off-site sediment tracking. Inspections may not be required if the remaining lot(s) within a larger common plan of development or sale disturb less than one acre of land In addition, inspections may not be required on a completed section of a linear project if final stabilization has been completed for that section. Stabilized areas of the project shall be indicated in the SWPPP and site map and show what date they were stabilized. The operator shall ensure that no sediment will leave the lot(s) that are stabilized. These lots shall be identified within the SWPPP and show what date they were stabilized. If the operator is unable to ensure this, then inspections shall continue.

1) Inspection Frequency. Inspections shall be conducted in accordance with one of the following schedules listed below. The schedule **must be specified** in the SWPPP.

   a. At least once every seven (7) calendar days, or
   b. At least once every fourteen (14) calendar days and within twenty-four (24) hours of the end of a storm event of 0.25 inches or greater (a rain gauge must be maintained on-site).

2) Inspection Form. The DEQ inspection form should be used for all inspections. The inspection form shall include all stormwater controls that are being used on site as well as at construction support activities off site. The form is available on DEQ's website www.adeq.state.ar.us. If a different form is used, it shall at a minimum contain the following information:

   a. Inspector name and title;
   b. Date of Inspection;
   c. Amount of rainfall and days since last rain event (only applicable to Part II.A.4.N.1.b);
   d. Approximate beginning and duration of the storm event;
   e. Description of any discharges during inspection;
   f. Locations of discharges of sediment/other pollutants;
   g. Locations of BMPs in need of maintenance or where maintenance was performed;
   h. If the BMPs are in working order and if maintenance is required (including when scheduled and completed);
   i. Locations that are in need of additional controls;
   j. Location and dates when major construction activities begin, occur or cease;
   k. Signature of qualified signatory official, in accordance with Part II.B.9.

   Additional information may be added to the inspection report at the permittee's discretion.

3) Inspection Records. Each report shall be retained as part of the SWPPP for at least three (3) years from the date the site is finally stabilized. Each report shall be signed and have a certification statement in accordance with Parts II.B.9 and 10 of this permit.

4) Winter Conditions. Inspections will not be required at construction sites nor the construction support activities located off site where snow cover exists over the entire site for an extended period, and melting conditions do not exist. If there is any runoff from the site at any time during snow cover, melting conditions are considered to be existent at the site and this inspection waiver does not apply. Regular inspections, as required by this permit, are required at all other times as specified in this permit. If winter conditions prevent compliance with the permit, documentation of the beginning and ending date of winter conditions shall be included in the SWPPP.

5) Adverse Weather Conditions. Adverse conditions are those that are dangerous or create inaccessibility for personnel, such as local flooding, high winds, or electrical storms, or situations that otherwise make inspections

impractical, such as extended frozen conditions. When adverse weather conditions prevent the inspection of the site, an inspection shall be completed as soon as is safe and feasible. If adverse weather conditions prevent compliance with the permit, documentation of the beginning and ending date of adverse weather conditions shall be included in the SWPPP.

O. *Maintenance*. A description of procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition shall be outlined in the plan. Any repairs that are needed based on an inspection shall be completed, when practicable, before the next storm event, but not to exceed a period of three (3) business days of discovery, or as otherwise directed by state or local officials. However, if conditions do not permit large equipment to be used, a longer time frame is allowed if the condition is thoroughly documented on the inspection form. Maintenance for manufactured controls shall be done at a minimum of the manufacturer's specifications. Maintenance for non-manufactured controls, i.e. check dams and sediment traps, shall be done when 50% of treatment capacity remains.

P. *Employee Training*. The permittee/operator is responsible for training personnel, who are responsible for implementing activities identified in the SWPPP, on the components and requirements of the SWPPP and the requirements of the general permit. This includes contractors and subcontractors. Training shall be given by a knowledgeable and qualified trainer. The SWPPP shall identify periodic dates for such training for all personnel and records of training shall be maintained with the SWPPP. Training records that are maintained electronically (i.e. database, etc.) do not need to be maintained with the SWPPP, but shall be accessible upon request. Formal training classes given by Universities or other third-party organizations are not required but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.

**5. Plan Certification.** The SWPPP Certification shall be signed by either the operator or the cognizant official identified on the NOI. All documents required by the permit and other information requested by the Director shall be signed by operator or by a duly authorized representative of the operator (Please see Part II.B.10 below for certification).

## SECTION B: STANDARD PERMIT CONDITIONS

1. **Retention of Records.**

   A. The operator shall retain records of all Stormwater Pollution Prevention Plans, all inspection reports required by this permit, and records of all data used to complete the NOI to be covered by this permit for a period of at least three (3) years from the date the NOT letter is signed by DEQ. This period may be extended by request of the Director at any time.

   B. The operator shall retain a signed copy of the SWPPP and inspection reports required by this permit at the construction site from the date of project initiation to the date of final stabilization.

2. **Duty to Comply.** The operator shall comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the federal Clean Water Act and the Arkansas Water and Air Pollution Control Act and is grounds for: enforcement action; permit termination, revocation and re-issuance, or modification; or denial of a permit renewal application.

3. **Penalties for Violations of Permit Conditions.** The Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.) provides that any person who violates any provisions of a permit issued under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year, or a criminal penalty of not more than twenty five thousand dollars ($25,000) or by both such fine and imprisonment for each day of such violation. Any person who violates any provision of a permit issued under the Act may also be subject to civil penalty in such amount as the court shall find appropriate, not to exceed ten thousand dollars ($10,000) for each day of such violation. The fact that any such violation may constitute a misdemeanor shall not be a bar to the maintenance of such civil action. Any person that purposely, knowingly, or recklessly causes pollution of the water of the state in a manner not otherwise permitted by law and thereby places another person in imminent danger of death or serious bodily injury shall be guilty of a felony and shall be subject to imprisonment, a fine not more than two hundred fifty thousand dollars ($250,000), or both such fine and imprisonment.

4. **Continuance of the General Permit.** Permittees wishing to continue coverage under this general permit shall submit a Renewal NOI (see Part I.B.4 for where to submit documentation) up to 180 days prior to the expiration date, but no later than thirty (30) days prior to the expiration date. No additional fee is required to be submitted along with the Renewal NOI.

   An expired general permit continues in force and effect until a new general permit is issued. If this permit is not re-issued or replaced prior to the expiration date, it will be administratively continued in accordance with Ark. Code Ann. § 8-4-203(m) and remain in force and effect. If a permittee was granted permit coverage prior to the expiration date, the permittee will remain covered by the continued permit until the earliest of:

   A. The effective date of the re-issuance or replacement of this permit and a timely submittal of a renewal NOI by the operator; or

   B. The operator's submittal and DEQ approval of a NOT; or

   C. Issuance and effectiveness of an individual permit for the project's discharges and completion of item B of this section (see Part I.B.24); or

   D. A formal permit decision by DEQ to not re-issue this general permit, at which time operators must seek coverage under an alternative permit (see Part I.B.24).

   Small site operators are responsible for ensuring that the site is in compliance with any changes or updates of this general permit by reviewing DEQ's website at:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

5. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for an operator in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

6. **Duty to Mitigate.** The operator shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has reasonable likelihood of adversely affecting human health or the environment.

7. **Duty to Provide Information.** The operator shall furnish to the Director, an authorized representative of the Director, the EPA, a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or in the case of a stormwater discharge associated with industrial activity which discharges through a MS4 with an NPDES permit, to the municipal operator of the system, within a reasonable time, any information which is requested to determine compliance with this permit.

8. **Other Information.** When the operator becomes aware that he or she failed to submit any relevant facts or submitted incorrect information in the NOI or in any other report to the Director, he or she shall promptly submit such facts or information.

9. **Signatory Requirements.** All NOIs, reports, or information submitted to the Director shall be signed and certified by the operator.

   A. All NOI shall be signed as follows:

      1) For a corporation: by a responsible corporate officer. For purposes of this section, a responsible corporate officer means:

         a. A president, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or

         b. The manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to ensure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

      2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;

      3) For a municipality, State, Federal or other public agency: by either a principal executive or ranking elected official. For purposes of this section, a principal executive officer of a Federal agency includes:

         a. The chief executive officer of the agency; or

         b. A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.

   B. All reports required by the permit and other information requested by the Director shall be signed by a person described

above or by a duly authorized representative of that person. A person is a duly authorized representative only if:

1) The authorization is made in writing by a person described above and submitted to the Director;

2) The authorization specifies either an individual or a person having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility, or position of equivalent responsibility for environmental matters for the company (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and

3) Changes to authorization. If an authorization under this Part is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the above requirements shall be submitted to the Director prior to or together with any reports, information, or applications to be signed by an authorized representative.

**10. Certification.** Any person signing a document under this section shall make the following certification:

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Note: For this permit only, “this document” refers to the Stormwater Pollution Prevention Plan, “attachments” refers to the site map and inspection forms, and “system” is referencing the project site.

**11. Penalties for Falsification of Reports.** The Arkansas Water and Air Pollution Control Act provides that any person who knowingly makes any false statement, representation, or certification in any application, record, report, plan or other document filed or required to be maintained under this permit shall be subject to civil penalties specified in Part II.B.3 of this permit and/or criminal penalties under the authority of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.).

**12. Penalties for Tampering.** The Arkansas Water and Air Pollution Control act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year or a fine of not more than twenty five thousand dollars ($25,000) or by both such fine and imprisonment.

**13. Oil and Hazardous Substance Liability.** Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the operator from any responsibilities, liabilities, or penalties to which the operator is or may be subject under Section 311 of the Clean Water Act or Section 106 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).

**14. Property Rights.** The issuance of this permit does not convey any property rights of any sort or any exclusive privileges, nor does it authorize any injury to private property, any invasion of personal rights, or any infringement of Federal, State, or local laws or regulations.

**15. Severability.** The provisions of this permit are severable. If any provisions of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provisions to other circumstances and the remainder of this permit shall not be affected thereby.

**16. Transfers.** This permit is not transferable to any person except after notice to the Director. A transfer form shall be submitted to DEQ as required by this permit.

**17. Proper Operation and Maintenance.** The operator shall at all times:

A. Properly operate and maintain all systems of treatment and control (and related appurtenances) which are installed or used by the operator to achieve compliance with the conditions of this permit. This provision requires the operation of backup or auxiliary facilities or similar systems which are installed by an operator only when the operation is necessary to achieve compliance with the conditions of the permit.
B. Provide an adequate operating staff which is duly qualified to carry out operation, inspection, maintenance, and testing functions required to ensure compliance with the conditions of this permit.

**18. Inspection and Entry.** The operator shall allow the Director, the EPA, or an authorized representative, or, in the case of a construction site which discharges to a municipal separate storm sewer, an authorized representative of the municipal operator of the separate sewer system receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:

A. Enter upon the operator's premises where a regulated facility or activity is located or conducted, or where records shall be kept under the conditions of this permit;
B. Have access to and copy, at reasonable times, any records that shall be kept under the conditions of this permit;
C. Inspect at reasonable times any facilities or equipment, including monitoring and control equipment and practices or operations regulated or required by the permit;
D. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the CWA, any substances or parameters at any location on the permitted property.

**19. Permit Actions.** This permit may be modified, revoked and reissued, or terminated for any cause including, but not limited to, the following;

A. Violation of any terms or conditions of this permit;
B. Obtaining this permit by misrepresentation or failure to fully disclose all relevant facts;
C. A change in any conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge;
D. A determination that the permitted activity endangers human health or the environment and can only be regulated to acceptable levels by permit modification or termination; or
E. Failure of the operator to comply with the provisions of DEQ Rule 9 (Fee Rule). Failure to promptly remit all required fees shall be grounds for the Director to initiate action to terminate this permit under the provisions of 40 C.F.R. §122.64 and §124.5(d), as adopted by reference in DEQ Rule 6, and the provisions of DEQ Rule 8.

**20. Re-Opener Clause.**

A. If there is evidence indicating potential or realized impacts on water quality due to any stormwater discharge associated with industrial activity covered by this permit, the operator of such discharge may be required to obtain an individual permit or an alternative general permit in accordance with Part I.B.24 of this permit, or the permit may be modified to include different limitations and/or requirements.

B. Permit modification or revocation will be conducted in accordance with the provisions of 40 C.F.R. §122.62, §122.63, §122.64 and §124.5, as adopted by reference in DEQ Rule 6.

**21. Local Requirements.** All dischargers shall comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding any discharges of stormwater to storm drain systems or other water sources under their jurisdiction, including applicable requirements in municipal stormwater management programs developed to

comply with the DEQ permits. Dischargers shall comply with local stormwater management requirements, policies, or guidelines including erosion and sediment control.

22. **Applicable Federal, State, or local Requirements.** Permittees are responsible for compliance with all applicable terms and conditions of this permit. Receipt of this permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance policy, or regulation. Nothing in this permit shall be construed to preclude the institution of any legal action or enforcement actions or relieve the permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable local state, or federal law or regulation.

# New Facility For:
# Butler Center
# 1109 N Reynolds Road
# Bryant, AR 72022

## STORM WATER MAINTENANCE PLAN

The Reynolds Road Storage owner will be responsible for the inspection and maintenance of the stormwater detention pond located on its.


Inspections are to be scheduled as directed in this document. All documentation on scheduled inspections, dates of inspections, and maintenance completed shall be retained by the Reynolds Road Storage owner for a period of three years.

**DETENTION PIPES**

Annual Maintenance (as applicable):

[ ] Check pipes for sediment in-fill, clean when necessary

[ ] Check outlets for clogging with trash or dead vegetation, clean when necessary




Michael Butler
Butler Wealth Capital, LLC

03/07/2023
date

# INSPECTION REPORT

**DATE: / /**

**BUTLER CENTER**




OUTLET

DETENTION PIPE

**COMMENT**

# NEW FACILITY FOR:
# BUTLER CENTER
# CITY OF BRYANT, AR
## DRAINAGE CALCULATIONS – SUMMARY
### 3/2/2023

**DESCRIPTION OF PROJECT**

Butler center is an approximately 1.51 Acre development located in the City of Bryant, Arkansas approximately a mile south of Reynolds Road. There are three drainage basins on the site. Eastern and Southern basins are small and will not be detained. The large basin will be detained in a pipe network storage located in the western end of the site. The detention for the storage network will be underground in 30" HDPE pipe.

Stormwater Calculations were prepared with the intent to comply with the City of Bryant's Drainage Code. The primary intent of this analysis is to produce a drainage system adequately sized to convey post development runoff while attenuating post development discharge levels equal to or less than pre development flows.

Hydraulic calculations were made using the Rational Method. Design frequencies were analyzed for 2, 5, 10, 25, 50, and 100 year return periods.

These calculations are divided into the following sections:

**Summary of Drainage Basins**

**Summary of Inlets**

**Summary of Pipes**

**Pipe Network Storage Summary**

**Appendices**

Exhibit A – Pre-Development Drainage Basins

Exhibit B – Post-Development Drainage Basins

# NEW FACILITY FOR:
# BUTLER CENTER
# CITY OF BRYANT, AR
## DRAINAGE CALCULATIONS – SUMMARY
### 3/2/2023

**SUMMARY OF DRAINAGE BASINS**

PRE-DEVELOPMENT CONDITIONS

There are three drainage basins on the site. Basin 1 drains to east side and Basin 3 drains to south side of the site. This discharge will not be captured. Basin 2 is developed. This discharge will be captured. The existing site is a mixture of gravel, grass and a building.

POST-DEVELOPMENT CONDITIONS

As previously described, this site is being developed into a commercial facility. Slopes range from 1% to 8%. Runoff drains from the developed areas to underground detention in the south western section of the development.

**SUMMARY OF INLETS**

On the drainage plan you will see labels for all of the inlets for these calculations. The flows shown are for the 10-year return storm. The distance from the face of the curb to the center of the street is 15 feet.

**SUMMARY OF PIPES**

All pipes used in this project are HDPE and RCP. Therefore, a manning's of 0.012 was used on all pipes in the analysis.

**PIPE NETWORK STORAGE SUMMARY**

The pipe network storage in these calculations detains flows from all of the runoff of the site. The pipe network storage is located in the south western portion of the property. Water collected in the storm water system is discharged into the pipe network via curb inlets. The pipe network storage is made of 263 linear feet of 30" HDPE and RCP pipe and has a volume of 1,289 cf. A concrete control structure is constructed on the southern end of the pipe network storage. This control structure uses a slotted weir to limit the discharge through the structure to that of the 2, 10, 25, 50, and 100-year pre-development flow. The pipe network storage is designed to hold the 100-year storm event.

TPOST

TPOST

SDMH
RIM=432.16'
8" MP OUT (N)=427.91'
8" MP IN (S)=427.97'

6.5N/30" SWEETGUM TREE

4.2N/14" TREE

6S/32" PINE TREE

6.1S/38" PINE TREE

8.2S/38" PINE TREE

16"S12" TREE

6" TREE

6" TREE

6" TREE

6.5S/24" TREE

**BASIN 2**
C=0.49
I=10.00 IN/HR
A=1.18 ACRES
$Q_{100}$=5.79 CFS

5.7N/40" HACKBERRY TREE

**BASIN 3**
C=0.47
I=10.00 IN/HR
A=0.16 ACRES
$Q_{100}$=0.75 CFS

6" HACKBERRY TREE

4.3S/22" SWEETGUM TREE

SWEETGUM TREE

30" SPLIT TREE

2.8S/10" HACKBERRY TREE

8" ELM TREE

SDMH
RIM=436.18'
18" RCP (OUT)=432.90'

SDMH
RIM=436.13'
18" RCP (IN)=432.00'

12" PEAR TREE

**BASIN 1**
C=0.73
I=10.00 IN/HR
A=0.17 ACRES
$Q_{100}$=1.25 CFS

3.5N/16" SPLIT MAGNOLIA TREE

3.4N/20" HACKBERRY TREE

FFE
440.90

60.3'

16" HACKBERRY TREES

4N/24" HACKBERRY TREE

6" MIMOSA TREE

5N/26" CEDAR TREE

4N/12" WATER OAK TREE

3-6" SPLIT TREES

3.4N/14" HACKBERRY TREE

32'

2.8S/16" TREE

3.4E/8" TREE

HIGHWAY #183/REYNOLDS ROAD
(80' R/W)

N

20' 10' 0 20'

| BY | REVISION | DATE |
|---|---|---|
| | | |

**GNE** Designing our client's success


**GarNat Engineering, LLC**
P.O. Box 116
Benton, AR 72018
Ph (501) 408-4650
3825 Mt Carmel Rd
Bryant, AR 72022
garnatengineering@gmail.com


**NEW FACILITY FOR:**
**BUTLER CENTER**
**CITY OF BRYANT, AR**

..\..\Document Scans\PE Stamps\VERNONS NEW TEMPLATE.jpg


CONTENTS:
PRE
DRAINAGE
PLAN

PROJECT NO:
22203

DATE:
FEB 2023

SHEET NO:
1.0


a:\Projects\2022 Projects\22203 Butler Center 1109 North Reynolds Road Kenny Whitfield\Drawings\CAD's\Design\22203 1109 N Reynolds Rd Design.dwg




**NEW FACILITY FOR:**
**BUTLER CENTER**
**CITY OF BRYANT, AR**


**GNE** Designing our client's success

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018
Ph (501) 408-4650

3825 Mt Carmel Rd
Bryant, AR 72022
garnatengineering@gmail.com


| DATE | REVISION | BY |
|---|---|---|
| | | |

CONTENTS: POST DRAINAGE PLAN

PROJECT NO: 22203

DATE: FEB 2023

SHEET NO: 2.0

J:\Projects\2022 Projects\22203 Butler Center 1109 North Reynolds Road Kenny Whitfield\Drawings\DWGs\Design\22203 1109 N Reynolds Rd Design.dwg

**Stormwater Calcs - Butler Center**
**Using Rational Method**

Pre-development

**Calculated Tc values - Drainage Basin 1 & 3**

$$Tc = \frac{56 * L^{.6} * n^{.6}}{i^{.4} * S^{.3}} \text{ seconds}$$

| | | | |
|---|---|---|---|
| L1 = | 100 | feet | |
| n1 = | 0.03 | | |
| S1 = | 0.032 | ft/ft | |
| $I_{assumed}$ = | 8.40 | inches | |
| $Tc_{calculated}$ | 130 | seconds | |
| $Tc_{calculated}$ | 2.16 | minutes | |
| Tc = | 2.16 | minutes | Tc for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| I = | 8.40 | inches | i for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| Use Tc = | **5.00** | minutes | |

| | | | | | |
|---|---|---|---|---|---|
| $I_{100}$ = | 10 | Inches | $I_{10}$ = | 7.2 | Inches |
| $I_{50}$ = | 9.2 | Inches | $I_{5}$ = | 6.5 | Inches |
| $I_{25}$ = | 8.40 | Inches | $I_{2}$ = | 5.6 | Inches |

**Calculated Tc values - Drainage Basin 2**

$$Tc = \frac{56 * L^{.6} * n^{.6}}{i^{.4} * S^{.3}} \text{ seconds}$$

| | | | |
|---|---|---|---|
| L1 = | 320 | feet | |
| n1 = | 0.03 | | |
| S1 = | 0.032 | ft/ft | |
| $I_{assumed}$ = | 8.40 | inches | |
| $Tc_{calculated}$ | 261 | seconds | |
| $Tc_{calculated}$ | 4.35 | minutes | |
| Tc = | 4.35 | minutes | Tc for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| I = | 8.40 | inches | i for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| Use Tc = | **5.00** | minutes | |

| | | | | | |
|---|---|---|---|---|---|
| $I_{100}$ = | 10 | Inches | $I_{10}$ = | 7.2 | Inches |
| $I_{50}$ = | 9.2 | Inches | $I_{5}$ = | 6.5 | Inches |
| $I_{25}$ = | 8.40 | Inches | $I_{2}$ = | 5.6 | Inches |

**Stormwater Calcs - Butler Center**
**Using Rational Method**

Post-development

**Calculated Tc values - Drainage Basin 1, 2 & 3**

$$Tc = \frac{56 * L^{.6} * n^{.6}}{i^{.4} * S^{.3}} \text{ seconds}$$

| | | |
|---|---|---|
| L1 = | 320 | feet |
| n1 = | 0.013 | |
| S1 = | 0.035 | ft/ft |
| $I_{assumed}$ = | 8.40 | inches |
| $Tc_{calculated}$ | 154 | seconds |
| $Tc_{calculated}$ | 2.56 | minutes |

| | | | |
|---|---|---|---|
| Tc = | 2.56 | minutes | Tc for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| I = | 8.40 | inches | i for 25-yr Storm from Exhibit 400-1 of Bryant Drainage Manual |
| Use Tc = | **5.00** | minutes | |

| | | | |
|---|---|---|---|
| $I_{100}$ = | 10 Inches | $I_{10}$ = | 7.2 Inches |
| $I_{50}$ = | 9.2 Inches | $I_{5}$ = | 6.5 Inches |
| $I_{25}$ = | 8.40 Inches | $I_{2}$ = | 5.6 Inches |

**Stormwater Calcs - Butler Center**
**using Rational Method**

**Pre-development**

**Calculated C values - Drainage Basin 1**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
| Greenspace | 0.08 | 0.47 | 0.43 | 0.4 | 0.36 | 0.34 | 0.31 | Flat, 0-2% |
| | | | | | | | | |
| Driveway | 0.09 | 0.97 | 0.92 | 0.88 | 0.83 | 0.8 | 0.75 | Road |
| **Total Area =** | **0.17** | **0.73** | **0.69** | **0.65** | **0.61** | **0.58** | **0.54** | |

**Calculated C values - Drainage Basin 2**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
| Greenspace | 1.09 | 0.47 | 0.43 | 0.4 | 0.36 | 0.34 | 0.31 | Flat, 0-2% |
| Gravel | 0.07 | 0.65 | 0.55 | 0.5 | 0.35 | 0.3 | 0.25 | Gravel |
| Roof | 0.02 | 0.97 | 0.92 | 0.88 | 0.83 | 0.8 | 0.75 | Roof |
| **Total Area =** | **1.18** | **0.49** | **0.45** | **0.42** | **0.37** | **0.35** | **0.32** | |

**Calculated C values - Drainage Basin 3**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
| Greenspace | 0.16 | 0.47 | 0.43 | 0.4 | 0.36 | 0.34 | 0.31 | Flat, 0-2% |
| | | | | | | | | |
| | | | | | | | | |
| **Total Area =** | **0.16** | **0.47** | **0.43** | **0.40** | **0.36** | **0.34** | **0.31** | |

**Stormwater Calcs - Butler Center**
**using Rational Method**

**Post-development**

**Calculated C values - Drainage Basin 1**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ |
|---|---|---|---|---|---|---|---|
| | | | | | | | |
| Greenspace | 0.13 | 0.46 | 0.42 | 0.39 | 0.35 | 0.32 | 0.29 |
| | | | | | | | |
| | | | | | | | |
| **Total Area =** | **0.13** | **0.46** | **0.42** | **0.39** | **0.35** | **0.32** | **0.29** |

(C values taken from Table 400-2 of City of Bryant Drainage Manual)

Good Condition, Average 2-7%

**Calculated C values - Drainage Basin 2**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ |
|---|---|---|---|---|---|---|---|
| | | | | | | | |
| Greenspace | 0.05 | 0.46 | 0.42 | 0.39 | 0.35 | 0.32 | 0.29 |
| | | | | | | | |
| Roof/Pavement | 0.90 | 0.97 | 0.92 | 0.88 | 0.83 | 0.8 | 0.75 |
| **Total Area =** | **0.95** | **0.94** | **0.89** | **0.85** | **0.80** | **0.77** | **0.73** |

(C values taken from Table 400-2 of City of Bryant Drainage Manual)

Good Condition, Average 2-7%

Road

**Calculated C values - Drainage Basin 3**

| | Area | $C_{100}$ | $C_{50}$ | $C_{25}$ | $C_{10}$ | $C_5$ | $C_2$ |
|---|---|---|---|---|---|---|---|
| | | | | | | | |
| Greenspace | 0.34 | 0.46 | 0.42 | 0.39 | 0.35 | 0.32 | 0.29 |
| | | | | | | | |
| | | | | | | | |
| **Total Area =** | **0.34** | **0.46** | **0.42** | **0.39** | **0.35** | **0.32** | **0.29** |

(C values taken from Table 400-2 of City of Bryant Drainage Manual)

Good Condition, Average 2-7%

**Stormwater Calcs - Butler Center**
**using Rational Method**

## Pre-development

### Drainage Basin 1

| $Q_{100}$ = | 1.25 CFS | $Q_{50}$= | 1.08 CFS | $Q_{25}$ = | 0.93 CFS | $Q_{10}$ = | 0.75 CFS | $Q_5$ = | 0.64 CFS | $Q_2$ = | 0.52 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.73 | c = | 0.69 | c = | 0.65 | c = | 0.61 | c = | 0.58 | c = | 0.54 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 0.17 acres | A= | 0.17 acres | A= | 0.17 acres | A= | 0.17 acres | A= | 0.17 acres | A= | 0.17 acres |

### Drainage Basin 2

| $Q_{100}$ = | 5.79 CFS | $Q_{50}$= | 4.85 CFS | $Q_{25}$ = | 4.12 CFS | $Q_{10}$ = | 3.13 CFS | $Q_5$ = | 2.66 CFS | $Q_2$ = | 2.08 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.49 | c = | 0.45 | c = | 0.42 | c = | 0.37 | c = | 0.35 | c = | 0.32 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 1.18 acres | A= | 1.18 acres | A= | 1.18 acres | A= | 1.18 acres | A= | 1.18 acres | A= | 1.18 acres |

### Drainage Basin 3

| $Q_{100}$ = | 0.75 CFS | $Q_{50}$= | 0.63 CFS | $Q_{25}$ = | 0.54 CFS | $Q_{10}$ = | 0.41 CFS | $Q_5$ = | 0.35 CFS | $Q_2$ = | 0.28 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.47 | c = | 0.43 | c = | 0.40 | c = | 0.36 | c = | 0.34 | c = | 0.31 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 0.16 acres | A= | 0.16 acres | A= | 0.16 acres | A= | 0.16 acres | A= | 0.16 acres | A= | 0.16 acres |

## Post-development

### Drainage Basin 1

| $Q_{100}$ = | 0.60 CFS | $Q_{50}$= | 0.50 CFS | $Q_{25}$ = | 0.43 CFS | $Q_{10}$ = | 0.33 CFS | $Q_5$ = | 0.27 CFS | $Q_2$ = | 0.21 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.46 | c = | 0.42 | c = | 0.39 | c = | 0.35 | c = | 0.32 | c = | 0.29 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 0.13 acres | A= | 0.13 acres | A= | 0.13 acres | A= | 0.13 acres | A= | 0.13 acres | A= | 0.13 acres |

### Drainage Basin 2

| $Q_{100}$ = | 8.96 CFS | $Q_{50}$= | 7.81 CFS | $Q_{25}$ = | 6.82 CFS | $Q_{10}$ = | 5.50 CFS | $Q_5$ = | 4.78 CFS | $Q_2$ = | 3.86 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.94 | c = | 0.89 | c = | 0.85 | c = | 0.80 | c = | 0.77 | c = | 0.73 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 0.95 acres | A= | 0.95 acres | A= | 0.95 acres | A= | 0.95 acres | A= | 0.95 acres | A= | 0.95 acres |

### Drainage Basin 3

| $Q_{100}$ = | 1.56 CFS | $Q_{50}$= | 1.31 CFS | $Q_{25}$ = | 1.11 CFS | $Q_{10}$ = | 0.86 CFS | $Q_5$ = | 0.71 CFS | $Q_2$ = | 0.55 CFS |
|---|---|---|---|---|---|---|---|---|---|---|---|
| c = | 0.46 | c = | 0.42 | c = | 0.39 | c = | 0.35 | c = | 0.32 | c = | 0.29 |
| i= | 10.00 in/hr | i= | 9.20 in/hr | i= | 8.40 in/hr | i= | 7.20 in/hr | i= | 6.50 in/hr | i= | 5.60 in/hr |
| A= | 0.34 acres | A= | 0.34 acres | A= | 0.34 acres | A= | 0.34 acres | A= | 0.34 acres | A= | 0.34 acres |

## Detention Volume

Pond-1
for Q100

| | | |
|---|---|---|
| Cundev= | 0.49 | |
| Iundev= | 10.00 | in/hr |
| Cdev= | 0.94 | |
| Idev= | 10.00 | in/hr |
| R= | 4.52 | |
| A= | 0.95 | acres |
| Tc= | 5.00 | minutes |
| | 60 | sec/min |

Detention Volume= 1,289 cubic feet

R= (Cdev*Idev)-(Cundev*Iundev)
Detention Volume= R*A*Tc*60

**Stormwater Calcs - Butler Center**
**using Rational Method**
**Weir & Detention Pond Sizing**

| Storm Event | Flow (cfs) |
|---|---|
| Q2 - Pre Basin 2 | 2.08 |
| Q10 - Pre Basin 2 | 3.13 |
| Q25 - Pre Basin 2 | 4.12 |
| Q50 - Pre Basin 2 | 4.85 |
| Q100 - Pre Basin 2 | 5.79 |
| Q10 - Post Basin 2 | 5.50 |
| Q25 - Post Basin 2 | 6.82 |
| Q100 - Post Basin 2 | 8.96 |

**Rectangular Weir**

Q2

| Q (cfs) | **CLH^1.5** |
|---|---|
| | |
| C | **2.5** |
| L | **0.5** 6" |
| H | **1.33** |
| | |
| Q (cfs) | **1.92** |

Q10

| Q (cfs) | **CLH^1.5** |
|---|---|
| | |
| C | **2.5** |
| L | **0.5** 6" |
| H | **1.75** |
| | |
| Q (cfs) | **2.89** |

Q25

| Q (cfs) | **CLH^1.5** |
|---|---|
| | |
| C | **2.5** |
| L | **0.5** 6" |
| H | **2.17** |
| | |
| Q (cfs) | **4.00** |

Q50

| Q (cfs) | **CLH^1.5** |
|---|---|
| | |
| C | **2.5** |
| L | **0.5** 6" |
| H | **2.33** |
| | |
| Q (cfs) | **4.45** |

Q100

| Q (cfs) | **CLH^1.5** |
|---|---|
| | |
| C | **2.5** |
| L | **0.5** 6" |
| H | **2.5** |
| | |
| Q (cfs) | **4.94** |

Pond Volume
Volume Required 1289 CF

Use 36" Pipe

Dia = 30.00
A = 4.91 SF
L (required) = 262.61 FT

**Stormwater Calcs - Butler Center**
**Detention Culverts**

| PIPE NAME | DIAMETER (IN) | LENGTH (FT) | AREA (SF) | VOLUME (CF) |
|---|---|---|---|---|
| PIPE 141 | 30.00 | 117 | 4.91 | 574.47 |
| PIPE 139 | 30.00 | 121 | 4.91 | 594.11 |
| PIPE 140 | 30.00 | 46 | 4.91 | 225.86 |
| **TOTAL** | | 284 | | **1394.44** |

**Stormwater Calcs - Butler Center**
**Outlet Pipe Capacity**

OUTLET CULVERT

| Pipe | From | To | Design Flow (cfs): | Slope (ft/ft): | Diameter (inches) | No. Pipes | Manning's | Area Full (sf) | Wetted Perimeter Full (ft) | Hydraulic Radius Full (ft) | Flow Capacity (cfs) | % Capacity |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 18" HDPE | East | West | 5.79 | 0.0050 | 18 | 1 | 0.012 | 1.77 | 4.712 | 0.375 | 8.05 | 72% |


**Stormwater Calcs - Butler Center**

Ditch Capacity

Mannings equation for ditch

n= 0.022 based on n for open channel earth with short grass, few weeds

| Depth (ft) | Width Bottom (ft) | Top (ft) | area (ft^2) | rH | slope (ft/ft) | Velocity (ft/s) | Q (cfs) |
|---|---|---|---|---|---|---|---|
| 0.75 | 0.00 | 4.50 | 1.69 | 0.36 | 1.000% | 3.40 | 5.74 |




| BY | REVISION | DATE |
|---|---|---|
| | | |

**GNE** Designing our client's success


**GarNat Engineering, LLC**
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com


**NEW FACILITY FOR:**
**BUTLER CENTER**
**CITY OF BRYANT, AR**

..\..\..\Document Scans\PE Stamps\ARSIGNS NEW TEMPLATE.jpg

CONTENTS:

INLET BASIN PLAN

PROJECT NO:
22203

DATE:
FEB 2023

SHEET NO:
3.0


a:\Projects\2022 Projects\22203 Butler Center 1109 North Reynolds Road Kenny Mitchell\Drawings\ARCH\Design\22203 1109 N Reynolds Rd Design.dwg

**Stormwater Calcs - Butler Center**
**Using Rational Method**

Post-development Basin

**Calculated Tc values - Drainage Basin CI-1**

$$Tc = \frac{56 * L^{.6} * n^{.6}}{i^{.4} * S^{.3}} \text{ seconds}$$

| | | | |
|---|---|---|---|
| L1 = | 700 | | feet |
| n1 = | 0.013 | | Smooth Concrete/Asphalt |
| S1 = | 0.031 | | ft/ft |
| $I_{assumed}$ = | 7.20 | | inches |
| $Tc_{calculated}$ | | 271 | seconds |
| $Tc_{calculated}$ | | 4.52 | minutes |
| Tc = | 4.52 | | minutes |
| I = | 7.20 | | inches |
| Use Tc = | **5.00** | | minutes |

**Stormwater Calcs - Butler Center**
**using Rational Method**
**POST-DEV C VALUES**

CI-1

| | Area | $C_{10}$ | $C_{25}$ | $C_{100}$ | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
|---|---|---|---|---|---|
| | 0.41 | 0.83 | 0.88 | 0.97 | Asphalt/Roof |
| **Total Area =** | **0.41** | **0.83** | **0.88** | **0.97** | |

CI-2

| | Area | $C_{10}$ | $C_{25}$ | $C_{100}$ | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
|---|---|---|---|---|---|
| | 0.09 | 0.83 | 0.88 | 0.97 | Asphalt/Roof |
| **Total Area =** | **0.09** | **0.83** | **0.88** | **0.97** | |

CI-4

| | Area | $C_{10}$ | $C_{25}$ | $C_{100}$ | (C values taken from Table 400-2 of City of Bryant Drainage Manual) |
|---|---|---|---|---|---|
| | 0.29 | 0.83 | 0.88 | 0.97 | Asphalt/Roof |
| **Total Area =** | **0.29** | **0.83** | **0.88** | **0.97** | |

**Stormwater Calcs - Butler Center**
**using Rational Method**
**Post Development Flowrates**

CI-1

| | | |
|---|---|---|
| $Q_{10}$ = | 2.45 | CFS |
| c = | 0.83 | |
| i= | 7.20 | in/hr |
| A= | 0.41 | acres |

CI-2

| | | |
|---|---|---|
| $Q_{10}$ = | 0.54 | CFS |
| c = | 0.83 | |
| i= | 7.20 | in/hr |
| A= | 0.09 | acres |

CI-4

| | | |
|---|---|---|
| $Q_{10}$ = | 1.73 | CFS |
| c = | 0.83 | |
| i= | 7.20 | in/hr |
| A= | 0.29 | acres |

# Stormwater Calcs - Butler Center GUTTER SPREAD 10-YR STORM

## CI-1

$$T = \left( \frac{Q^* n}{k_u^* S_x^{1.67} * S_L^{0.5}} \right)^{.375}$$

| | | | |
|---|---|---|---|
| | | | Q= Flowrate(cfs) |
| Q | 2.45 | cfs | n=manning's number |
| n | 0.012 | | k=0.56 |
| $k_u$ | 0.56 | | $S_x$= cross slope |
| $S_x$ | 0.028 | | $S_L$= longitudinal slope |
| $S_L$ | 0.031 | | T= Gutter Spread |
| T | **5.96** | ft | |

## CI-2

$$T = \left( \frac{Q^* n}{k_u^* S_x^{1.67} * S_L^{0.5}} \right)^{.375}$$

| | | |
|---|---|---|
| Q | 0.54 | cfs |
| n | 0.012 | |
| $k_u$ | 0.56 | |
| $S_x$ | 0.03 | |
| $S_L$ | 0.017 | |
| T | **3.62** | ft |

## CI-4

$$T = \left( \frac{Q^* n}{k_u^* S_x^{1.67} * S_L^{0.5}} \right)^{.375}$$

| | | |
|---|---|---|
| Q | 1.73 | cfs |
| n | 0.012 | |
| $k_u$ | 0.56 | |
| $S_x$ | 0.028 | |
| $S_L$ | 0.03 | |
| T | **5.34** | ft |

# Stormwater Calcs - Butler Center - CURB INLETS

**10-YEAR STORM**

| Area # | Area | I | C | Q (cfs) | Weir Q=3.0LY^1.5 Q (cfs) | Y (ft) | Required L (ft) | Actual L (ft) | |
|---|---|---|---|---|---|---|---|---|---|
| CI-1 | 0.41 | 7.20 | 0.83 | 2.45 | 2.45 | 0.49 | **2.38** | **5** | 5' box |
| CI-2 | 0.09 | 7.20 | 0.83 | 0.54 | 0.54 | 0.49 | **0.52** | **5** | 5' box |
| CI-4 | 0.29 | 7.20 | 0.83 | 1.73 | 1.73 | 0.49 | **1.68** | **5** | 5' box |

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018

March 8, 2023

Mr. Truett Smith
Bryant Planning Coordinator/Planning Commission Secretary
210 SW 3rd Street
Bryant, AR 72022

Re: Large Scale Development Commercial Building – Butler Center

Dear Mr. Smith:

Please allow this letter and following list of enclosures to serve as my application for approval of the referenced large scale development. It is my desire that this matter be included on the agenda for your May 2023 City of Bryant Planning Commission Meeting.

List of Enclosures

- 2 Full Set Plans
- Affidavit
- 8 copies of Site Plan
- Drainage Study
- Bryant Large Development Checklist
- ADA/ABA Form

If you have questions or need any additional information, please do not hesitate to contact me.

Sincerely,
GarNat Engineering, LLC

Vernon J. Williams

Vernon J. Williams, P.E., President

# AFFIDAVIT

I, Michael Butler, Butler Wealth Capital, LLC certify by my signature below that I hereby authorize Vernon Williams of GarNat Engineering, LLC to act as Butler Wealth Capital, LLC's agent regarding the Planning Commission Approval of the proposed development at 1109 N Reynolds Road.

Michael Butler
Butler Wealth Capital, LLC

03/07/2023
Date

Subscribed and sworn to me a Notary Public on this 7TH day of MARCH, 2023.

Notary Public

My Commission Expires:

02-05-2031

GEORGE P. WOODEN
Notary Public-Arkansas
Saline County
My Commission Expires 02-05-2031
Commission # 12714343

# LANDSCAPING NOTES:

1. REPORT ANY DISCREPANCIES FOUND IN THE PLANS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ADVISE THE DESIGNER OF ANY CONDITION FOUND ON THE SITE WHICH PROHIBITS INSTALLATION AS SHOWN ON THESE DRAWINGS.

2. THE NUMBER OF PLANTS OR INTENDED COVERAGE AREAS SHOWN SHALL SUPERSEDE NOTED QUANTITIES. TREE LOCATIONS ARE DIAGRAMMATIC.

3. ALL PLANT MATERIALS MUST BE APPROVED PRIOR TO INSTALLATION. SUBSTITUTIONS OF SIZE OR TYPE OF MATERIAL ARE NOT PERMITTED WITHOUT WRITTEN APPROVAL PRIOR TO DELIVERY OR INSTALLATION.

4. ALL PLANT MATERIALS SHALL BE MAINTAINED IN A HEALTHY AND GROWING CONDITION. REPLACE ANY DAMAGED, DESTROYED, OR REMOVED PLANT MATERIALS WITH THE SAME VARIETY AND SIZE PRIOR TO FINAL ACCEPTANCE.

5. PLANT STORAGE TO BE LOCATED OUT OF VEHICULAR USE AREAS AND NEAR A WATERING SYSTEM TO OPTIMIZE SURVIVAL.

6. ALL PLANTING BEDS SHALL BE IRRIGATED BY AN AUTOMATIC UNDERGROUND IRRIGATION SYSTEM.

7. ALL PLANTING BEDS SHALL BE MULCHED WITH 3-INCHES SHREDDED HARDWOOD OR CYPRESS MUCH.

8. ALL SHRUBS AND TREES SHALL RECEIVE PLANTING BACKFILL OF 2/3 TOPSOIL AND 1/3 COMPOST BY VOLUME AND 2 POUNDS OF 14-14-14 TIMED-RELEASE FERTILIZER PER CUBIC YARD OF BACKFILL.

9. ALL BEDS INSIDE LAWN AREAS TO BE EDGED WITH 4" PAINTED STEEL EDGING.

10. ALL TREES AND SHRUBS SHALL BE THOROUGHLY WATERED IMMEDIATELY AFTER PLANTING.

11. TREES SHALL NOT BE TOPPED AT ANY TIME. PROPER TREE PRUNING TECHNIQUES AS ESTABLISHED BY THE LATEST EDITION OF ANSI A300 STANDARDS FOR TREE CARE SHALL BE UTILIZED FOR MAINTENANCE PURPOSES.

12. COORDINATE ALL INSTALLATION ACTIVITIES WITH IRRIGATION WORK AND IMMEDIATELY REPAIR DAMAGES TO FINISH GRADES, SOD, AND PLANT MATERIALS UNTIL FINAL ACCEPTANCE.

13. SEE GRADING AND DRAINAGE PLAN FOR PROPOSED SLOPES, SWALES, BERMS, AND WATER FEATURES. MAINTAIN PROPER FINISH GRADES IN ALL AREAS AS INDICATED.

14. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR FINE GRADING, REMOVAL OF MISCELLANEOUS DEBRIS AND ANY ADDITIONAL FILL REQUIRED TO PROVIDE MINIMUM TOPSOIL DEPTHS AND CREATE A SMOOTH CONDITION PRIOR TO PLANTING IN ALL AREAS.

15. TOPSOIL SHALL BE FREE OF STONES, ROOTS, CLODS, AND ANY OTHER FOREIGN MATERIAL THAT IS NOT BENEFICIAL FROM PLANT GROWTH.


16. LANDSCAPE AND OPEN AREAS SHALL BE KEPT FREE OF TRASH, LITTER, AND WEEDS AT ALL TIMES DURING CONSTRUCTION.

17. IDENTIFICATION LABELS MUST BE ATTACHED TO ALL PLANT MATERIALS AND SHALL REMAIN INTACT UNTIL FINAL ACCEPTANCE OF THE WORK. REMOVE ALL TAGS AND LABELS FOLLOWING FINAL ACCEPTANCE.

18. CALIPER OF TREES TO BE MEASURED 6-INCHES ABOVE GROUND LEVEL FOR TREES UP TO 4-INCH CALIPER SIZE.

19. GENERAL CONTRACTOR SHALL PROVIDE 6-INCH DIAMETER MINIMUM SCHEDULE 40 PVC SLEEVING FOR IRRIGATION TO ALL CURB ISLANDS AND UNDER ALL DRIVE ISLE CROSSINGS.

20. CONTRACTOR TO REFER TO THE UTILITY PLAN SHEET FOR RECENT FIRE FLOW INFORMATION.




1 L1 TREE PLANTING DETAIL
No Scale

## SODDING OF DISTURBED AREAS

AREAS AND LIMITS OF SODDING ARE INDICATED BASED ON ANTICIPATED DISTURBANCE BY GRADING OPERATIONS. CONTRACTOR TO PROVIDE ADDITIONAL SODDING IN ANY OTHER AREAS DISTURBED BY WORK UNDER THIS CONTRACT. EXCAVATE AND REMOVE ANY REMAINING TURF AND SOIL TO A 4-INCH MINIMUM DEPTH WITHIN NEW SOD AREAS. HAND EXCAVATION REQUIRED WITHIN DRIP LINES OF TREE AREAS TO AVOID DAMAGE TO EXISTING ROOTS.CONTRACTOR TO INSTALL MINIMUM OF 3" OF TOPSOIL TO ALL AREAS TO BE SODDED OR SEEDED. FINE GRADE THE TOPSOIL TO ENSURE POSITIVE DRAINAGE AND A SMOOTH SURFACE FOR SOD INSTALLATION.

## MAINTENANCE AND WARRANTY

CONTRACTOR TO PROVIDE FULL MAINTENANCE OF INSTALLED LANDSCAPE AND IRRIGATION UNTIL DATE OF FINAL ACCEPTANCE. ADDITIONALLY, CONTRACTOR TO PROVIDE ONE YEAR WARRANTY FOR ALL LANDSCAPE AND IRRIGATION WORK FROM THE DATE OF FINAL ACCEPTANCE.


## IRRIGATION SYSTEM

CONTRACTOR TO PROVIDE AUTOMATIC IRRIGATION SYSTEM FOR ALL NEW LANDSCAPE AND TURF AREAS SHOWN ON THE PLANS. SYSTEM WILL REQUIRE PROVIDING BACKFLOW PREVENTER, PERMITTING, POWER CONNECTION, CONTROLLER, AND ALL OTHER WORK REQUIRED FOR A COMPLETE AND FUNCTIONING SYSTEM THAT PROVIDES 100% COVERAGE. COORDINATE LOCATION OF CONTROLLER WITH OWNER, GENERAL CONTRACTOR, AND ELECTRICAL CONTRACTOR. COORDINATE LOCATION OF IRRIGATION SLEEVES WITH GENERAL CONTRACTOR PRIOR TO FULLY MOBILIZING TO SITE. CONTRACTOR TO REFER TO THE UTILITY PLAN SHEET FOR CURRENT FIRE FLOW INFORMATION.

# LEGEND:

# PLAN QUANTITIES:

| | QUANTITY: | COMMON NAME / BOTANICAL NAME: | SIZE: | REMARKS: |
|---|---|---|---|---|
| | 5 | October Glory Red Maple<br>Acer rubrum ' October Glory' | 2" caliper | Specimen with positive upright form and symmetrical. Well branched canopies. |
| | 46 | Compacta Holly<br>Ilex crentata 'Compacta' | 3 gallon | Full well branched shrub with uniform shape. |
| | 44 | Stella D'Oro Daylily<br>Hemerocallis x Stella D'oro | 1 gallon | Plant 18" o.c. |
| | CONTRACTOR TO MEASURE | Bermuda Tifway 419<br>Cynodon Dactylon var. Tifway 419 | SOD | Solid sod, all areas indicated with close knit joints |




NOTES:
1. PROVIDE WEED CONTROL AND/OR FERTILIZER AS SPECIFIED BELOW.
2. WEED CONTROL AND FERTILIZER MAY BE APPLIED AT A LATER DATE TO COMPLY WITH SEASONAL CONDITIONS AND THE GROWING PERIOD.
3. PROVIDE AGRIFORM TABLETS AS PER MANUFACTURERS RECOMMENDATIONS.
4. PROVIDE HOMOGENOUS BACKFILL PLANTING MIXTURE OF 3:1 RATIO TOPSOIL TO PEATMOSS AND/OR OTHER APPROVED SOIL AMENDMENTS.
5. PROVIDE FERTILOME ROOT STIMULATOR OR APPROVED EQUAL IN PITS.
6. APPLY BALAN PREEMERGENT WEED CONTROL OR APPROVED EQUAL TREATMENT ON ALL SHRUB AND GROUNDCOVER BEDS.

2 L1 SHRUB PLANTING DETAIL
No Scale

| BY | REVISION | DATE |
|---|---|---|
| GPW | REVISED PER CITY OF BRYANT | 3-31-23 |


GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116 3825 Mt Carmel Rd
Benton, AR 72018 Bryant, AR 72022
Ph (501) 408-4650 garnatengineering@gmail.com


**A NEW ELITE VOLLEYBALL ACADEMY GYM FOR JOHN ECKART VERNIA OFFICE PARK 1601 CHRISTY LANE ALEXANDER, ARKANSAS 72002**

LICENSED LANDSCAPE ARCHITECT CHAD M. OPPEIHUIZEN No.5064 ARKANSAS

3/13/23

CONTENTS:

LANDSCAPING NOTES & DETAILS

PROJECT NO: 22140

DATE: MARCH 13, 2023

SHEET NO: L1.1


Drawings and Specifications as instruments of service are and shall remain the property of GarNat Engineering, LLC whether the project for which they are made is executed or not. They are not to be used by the owner or others on extensions of this project or on any other project without written agreement with GarNat Engineering, LLC and specific written verification or adaptation by GarNat Engineering, LLC for the specific purpose intended will be at user's sole risk and without liability or legal exposure to GarNat Engineering, LLC. All titles and rights are reserved by GarNat Engineering, LLC.

OPAQUE WOOD FENCE (6' TALL)

INSTALL FENCE ON WEST SIDE OF PROPERTY LINE OR AS CLOSE AS POSSIBLE TO EXISTING TREES.

RETAIN EXISTING TREES (SEE PHOTO BELOW)

FND 1/2" RBR

FND 5/8" RBR

#2389
SSMH FL ELEV: 385.46
RIM ELEV=390.28

#6205
Ssmh 9.10 INV
RIM ELEV=397.59

#2388
SSMH FL ELEV: 390.36
RIM ELEV=394.62

8" SS

SOD

VOLLEYBALL NETTING SYSTEM

BUILDING FINISH FLOOR = 400
21,225 SQUARE FEET

(23) COMPACTA HOLLY

(23) COMPACTA HOLLY

HENRY AVENUE

SIDEWALK

SOD

SOD

SOD

SOD

ELECTRIC BOX

(5) OCTOBER GLORY RED MAPLE

(22) STELLA D'ORO DAYLILY - 50 SQ. FT.

(22) STELLA D'ORO DAYLILY - 50 SQ. FT.

STEEL EDGING (TYP.)

STEEL EDGING (TYP.)

BIKE/WALK PATH

#2367
sdmh rim 5.08 Inv
RIM ELEV=393.24

#2351
sdmh rim 5.88 Inv
RIM ELEV=388.79

#1571
7.02 Inv curb inlet rim
RIM ELEV=408.34


#1569
curb inlet rim 7.5 Inv
RIM ELEV=408.61

CHRISTY LANE

W

M

20' 10' 0 20'




| DATE | REVISION | BY |
|---|---|---|
| 3-31-23 | REVISED PER CITY OF BRYANT | GPW |


GNE Designing our client's success

GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com


# A NEW ELITE VOLLEYBALL ACADEMY GYM FOR JOHN ECKART VERNIA OFFICE PARK
## 1601 CHRISTY LANE
## ALEXANDER, ARKANSAS 72002

LICENSED LANDSCAPE ARCHITECT
CHAD M. OPPENHUIZEN
No. 5064
ARKANSAS

3/13/23

CONTENTS:

LANDSCAPE PLAN

PROJECT NO: 22140

DATE: MARCH 13, 2023

SHEET NO: L1.0

PARKING SPACES:
2 HANDICAP SPACES
90 CUSTOMER SPACES
92 PARKING SPACES TOTAL

#2389 SSMH FL ELEV: 385.46 RIM ELEV=390.28

FND 1/2" RBR

NEW FENCE

EXISTING TREES

FND 5/8" RBR

#6205 Ssmh 9.10 INV RIM ELEV=397.59

25' SETBACK

20' SEWER / DRAINAGE EASEMENT

STORM DRAIN BOX (TYP.) SEE SHEET C3.0

#2388 SSMH FL ELEV: 390.36 RIM ELEV=394.62

25' SETBACK - UTILITY - DRAINAGE EASEMENT

70' DETENTION AREA ESMT.

VOLLEYBALL NETTING SYSTEM

5' WIDE STAIR WITH RAILING (7 STEPS)

BUILDING FINISH FLOOR = 400 **
21,225 SQUARE FEET

ARDOT STANDARD TYPE A CURB

15' SETBACK / EASEMENT

6.5' WIDE WALK

SIGN TO DESIGNATE SPOT AS HANDICAP ACCESSIBLE (2 TOTAL)

HENRY AVENUE

6.5' WIDE WALK

24'

15' SETBACK / EASEMENT

SIDEWALK

CURB 6" TURN DOWN

CURB & ASPH. FLUSH

CURB STOP (TYP.) (4 TOTAL)

15' WATER LINE EASEMENT

CURB & ASPH. FLUSH

CURB 6" TURN DOWN

7' WIDE WALK

PARKING SPACE (TYP.)

9'

18'

24'

DETECTABLE WARNING DEVICE

6" INTEGRAL CURB

9' CURB TRANSITION

WHEELCHAIR RAMP (SEE ARDOT DWG WR-1)

EXISTING PATH

5' SIDEWALK

ELECTRIC BOX

#2351 ssmh rim 5.88 Inv RIM ELEV=388.79

#2352 ssmh rim 7.68 Inv RIM ELEV=390.53

8'BIKE/WALK PATH

15' SETBACK / EASEMENT

#1571 7.02 Inv curb inlet rim RIM ELEV=408.34

REMOVE 5' OF PATH TO INSTALL STORM DRAIN THEN REBUILD AND CONSTRUCT REST OF PATH TO INTERSECTION.

CHRISTY LANE

#1569 curb inlet rim 7.5 Inv RIM ELEV=406.61

INSTALL 48 LF OF MODIFIED CURB

15' WATER LINE EASEMENT

20' 10' 0 20'

LEGEND:

PROPOSED CONCRETE

PROPOSED ASPHALT

EXISTING CONCRETE

NOTES:

1. SITE PAVEMENT MARKINGS SHALL BE 4" WIDE WHITE PAINT (PER ARDOT STANDARD SPECIFICATION SECTION 718)

** BUILDING CONSTRUCTION / FACADE WILL COMPLY WITH CITY OF BRYANT COMMERCIAL BUILDING CODE REQUIREMENTS.

BUILDING WILL BE LESS THAN 40 FEET TALL.

BUILDING WILL HAVE KNOX BOX AND FIRE DEPARTMENT CONNECTION PER CITY OF BRYANT REQUIREMENTS.

| DATE | REVISION | BY |
|---|---|---|
| 3-31-23 | REVISED PER CITY OF BRYANT | GPW |


GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116 Benton, AR 72018
3825 Mt Carmel Rd Bryant, AR 72022
garnatengineering@gmail.com
Ph (501) 408-4650


# A NEW ELITE VOLLEYBALL ACADEMY GYM FOR JOHN ECKART VERNIA OFFICE PARK
1601 CHRISTY LANE
ALEXANDER, ARKANSAS 72002

STATE OF ARKANSAS
Vernon J. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON J. WILLIAMS

03-13-2023

CONTENTS:
SITE PLAN

PROJECT NO: 22140

DATE: MARCH 13, 2023

SHEET NO: C1.0

# New Facility For:
# Elite Voleyball
# NE Lot of Vernia
# Bryant, AR 72022

## STORM WATER MAINTENANCE PLAN

The NE Lot of Vernia owner will be responsible for the inspection and maintenance of the stormwater detention pond located on its.

Inspections are to be scheduled as directed in this document. All documentation on scheduled inspections, dates of inspections, and maintenance completed shall be retained by the NE Lot of Vernia owner for a period of three years.

**DETENTION PIPES**

Annual Maintenance (as applicable):

[ ] Check pipes for sediment in-fill, clean when necessary

[ ] Check outlets for clogging with trash or dead vegetation, clean when necessary


John Eckart
EVA Real Estate

3/17/2023
Date

# INSPECTION REPORT

## DATE: / /

## ELITE VOLLEYBALL ACADEMY




OUTLET

DETENTION PIPE

**COMMENT**

# SITE WITH AUTOMATIC COVERAGE (LESS THAN 5 ACRES) CONSTRUCTION SITE NOTICE

FOR THE
Arkansas Department of Environmental Quality (ADEQ)
Storm Water Program

## NPDES GENERAL PERMIT NO. ARR150000

The following information is posted in compliance with **Part I.B.8.A** of the ADEQ General Permit Number **ARR150000** for discharges of stormwater runoff from sites with automatic coverage. Additional information regarding the ADEQ stormwater program may be found on the internet at:

*www.adeq.state.ar.us/water/branch_npdes/stormwater*

| | |
|---|---|
| Permit Number | ARR150000 |
| Contact Name:<br>Phone Number: | John Eckart<br>(786) 256-0080 |
| Project Description (Name, Location, etc.):<br>Start Date:<br>End Date:<br>Total Acres: | Elite Volleyball Academy Gym Alexander, AR 72002<br><br><br>2.13 |
| Location of Stormwater Pollution Prevention Plan: | Mailbox on Site |

For Construction Sites Authorized under **Part I.B.6.A** (Automatic Coverage) the following certification must be completed:

I _____ (Typed or Printed Name of Person Completing this Certification) certify under penalty of law that I have read and understand the eligibility requirements for claiming an authorization under Part I.B.2. of the ADEQ General Permit Number ARR150000. A stormwater pollution prevention plan has been developed and implemented according to the requirements contained in Part II.A.2.B & D of the permit. I am aware there are significant penalties for providing false information or for conducted unauthorized discharges, including the possibility of fine and imprisonment for knowing violations.

_____ _____

Signature and Title Date

# Stormwater Pollution Prevention Plan (SWPPP) for Construction Activity for Small Construction Sites

National Pollutant Discharge Elimination System (NPDES)
General Permit # ARR150000

Prepared for:

Elite Volleyball Academy Gym
For John Eckert

Date:

03/17/2023

Prepared by:

GarNat Engineering, LLC

Revised date: 10/20/2016

**Table of Contents**
**Elite Volleyball Academy Gym**
**Alexander, Arkansas 72002**

SWPPP for Construction Activity for Small Construction Sites

Appendix A- ARR150000 Inspection Form

SWPPP Figures

Elite Volleyball Academy Gym Erosion Control Plan

AHTD Standard Drawings:

TEC-1 – Temporary Erosion Control Devices

TEC-4 – Temporary Erosion Control Devices

NPDES ARR150000

Project Name and Location: Elite Volleyball Academy Gym, 1601 Christy Lane, Alexander, Arkansas 72002

Property Parcel Number (*Optional*): _____

Operator Name and Address: _____

A. Site Description

a. Project description, intended use after NOI is filed: Development of a Volleyball Gym

b. Sequence of major activities which disturb soils: Earthwork, Drainage Structures, Utilities

c. Total Area: 2.13 Ac Disturbed Area: 2.13 Ac

B. Responsible Parties

*Be sure to assign all SWPPP related activities to an individual or position; even if the specific individual is not yet known (i.e. contractor has not been chosen).*

| Individual/Company | Phone Number | Service Provided for SWPPP (i.e., Inspector, SWPPP revisions, Stabilization Activities, BMP Maintenance, etc.) |
|---|---|---|
| John Eckart | 786-256-0080 | |
| | | |
| | | |
| | | |
| | | |

C. Receiving Waters

a. The following waterbody (or waterbodies) receives stormwater from this construction site: Unnamed tributaries of Owen Creek

b. Is the project located within the jurisdiction of an MS4? ☒ Yes ☐ No

i. If yes, Name of MS4: Bryant

c. Ultimate Receiving Water:

☐ Red River
☐ Ouachita River
☒ Arkansas River
☐ White River
☐ St. Francis River
☐ Mississippi River

D. Site Map Requirements (Attach Site Map):

a. Pre-construction topographic view;

b. Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
c. Delineate on the site map areas of soil disturbance and areas that will not be disturbed under the coverage of this permit;
d. Location of major structural and nonstructural controls identified in the plan;
e. Location of main construction entrance and exit;
f. Location where stabilization practices are expected to occur;
g. Locations of off-site materials, waste, borrow area, or equipment storage area;
h. Location of areas used for concrete wash-out;
i. Location of all surface water bodies (including wetlands) with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
j. Locations where stormwater is discharged to a surface water and/or municipal separate storm sewer system if applicable,
k. Locations where stormwater is discharged off-site (should be continuously updated);
l. Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
m. A legend that identifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
n. Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

E. Stormwater Controls

a. Initial Site Stabilization, Erosion and Sediment Controls, and Best Management Practices:

i. Initial Site Stabilization: Prior to starting clearing activities, the BMP's shown on the Erosion Control Plan will be installed.

ii. Erosion and Sediment Controls: Erosion and sediment controls are shown on the erosion control plan. They will be constructed per AHTD standard details

iii. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the operator will replace or modify the control for site situations: ☒ Yes ☐ No

If No, explain: _____

_____

iv. Off-site accumulations of sediment will be removed at a frequency sufficient to minimize off-site impacts: ☒ Yes ☐ No

If No, explain: _____

_____

v. Sediment will be removed from sediment traps or sedimentation ponds when design capacity has been reduced by 50%: ☒ Yes ☐ No

If No, explain: _____

_____

vi. Litter, construction debris, and construction chemicals exposed to stormwater shall be prevented from becoming a pollutant source for stormwater discharges: ☒ Yes ☐ No

If No, explain: _____

_____

vii. Off-site material storage areas used solely by the permitted project are being covered by this SWPPP: ☐ Yes ☒ No (there are no such sites)

If Yes, explain additional BMPs implemented at off-site material storage area: _____

_____

b. Stabilization Practices

i. Description and Schedule: As soon as practical, the contractor will spread topsoil and seed the disturbed area with a perennial vegetation. Vegetation will be reseeded as required to establish the 80% coverage of perennial vegetation.

ii. Are buffer areas required? ☐ Yes ☒ No

If Yes, are buffer areas being used? ☐ Yes ☐ No

If No, explain why not: _____

_____

If Yes, describe natural buffer areas: _____

_____

iii. A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included with the plan. ☒ Yes ☐ No

If No, explain: _____

_____

iv. Deadlines for stabilization:

1. Stabilization procedures will be initiated 14 days after construction activity temporarily ceases on a portion of the site.
2. Stabilization procedures will be initiated immediately in portions of the site where construction activities have permanently ceased.

c. Structural Practices

i. Describe any structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site: BMPs shown on the erosion control plan will be used to limit sediment from leaving the site

ii. Describe Velocity Dissipation Devices: _____

iii. Sediment Basins:

Are 10 or more acres draining to a common point? ☐ Yes ☒ No

Is a sediment basin included in the project? ☐ Yes ☒ No

If Yes, what is the designed capacity for the storage?

☐ 3600 cubic feet per acre = : _____

or

☐ 10 year, 24 hour storm = : _____

☐ Other criteria were used to design basin: _____

If No, explain why no sedimentation basin was included and describe required natural buffer areas and other controls implemented instead: Not appropriate for this project.

F. Other Controls

a. Solid materials, including building materials, shall be prevented from being discharged to Waters of the State: ☒ Yes ☐ No

b. Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of:

☒ A stabilized construction entrance and exit

☐ Vehicle tire washing

☒ Other controls, describe: * see below

c. Temporary Sanitary Facilities: A portable toilet will be provided. The location is shown on the Erosion Control Plan.

* The road adjacent to the property will be swept to remove offside vehicle tracks. Disturbed areas will be watered during construction.

d. Concrete Waste Area Provided:
☒ Yes
☐ No. Concrete is used on the site, but no concrete washout is provided.
Explain why: _____
_____
☐ N/A, no concrete will be used with this project

e. Fuel Storage Areas, Hazardous Waste Storage, and Truck Wash Areas: _____
_____

G. Non-Stormwater Discharges

a. The following allowable non-stormwater discharges comingled with stormwater are present or anticipated at the site:
☒ Fire-fighting activities;
☒ Fire hydrant flushings;
☒ Water used to wash vehicles (where detergents or other chemicals are not used) or control dust in accordance with Part II.A.4.H.2;
☒ Potable water sources including uncontaminated waterline flushings;
☒ Landscape Irrigation;
☒ Routine external building wash down which does not use detergents or other chemicals;
☒ Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents or other chemicals are not used;
☒ Uncontaminated air conditioning, compressor condensate (See Part I.B.12.C of the permit);,
☒ Uncontaminated springs, excavation dewatering and groundwater (See Part I.B.13.C of the permit);
☒ Foundation or footing drains where flows are not contaminated with process materials such as solvents (See Part I.B.13.C of the permit);

b. Describe any controls associated with non-stormwater discharges present at the site: BMP's shown on the Erosion Control plan will also be utilized to prevent sedimentation from leaving site during construction.

H. Applicable State or Local Programs: The SWPPP will be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site. ☒ Yes ☐ No

I. Inspections

a. Inspection frequency:
☒ Every 7 calendar days
or
☐ At least once every 14 calendar days and within 24 hours of the end of a storm even 0.25 inches or greater (a rain gauge must be maintained on-site)

b. Inspections:

Completed inspection forms will be kept with the SWPPP.

☒ ADEQ's inspection form will be used (See Appendix B)

or

☐ A form other than ADEQ's inspection form will be used and is attached (See inspection form requirements Part II.A.4.L.2)

c. Inspection records will be retained as part of the SWPPP for at least 3 years from the date of termination.

d. It is understood that the following sections describe waivers of site inspection requirements. All applicable documentation requirements will be followed in accordance with the referenced sections.

i. Winter Conditions (Part II.A.4.L.4)

ii. Adverse Weather Conditions (Part II.A.4.L.5)

J. Maintenance:

The following procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition will be followed: See below*

Any necessary repairs will be completed, when practicable, before the next storm event, but not to exceed a period of 3 business days of discovery, or as otherwise directed by state or local officials.

K. Employee Training:

The following is a description of the training plan for personnel (including contractors and subcontractors) on this project: Operator will submit proof of training to engineer. Engineer will provide additional training as required to ensure that SWPPP is properly implemented.

**Note, Formal training classes given by Universities or other third-party organizations are not required, but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.

* Built up sediment will be removed from silt fencing when it has reached 1/3 of the height of the fence. Silt fences will be inspected for the depth of sediment, tears, fabric attachment to the fence posts, and to see that the fence posts are firmly in the ground. Temporary and permanent seeding will be inspected for bare spots, washouts, and healthy growth. Entrance will be inspected for sediment tracked on roads.

Certification

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible or Cognizant Official: _____

Title: _____ Date: _____

## ARR150000 Inspection Form

Appendix A

Inspector Name: _____ Date of Inspection: _____

Inspector Title: _____

Date of Rainfall: _____ Duration of Rainfall: _____

Days Since Last Rain Event: _____ days Rainfall Since Last Rain Event: _____ inches

Description of any Discharges During Inspection: _____

Location of Discharges of Sediment/Other Pollutant (specify pollutant & location): _____

_____

Locations in Need of Additional BMPs: _____

Information on Location of Construction Activities

| Location | Activity Begin Date | Activity Occuring Now (y/n)? | Activity Ceased Date | Stabilization Initiated Date | Stabilization Complete Date |
|---|---|---|---|---|---|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Information on BMPs in Need of Maintenance

| Location | In Working Order? | Maintenance Scheduled Date | Maintenance Completed Date | Maintenance to be Performed By |
|---|---|---|---|---|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Changes required to the SWPPP: _____ Reasons for changes: _____

_____ _____


_____ _____


SWPPP changes completed (date): _____

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."


Signature of Responsible or Cognizant Official: _____ Date: _____

Title: _____




SECTION A




## STABILIZED CONSTRUCTION ENTRANCE

NOT TO SCALE

BMP NOTES:

1. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.

2. DUST ON THE SITE SHALL BE CONTROLLED. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS IS PROHIBITED.

3. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIAL SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORMWATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE.

4. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS STOPPED FOR AT LEAST 14 DAYS, SHALL BE TEMPORARILY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS FROM THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS.

5. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY SEEDED. THESE AREAS SHALL BE SEEDED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE GRADING PLAN AND/OR LANDSCAPE PLAN.

6. IF THE ACTION OF VEHICLES TRAVELING OVER THE SITE IS NOT SUFFICIENT TO REMOVE THE MAJORITY OF DIRT OR MUD, THEN THE TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFF OF THE SITE.

7. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.

8. CONTRACTORS OR SUBCONTRACTORS WILL BE RESPONSIBLE FOR REMOVING SEDIMENT IN THE DETENTION POND AND ANY SEDIMENT THAT MAY HAVE COLLECTED IN THE STORM SEWER DRAINAGE SYSTEMS IN CONJUNCTION WITH THE STABILIZATION OF THE SITE.

9. ON-SITE & OFF SITE SOIL STOCKPILE AND BORROW AREAS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION THROUGH IMPLEMENTATION OF BEST MANAGEMENT PRACTICES. STOCKPILE AND BORROW AREA LOCATIONS SHALL BE NOTED ON THE SITE MAP AND PERMITTED IN ACCORDANCE WITH GENERAL PERMIT REQUIREMENTS.

10. ALL CONSTRUCTION SHALL BE STABILIZED AT THE END OF EACH WORKING DAY, THIS INCLUDES BACKFILLING OF TRENCHES FOR UTILITY CONSTRUCTION AND PLACEMENT OF GRAVEL OR BITUMINOUS PAVING FOR ROAD CONSTRUCTION.

TOTAL SITE: 2.13 ACRES (INCLUDES R-0-W)

TOTAL DISTURBED AREA: 2.13 ACRES (INCLUDES R-O-W)

LEGEND:

500 EXISTING CONTOURS

DIRECTION OF OVERLAND FLOW

SF SILT FENCING

N

30' 15' 0 30'

| BY | REVISION | DATE |
|---|---|---|
| | | |

GNE Designing our client's success

GarNat Engineering, LLC
P.O. Box 116
Benton, AR 72018
3825 Mt Carmel Rd
Bryant, AR 72022
Ph (501) 408-4650
garnatengineering@gmail.com

**A NEW ELITE VOLLEYBALL ACADEMY GYM FOR JOHN ECKART VERNIA OFFICE PARK 1601 CHRISTY LANE ALEXANDER, ARKANSAS 72002**

STATE OF ARKANSAS
Vernon J. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON J. WILLIAMS

03-10-2023

CONTENTS:

EROSION CONTROL PLAN

PROJECT NO: 22140


DATE: DATE

SHEET NO: C4.0


J:\Projects\2022 Projects\22140 Vernia Office Park\Drawings\Design\22140-John Eckart-Sports-ENV-Gym Plan Portfolio.dwg

GENERAL NOTES


INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.




## WATTLE DITCH CHECK (E-1)




## DROP INLET SILT FENCE (E-7)





## SILT FENCE ON R/W FENCE (E-4)

GENERAL NOTES

GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST, OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.


GENERAL NOTES

1. STRAW BALES SHALL BE INSTALLED SO THAT THE BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES. THE BALES SHALL BE A MINIMUM OF 30 INCHES IN LENGTH.
2. NO GAPS SHALL BE LEFT BETWEEN BALES.
3. BALED STRAW FILTER BARRIERS COMPLETED AND ACCEPTED WILL BE MEASURED BY THE BALE IN PLACE AS AUTHORIZED BY THE ENGINEER AND WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER BALE FOR BALED STRAW DITCH CHECKS.





## BALED STRAW FILTER BARRIER (E-2)


NUMBER OF SAND BAGS AND ARRANGEMENT VARIABLE WITH ON-SITE CONDITIONS.





PLACE SAND BAGS AT BASE OF DITCH CHECK IN AREA OF OVERFLOW





## SAND BAG DITCH CHECK (E-5)




## ROCK DITCH CHECK (E-6)




## SILT FENCE (E-11)

GENERAL NOTES

GEOTEXTILE FABRIC SHALL BE SPLICED TOGETHER WITH A SEWN SEAM ONLY AT A SUPPORT POST OR TWO SECTIONS OF FENCE MAY BE OVERLAPPED INSTEAD. PAYMENT OF ADDITIONAL MATERIAL FOR OVERLAP WILL NOT BE MADE.


PER CITY OF BRYANT REQUIREMENTS, REQUIRES WIRED BACK FENCE.

| DATE | REVISION | FILMED |
|---|---|---|
| 12-15-11 | DELETED BALED STRAW DITCH CHECK & ADDED WATTLE DITCH CHECK | |
| 11-18-98 | ADDED NOTES | |
| 7-02-98 | ADDED BALED STRAW FILTER BARRIER (E-2) | |
| 7-20-95 | REVISED SILT FENCE E-4 AND E-11 | 7-20-95 |
| 7-15-94 | REV. E-4 & E-11 MIN. 13" BURIED END OF FABRIC | |
| 6-2-94 | REVISED E-1,4,7 & 11; DELETED E-2 & 3 | 6-2-94 |
| 4-1-93 | REDRAWN | |
| 10-1-92 | REDRAWN | |
| 8-2-76 | ISSUED R.D.M. | 298-7-28-76 |


ARKANSAS STATE HIGHWAY COMMISSION

# TEMPORARY EROSION CONTROL DEVICES

STANDARD DRAWING TEC-1





TRIANGULAR SILT DIKE INSTALLATION
FOR
DIVERSION DITCH AND/OR DITCH LINER





TRIANGULAR SILT DIKE INSTALLATION
FOR
ROADWAY DITCH OR DRAINAGE DITCH

○ POINT "1" MUST BE HIGHER THAN POINT "2" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.


⊖ STAPLES SHALL BE PLACED WHERE THE UNITS OVERLAP AND IN THE CENTER OF THE UNIT AS SHOWN ON THE DIAGRAM.




TRIANGULAR SILT DIKE INSTALLATION
FOR
CONTINUOUS BARRIER




TRIANGULAR SILT DIKE INSTALLATION
FOR
DROP INLETS




TRIANGULAR SILT DIKE INSTALLATION
FOR
TEMPORARY DITCH LINER

## GENERAL NOTES

1. THIS WORK SHALL CONSIST OF FURNISHING, INSTALLING, AND MAINTAINING THE TRIANGULAR SILT DIKE. THE DIKES SHALL BE USED AS A CONTINUOUS LINE BARRIER AT THE TOE OF SLOPE OR ACROSS THE ROADWAY DITCH TO CONTAIN SEDIMENT AND MINIMIZE EROSION, OR AS DIRECTED BY THE ENGINEER. THESE DIKES SHALL BE INSTALLED AND LOCATED AS SOON AS CONSTRUCTION WILL ALLOW OR AS DIRECTED BY THE ENGINEER.

2. TRIANGULAR SILT DIKE SHALL BE TRIANGULAR SHAPED HAVING A HEIGHT OF AT LEAST 8" TO 10" IN THE CENTER WITH EQUAL SIDES AND A 16" TO 20" BASE. THE TRIANGULAR SHAPED INNER MATERIAL SHALL BE URETHANE FOAM. THE OUTER COVER SHALL BE A WOVEN GEOTEXTILE FABRIC PLACED AROUND THE INNER MATERIAL & ALLOWED TO EXTEND BEYOND BOTH SIDES OF THE TRIANGLE 24" TO 36". THIS FABRIC SHOULD BE MILDEW RESISTANT, ROT-PROOF AND RESISTANT TO HEAT AND ULTRAVIOLET RADIATION MEETING REQUIREMENTS FOR SEDIMENT CONTROL IN AASHTO M288. THE DIKES SHALL BE ATTACHED TO THE GROUND WITH WIRE STAPLES. THE STAPLES SHALL BE NO. 11 GAUGE WIRE AND BE AT LEAST 6" TO 8" LONG. STAPLES SHALL BE PLACED AS SHOWN ON THESE DETAILS.

   THE CONTRACTOR SHALL INSPECT ALL DIKES AFTER EACH RAINFALL EVENT OF AT LEAST 0.5" OR GREATER. ANY DEFICIENCIES OR DAMAGE SHALL BE REPAIRED BY THE CONTRACTOR. ACCUMULATED SILT OR DEBRIS SHALL BE REMOVED AND RELOCATED AS DIRECTED BY THE ENGINEER. IF THE DIKES ARE DAMAGED OR INADVERTENTLY MOVED DURING THE SILT REMOVAL PROCESS, THE CONTRACTOR SHALL IMMEDIATELY REPLACE AFTER DAMAGE OCCURS.

3. ACCEPTED TRIANGULAR SILT DIKE, MEASURED AS PROVIDED ABOVE, WILL BE PAID FOR AT THE CONTRACT UNIT PRICE BID FOR TRIANGULAR SILT DIKE. PRICE BID WILL INCLUDE THE COST OF FURNISHING THE DIKES, INSTALLING, MAINTAINING AND REMOVAL WHEN DIRECTED BY THE ENGINEER.

SYMBOLOGY
SYMBOL TO BE USED TO DENOTE DEVICE ON PLANS

**NOTE:** SILT DIKE SHOULD ONLY BE USED FOR DROP INLETS IN SUMP LOCATIONS.

| DATE | REVISION | FILMED |
|---|---|---|
| 7-26-12 | REVISED GENERAL NOTE 2. | |
| 12-15-11 | ISSUED | |

ARKANSAS STATE HIGHWAY COMMISSION

# TEMPORARY EROSION CONTROL DEVICES

STANDARD DRAWING TEC-4

# AUTHORIZATION TO DISCHARGE STORMWATER UNDER THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM AND THE ARKANSAS WATER AND AIR POLLUTION CONTROL ACT

In accordance with the provisions of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.), and the Clean Water Act (33 U.S.C. 1251 et seq.), an

**Operator of Facilities with Stormwater Discharges Associated with Construction Activity**

is authorized to discharge to all receiving waters except as stated in Part I.B.11 (Exclusions).

For large construction sites that are eligible for coverage under this General Permit (GP), the Arkansas Department of Energy and Environment - Division of Environmental Quality (DEQ), Office of Water Quality will provide a Notice of Coverage (NOC) with tracking permit number which starts with ARR15 and a copy of the permit to the facility. The cover letter includes the DEQ's determination that a facility is covered under the GP and may specify alternate requirements outlined in the permit.

Small construction sites that are eligible for coverage under this GP will be considered to have automatic coverage under this GP and must follow the permit requirements outlined in Condition 6 of Part I.

Effective Date: November 1, 2021

Expiration Date: October 31, 2026

Digitally signed by Alan J. York
DN: cn=Alan J. York, o, ou, email=alan.york@adeq.state.ar.us, c=US
Date: 2021.05.04 09:13:53 -05'00'

Alan J. York
Associate Director, Office of Water Quality
Division of Environmental Quality

05/04/2021
Issue Date

# PART I
# PERMIT REQUIREMENTS

Information in **Part I** is organized as follows:

**Section A:** Definitions with Included Commentary
**Section B:** Coverage Under this Permit:

1. Permitted Area
2. Eligibility
3. Responsibilities of the Operator
4. Where to Submit
5. Requirements for Qualifying Local Program (QLP)
6. Requirements for Coverage
7. Notice of Intent (NOI) Requirements
8. Posting Notice of Coverage (NOC)
9. Applicable Federal, State or Local Requirements
10. Allowable Non-Stormwater Discharges
11. Limitations on Coverage (Exclusions)
12. Short Term Activity Authorization (STAA)
13. Effluent Limitation Guidelines (ELG)
14. Natural Buffer Zones
15. Waivers from Permit Coverage
16. Notice of Termination (NOT)
17. Responsibilities of the Operator of a Larger Common Plan of Development for a Subdivision
18. Change in Operator
19. Late Notifications
20. Failure to Notify
21. Maintenance
22. Releases in Excess of Reportable Quantities
23. Attainment of Water Quality Standards
24. Requiring an Individual Permit

## SECTION A: DEFINITIONS WITH INCLUDED COMMENTARY

**1.** **"Arkansas Pollution Control and Ecology Commission"** shall be referred to as APC&EC throughout this permit.

**2.** **"Automatic Coverage"** is a term used to define the method of coverage for a small construction site.

**3.** **"Best Management Practices (BMPs)"** schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to waters of the State. BMPs also include treatment requirements, operating procedures, and practices to control construction site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage. According to the EPA BMP manual, the use of hay-bales in concentrated flow areas is not recommended as a BMP.

**4.** **"Cognizant Official" is** a duly authorized representative, as defined in Part II.B.9.B.

**5.** **"Commencement of Construction"** is the initial disturbance of soils (or breaking ground) associated with clearing, grading, or excavating activities or other construction-related activities (e.g., stockpiling of fill material; placement of raw materials at the site).

**6.** **"Contaminated"** is a substance the entry of which into the MS4, waters of the State, or Waters of the United States may cause or contribute to a violation of Arkansas water quality standards.

**7.** **"Control Measure"** as used in this permit, refers to any Best Management Practice or other method used to prevent or reduce the discharge of pollutants to waters of the State.

**8.** **"Construction Activity"** earth-disturbing activities, such as the clearing, grading, and excavation of land, and other construction–related activities (e.g., stockpiling of fill material; placement of raw materials at the site) that could lead to the generation of pollutants.

**9.** **"Construction Site"** is an area upon which one or more land disturbing construction activities occur that in total will disturb one acre or more of land, including areas that are part of a larger common plan of development or sale that may be less than one acre where multiple separate and distinct land disturbing construction activities may be taking place at different times on different schedules but under one plan such that the total disturbed area is one acre or more.

**10.** **"Construction Support Activity"** a construction-related activity that specifically supports the construction activity and involves earth disturbance of pollutant-generating activities of its own, and can include, but not limited to, activities associated with concrete or asphalt batch plants, equipment staging yards, materials storage areas, excavated material disposal areas, and burrow areas.

**11.** **"CWA"** is the Clean Water Act or the Federal Water Pollution Control Act.

**12.** **"Department"** is referencing the Department of Energy and Environment.

**13.** **"DEQ"** or **"Division"** is referencing the Division of Environmental Quality. The Division is the governing authority for the National Pollutant Discharge Elimination System program in the state of Arkansas.

**14.** **"Detention Basin"** is an area where excess stormwater is stored or held temporarily and then slowly drains when water levels in the receiving channel recede. In essence, the water in a detention basin is temporarily detained until additional room becomes available in the receiving channel.

**15.** **"Director"** is the Director of the Division of Environmental Quality, or a designated representative.

**16.** **"Discharge"** is when used without qualification means the "discharge of a pollutant".

**17.** **"Disturbed area"** is the total area of the site where any construction activity is expected to disturb the ground surface. This includes any activity that could increase the rate of erosion, including, but not limited to, clearing, grubbing, grading, excavation, demolition activities, haul roads, and areas used for staging. Also included are stockpiles of topsoil, fill material and any other stockpiles with a potential to create additional runoff.

**18.** **"Drainageway"** is an open linear depression, whether constructed or natural, that functions for the collection and drainage of surface water.

**19.** **"Duly Authorized Representative"** is a representative of the Responsible Official meeting the requirements specified in Part II.B.9.B.

**20.** **"Eligible"** refers to being qualified for authorization to discharge stormwater under this general permit.

**21.** **"Erosion"** is the process by which the land's surface is worn away by the action of wind, water, ice or gravity.

**22.** **"ERW"** Extraordinary Resource Water, in accordance with Rule 2.

**23.** **"ESW"** Ecologically Sensitive Waterbodies, in accordance with Rule 2.

**24.** **"Facility" or "Activity"** is any NPDES "point source" or any other facility or activity (including land or appurtenances thereto) that is subject to regulation under the NPDES program.

**25.** **"Final Stabilization"**:

A. All soil disturbing activities at the site have been completed and either of the two following criteria are met:

   1) A uniform (e.g., evenly distributed, without large bare areas) perennial vegetative cover with a density of 80% or more of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or
   2) Equivalent permanent stabilization measures (such as the use of riprap, gabions, or geotextiles) have been employed.

B. When background native vegetation will cover less than 100% of the ground (e.g., arid areas, beaches), the 80% coverage criteria is adjusted as follows: if the native vegetation covers 50% of the ground, 80% of 50% (0.80 x 0.50 = 0.40) would require 40% total cover for final stabilization. On a beach with no natural vegetation, no stabilization is required.

C. For individual lots in residential construction, final stabilization means that either:

   1) The homebuilder has completed final stabilization as specified above, or

2) The homebuilder has established temporary stabilization including perimeter controls for an individual lot prior to occupation of the home by the homeowner and informing the homeowner of the need for, and benefits of, final stabilization.

D. For construction projects on land used for agricultural purposes (e.g., pipelines across crop or range land, staging areas for highway construction, etc.), final stabilization may be accomplished by returning the disturbed land to its pre-construction agricultural use. Areas disturbed that were not previously used for agricultural activities, such as buffer strips immediately adjacent to "waters of the State", and areas which are not being returned to their pre-construction agricultural use shall meet the final stabilization criteria in A, B**,** or C above.

**26.** **"Grading Activities"** as used in this permit are those actions that disturb the surface layer of the ground to change the contouring, surface drainage pattern, or any other slope characteristics of the land without significantly adding or removing on-site rock, soil, and other materials. This can include demolition, excavation, and filling.

**27.** **"Impaired Water"** is a waterbody listed in the current, approved Arkansas 303(d) list.

**28.** **"Infrastructure"** refers to streets, drainage, curbs, utilities, etc.

**29.** **"Landscaping"** is improving the natural beauty of a piece of land (i.e. entrance of subdivision) through plantings or altering the contours of the ground.

**30.** **"Large Construction Site"** is a construction site in which construction activity including clearing, grading and excavation. Construction activity also includes the disturbance of less than five acres of total land area that is a part of a larger common plan of development or sale if the larger common plan will ultimately disturb five acres or greater. (Please see Part I.B.15 for partial waivers.)

**31.** **"Larger Common Plan of Development or Sale"** is a contiguous (sharing a boundary or edge; adjacent; touching) area where multiple and distinct construction activities may be taking place at different times on different schedules under one plan. Such a plan might consist of many small projects (e.g. a common plan of development for a residential subdivision might lay out the streets, house lots, and areas for parks, schools and commercial development that the developer plans to build or sell to others for development). All these areas would remain part of the common plan of development or sale. The following items can be used as guidance for deciding what might or might not be considered a "Common Plan of Development or Sale." The ''plan'' in a common plan of development or sale is broadly defined as any announcement or piece of documentation (including a sign, public notice or hearing, sales pitch, advertisement, drawing, permit application, zoning request, computer design, etc.) or physical demarcation (including boundary signs, lot stakes, surveyor markings, etc.) indicating construction activities may occur on a specific plot. The applicant shall still meet the definition of operator in order to be required to get permit coverage, regardless of the acreage that is personally disturbed.

If a smaller project (i.e., less than 1 acre) is part of a larger common plan of development or sale (e.g., you are building a residential home on a ½ acre lot in a 40 acre subdivision or are putting in a fast food restaurant on a ¾ acre pad that is part of a 20 acre retail center), permit coverage is required.

**32.** **"Losing Stream Segment"** a stream segment which, beginning at the point of existing or proposed discharge and extending two (2) miles downstream, contribute thirty percent (30%) or more of its flow at a 7Q10 flow or one (1) cfs, whichever is greater, through natural processes such as permeable subsoil or cavernous bedrock into an aquifer.

**33.** **"Natural Buffer"** for purposes of this permit, an area of undisturbed natural cover surrounding waters of the State. Natural cover includes vegetation, exposed rock, or barren ground that exists prior to commencement of construction activities

at the site.

**34.** **"NOC"** Notice of Coverage.

**35.** **"NOI"** Notice of Intent to be covered by this permit.

**36.** **"NOT"** Notice of Termination.

**37.** **"NSW"** Natural and Scenic Waterways, in accordance with Rule 2.

**38.** **"Operator"/"Permittee"** for the purpose of this permit and in the context of stormwater associated with construction activity, means any person(s),an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has financial and operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; additionally, the Division may require any person(s), an individual, association, partnership, corporation, municipality, state or federal agency, associated with a construction project that has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions can be named as a co-permittee.

In addition, for purposes of this permit and determining who is an operator, ''owner'' refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline or a landowner who allows a mining company to remove dirt, shale, clay, sand, gravel, etc. from a portion of his property). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g., having a house built by a residential homebuilder).

**39.** **"Outfall"** a point source where stormwater leaves the construction site.

**40.** **"Owner"** refers to the owner or operator of any "facility or activity" subject to regulation under the NPDES program. In addition, for purposes of this permit and determining who is an operator, ''owner'' refers to the party that owns the structure being built. Ownership of the land where construction is occurring does not necessarily imply the property owner is an operator (e.g., a landowner whose property is being disturbed by construction of a gas pipeline). Likewise, if the erection of a structure has been contracted for, but possession of the title or lease to the land or structure is not to occur until after construction, the would-be owner may not be considered an operator (e.g. having a house built by a residential homebuilder).

**41.** **"Physically Interconnected"** means that one municipal separate storm sewer system is connected to a second municipal separate storm sewer system in such a way that it allows for direct discharges into the second system.

**42.** **"Point Source"** is any discernible, confined, and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged. This term does not include return flows from irrigated agriculture or agricultural stormwater runoff.

**43.** **"Qualified Local Program"** is a municipal program for stormwater discharges associated with construction sites that has been formally approved by DEQ.

**44.** **"Qualified personnel"** a person knowledgeable in the principles and practice of erosion and sediment controls who possesses the skills to assess conditions at the construction site that could impact stormwater quality and to assess the effectiveness of any sediment and erosion control measures selected to control the quality of stormwater discharges from the

construction activity.

**45.** **"Regulated Small Municipal Separate Storm Sewer System"** are all municipal separate storm sewer systems that are either:

A. Located within the boundaries of an "urbanized area" with a population of 50,000 or more as determined by the latest Decennial Census by the Bureau of Census; or
B. Owned or operated by a municipality other than those described in paragraph A and that serve a jurisdiction with a population of at least 10,000 and a population density of at least 1,000 people per square mile; or
C. Owned or operated by a municipality other than those described in paragraphs A and B and that contributes substantially to the pollutant loadings of a "physically interconnected" municipal separate storm sewer system.

**46.** **"Responsible Official"** is the authorized representative, as defined in Part II.B.9.A.

**47.** **"Retention Basin"** a basin that is designed to hold the stormwater from a rain event and allow the water to infiltrate through the bottom of the basin. A retention basin also stores stormwater, but the storage of the stormwater would be on a more permanent basis. In fact, water often remains in a retention basin indefinitely, with the exception of the volume lost to evaporation and the volume absorbed into the soils. This differs greatly from a detention basin, which typically drains after the peak of the storm flow has passed, sometimes while it is still raining.

**48.** **"Runoff Coefficient"** is the fraction of total rainfall that will appear at the conveyance as runoff.

**49.** **"Sediment"** is material that settles to the bottom of a liquid.

**50.** **"Sediment Basin"** is a basin that is designed to maintain a 10 year-24 hour storm event for a minimum of 24-hours in order to allow sediment to settle out of the water.

**51.** **"Small Construction Site"** is a construction site in which construction activities including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre and less than five acres. Small construction activity also includes the disturbance of less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one and less than five acres. Small construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of the facility.

**52.** **"Stormwater"** is stormwater runoff from rainfall, snow melt runoff, and surface runoff and drainage.

**53.** **"Stormwater Discharge Associated with Construction Activity"** refers to the discharge of runoff from any conveyance which is used for collecting and conveying stormwater and which is directly related to construction activity.

**54.** **"Stormwater Pollution Prevention Plan (SWPPP or SWP3)"** is a plan that includes site map(s), an identification of construction/contractor, activities that could cause pollutants in the stormwater, and a description of measures or practices to control these pollutants.

**55.** **"Temporary Sediment Controls"** are controls that are installed to control sediment runoff from the site during construction activity. These could be silt fencing, rock check dams, etc.

**56.** **"Total Maximum Daily Load" or "TMDL"** is the sum of the individual wasteload allocations (WLAs) for point sources and load allocations (LAs) for non-point sources and natural background. If the receiving water has only one point

source discharger, the TMDL is the sum of that point source WLA plus the LAs for any non-point sources of pollution and natural background sources, tributaries, or adjacent segments. TMDLs can be expressed in terms of mass per time, toxicity, or other appropriate measure.

**57. "Uncontaminated"** means that the water will not exceed the water quality standards as set forth in APC&EC Rule 2; also not containing a harmful quantity of any substance.

**58. "Urbanized Area"** means the areas of urban population density delineated by the Bureau of the Census for statistical purposes and generally consisting of the land area comprising one or more central place(s) and the adjacent densely settled surrounding area that together have a residential population of at least 50,000 and an overall population density of at least 1,000 people per square mile as determined by the latest Decennial Census by the Bureau of Census.

**59. "Waters of the State"** waters of the State means all streams, lakes, marshes, ponds, watercourses, waterways, wells, springs, irrigation systems, drainage systems, and all other bodies or accumulations of water, surface and underground, natural or artificial, public or private, which are contained within, flow through, or border upon this state or any portion of the state.

## SECTION B: COVERAGE UNDER THIS PERMIT

### Introduction

This Construction General Permit (CGP) authorizes stormwater discharges from large and small construction activities that result in a total land disturbance of equal to or greater than one acre or less than one acre of total land area that is part of a larger common plan of development or sale if the larger common plan will ultimately disturb equal to or greater than one acre. This permit also authorizes stormwater discharges from any other construction activity designated by DEQ where DEQ makes that designation based on the potential for contribution to an excursion of a water quality standard or for significant contribution of pollutants to waters of the State. This permit replaces the permit issued in 2016. The goal of this permit is to minimize the discharge of stormwater pollutants from construction activity into waters of the State. The operator shall read and understand the conditions of the permit. A copy of the CGP is available on the DEQ web site at https://www.adeq.state.ar.us/water/permits/npdes/stormwater/. A hard copy may be obtained by contacting the DEQ's General Permits Section at (501) 682-0623.

**1. Permitted Area.** If a large or small construction activity is located within the State of Arkansas, the operator may be eligible to obtain coverage under this permit.

**2. Eligibility.** Permit eligibility is limited to discharges from "large" and "small" construction activity, or as otherwise designated by DEQ. This general permit contains eligibility restrictions, as well as permit conditions and requirements. Operators shall meet the requirements of Part I.B.6.A or Part I.B.6.B to be eligible for coverage under this permit. In such cases, operators shall continue to satisfy those eligibility provisions to maintain permit authorization. If operators do not meet the requirements that are a pre-condition to eligibility, then resulting discharges constitute unpermitted discharges. By contrast, if operators are eligible for coverage under this permit and do not comply with the requirements of the general permit, they may be in violation of the general permit for otherwise eligible discharges.

A. This general permit authorizes discharges from construction activities as defined in 40 C.F.R. §122.26(a), 40 C.F.R. §122.26(b)(14)(x), 40 C.F.R. §122.26(b)(15)(i)-(ii) and 40 C.F.R. §450.

B. This permit also authorizes stormwater discharges from support activities (e.g., concrete or asphalt batch plants, concrete truck washout, fueling, equipment staging yards, materials storage areas, excavated material disposal areas, stockpiles of top soil, borrow areas) provided:

1) The support activity is directly related to a specific construction site that is required to have NPDES permit coverage for discharges of stormwater associated with the construction activity;
2) The support activity is not a commercial operation, nor does it serve multiple unrelated construction projects; and does not continue to operate beyond the completion of the construction activity at the project it supports;
3) Pollutant discharges from support activity areas are minimized in compliance with conditions of this permit; and
4) Discharges from the support activity areas shall be identified in a Stormwater Pollution Prevention Plan (SWPPP) stating appropriate controls and measures for the areas off the construction site.

C. Other activities may be considered for this permit at the discretion of the Director as defined in 40 C.F.R. §122.26(b)(15)(ii).

3. **Responsibilities of the Operator.** Permittees with operational control are responsible for compliance with all applicable terms and conditions of this permit as it relates to their activities on the construction site including construction support activities off site, including protection of endangered species and implementation of BMPs and other controls required by the SWPPP. Receipt of this general permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance or regulation.

4. **Where to Submit.** The operator shall submit a complete and signed Notice of Intent (NOI) and SWPPP to DEQ through ePortal, unless the operator receives a waiver from DEQ, which can be found on the following website:

   https://eportal.adeq.state.ar.us/

   A. The operator shall submit the application fee to DEQ through ePortal (when available), submit an email requesting an invoice to be created to pay online, or mail in invoice from ePortal with a check (listing the invoice number on the check) to the follow address:

      Division of Environmental Quality
      ATTN: Fiscal
      5301 Northshore Drive
      North Little Rock, AR 72118-5317

   NOTE: Notice of Coverage (NOC) will **NOT** be issued until payment has been received by DEQ.

   B. Waivers from electronic reporting may be granted based on one of the following conditions:

      1) If the operational headquarters is physically located in a geographic area (i.e. Zip code or census tract) that is identified as under-served for broadcast internet access in the most recent report from the Federal Communications Commission;
      2) If available computer access or computer capability is limited; or
      3) If the operator is a religious community that choose not to use certain modern technologies pursuant to 40 C.F.R. §127.15(c)(1).

   C. In order to apply for a waiver from the electronic reporting, the operator must submit the required information outlined in 40 C.F.R. §127.15(b)(2).

   D. If DEQ grants a waiver approval to use a paper NOI, and operator elects to use it, the operator **must** use the approved form developed by DEQ.

5. **Requirements for Qualifying Local Program (QLP).** DEQ reviews and approves the QLPs to ensure that they meet or supersede both state and federal requirements outlined in this permit and 40 C.F.R. §122.44(s). DEQ will review the QLP at least every 5 years for recertification. If DEQ approves a QLP, then the QLP requirements shall at the minimum meet the DEQ's requirements. This includes all templates and forms. This permit may be modified to add new QLPs or modify existing QLPs at DEQ's discretion. All public notice and other applicable costs incurred by the modification of the permit for the addition or modification of a QLP will be paid by the QLP.

   If a small construction site is within the jurisdiction of a QLP, the operator of the small construction site is authorized to discharge stormwater associated with construction activity under QLP permit requirements only.

   At the time of issuance of this permit, only the City of Hot Springs is meeting the DEQ minimum requirements.

## 6. Requirements for Coverage.

A. *Small Construction Sites*. An operator of a small construction site will be considered to have automatic coverage under this general permit and may discharge without submitting a NOI, SWPPP or fee if the following conditions are met:

1) A completed Notice of Coverage (NOC) must be posted at the site prior to commencing construction and remain posted until final stabilization is completed;
2) A Stormwater Pollution Prevention Plan must be prepared in accordance with good engineering practice as described in Rule 6.203(B), completed prior to posting the NOC, implemented upon commencement of construction activities, and the latest copy must be maintained at the construction site;
3) All permit conditions set forth in this general permit must be followed; and
4) The operator is responsible for ensuring that the site is in compliance with any changes or updates of this general permit, by either contacting DEQ or reviewing the DEQ website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

B. *Large Construction Sites.* An operator of a large construction site discharging under this general permit shall submit the following items at least ten (10) business days prior to the commencement of construction activities:

1) A complete NOI in accordance with the requirements of Part I.B.7 of this permit.
2) A complete SWPPP in accordance with the requirements of Part II.A of this permit.
3) An initial permit fee shall accompany the NOI under the provisions of APC&EC Rule 9. Subsequent annual fees will be billed by DEQ until the operator has requested a termination of coverage by submitting a Notice of Termination (NOT). Failure to remit the required initial permit fee shall be grounds for the Director to deny coverage under this general permit. Failure to remit the required annual fees shall be grounds for the Director to revoke coverage under this permit.

C. Modification of Permit Coverage to Include Additional Acreage. Any request to increase the total acreage of a construction site shall be accompanied by a $200 permit modification fee and an updated SWPPP. Any request to only increase the disturbed acreage without changing the total acreage shall be accompanied by an updated SWPPP. A $200 permit modification fee is not required with an increase in disturbed acreage. The operator shall submit a complete and signed Additional Acreage Request Form to DEQ through ePortal, which can be found on the following website:

https://eportal.adeq.state.ar.us/

## 7. Notice of Intent (NOI) Requirements.

A. *NOI Form*. Large construction site operators who intend to seek coverage for a stormwater discharge under this general permit shall submit a complete and accurate DEQ NOI form through the ePortal system (at https://eportal.adeq.state.ar.us/) at least ten (10) business days prior to the date coverage under this permit is desired, unless granted a waiver in accordance with Part I.B.4.D. The NOI form completed **must** be the current version obtained from ePortal.

If the NOI is deemed incomplete, DEQ will notify the applicant with regard to the deficiencies by a letter, email, or phone within ten (10) business days of the receipt of the NOI. If the operator does not receive a notification of deficiencies from DEQ's receipt of the NOI, the NOI is deemed complete. If the applicant does not provide DEQ with the requested deficiencies within the deadline set by DEQ, then DEQ will return the NOI, fee and SWPPP back to the

applicant.

B. *Contents of the NOI*. The NOI form contains, at a minimum, the following information:

1) Operator (Permittee) information (name, mailing address, telephone, and E-mail address)
2) Whether the operator is a federal, state, private, public, corporation, or other entity
3) Invoice mailing information (name, address, and telephone and fax numbers)
4) Project Construction site information (name, county, address, contact person, directions to the site, latitude and longitude for the entrance of the site or the endpoints for linear project (in degrees, minutes, and seconds), estimated construction start date and completion date through site final stabilization, the total project acreage and the acreage to be disturbed by the operator submitting the NOI, type of the project (subdivision, school, etc), whether the project is part of a larger common plan of development or sale.)
5) Discharge information (name of the receiving stream, ultimate receiving stream, name of municipal storm sewer system)
6) List of current permits
7) The Certification statement and signature of a qualified signatory person in accordance with 40 CFR 122.22, as adopted by reference in APC&EC Rule 6
8) The certification of the facility corporation
9) Other information (location of the SWPPP)
10) And the SIC Code.

C. *Notice of Coverage (NOC)*. Unless notified by the Director to the contrary, operators who submit a complete NOI and SWPPP in accordance with the requirements of this permit are authorized to discharge stormwater from the construction sites under the terms and conditions of this permit ten (10) business days after the date the NOI is deemed complete (which may not be the original submission date if revisions or additions were necessary) by DEQ. If the NOC has not been received by the permittee ten (10) business days after the date the NOI is deemed complete by DEQ, the NOI may be posted until the NOC is received. Upon review of the NOI and other available information, the Director may deny coverage under this permit and require submittal of an application for an individual NPDES permit.

**8. Posting Notice of Coverage (NOC).**

A. *Automatic Coverage Sites*. The NOC for small sites, as defined in Part I.A.51, shall be obtained from the DEQ's Stormwater website:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/ .

The NOC must be posted at the site prior to commencing construction. In addition, a copy of the latest signed and certified SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

B. *Large Sites: NOC Posting for Large Construction Sites*. The posting for large construction sites shall be obtained from DEQ only after the permittee has submitted the required NOI, permit fee and complete SWPPP to DEQ for the coverage.

C. *Linear Projects*. If the construction project is a linear construction project (e.g., pipeline, highway, etc.), the notice shall be placed in a publicly accessible location near where construction is actively underway and moved as necessary.

Please note, this permit does not provide the public with any right to trespass on a construction site for any reason, including inspection of a site; nor does this permit require that the permittee allow members of the public access to a construction site.

**9. Applicable Federal, State or Local Requirements.** The operator shall ensure that the stormwater controls implemented at the site are consistent with all applicable federal, state, or local requirements. Additionally, an operator who is operating under approved local erosion and sediment plans, grading plans, local stormwater permits, or stormwater management plans shall submit signed copies of the NOI to the local agency (or authority) upon the local agency's request.

**10. Allowable Non-Stormwater Discharges.**

A. The following non-stormwater discharges as part of the construction activity may be authorized by this permit through appropriate controls. Non-stormwater discharges shall be addressed in the stormwater pollution prevention plan and measures to minimize or eliminate non-stormwater discharge should be taken if reasonably possible.
   1) Fire-fighting activities;
   2) Fire hydrant flushings;
   3) Water used to wash vehicles and equipment (where detergents, soaps, solvents or other chemicals are not used) or to control dust in accordance with Part II.A.4.J.2;
   4) Potable water sources including uncontaminated waterline flushings;
   5) Uncontaminated landscape irrigation;
   6) Uncontaminated routine external building wash down which does not use detergents, soaps, solvents or other chemicals;
   7) Uncontaminated pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless all spilled materials have been removed) and where detergents, soaps. solvents or other chemicals are not used);
   8) Uncontaminated air conditioning compressor condensate (See Part I.B.13.C of this permit);
   9) Uncontaminated springs, excavation dewatering and uncontaminated groundwater (See Part I.B.13.C of this permit);
   10) Foundation or footing drains where flows are not contaminated with process materials such as solvents or contaminated groundwater (See Part I.B.13.C of this permit).

**11. Limitations on Coverage (Exclusions).** The following stormwater discharges associated with construction activity are not covered by this permit:

A. *Post Construction Discharge.* Stormwater discharges associated with construction activities that originate from the site, as well as construction support activities located off site, after construction activities have been completed, the site has undergone final stabilization, and the permit has been terminated.

B. *Discharges Mixed with Non-Stormwater.* Stormwater discharges that are mixed with sources of non-stormwater other than those identified in Part I.B.10.

C. *Discharges Covered by another Permit.* Stormwater discharges associated with construction activity that are covered under an individual or an alternative general permit may be authorized by this permit after an existing permit expires, provided the expired permit did not establish numeric effluent limitations for such discharges.

D. *Discharges into Receiving Waters with an Approved TMDL.* Discharges from a site into receiving waters for which there is an established total maximum daily load (TMDL) allocation (https://www.adeq.state.ar.us/water/planning/integrated/tmdl/) are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that is consistent with the assumptions and requirements in the EPA approved TMDL. To be eligible for coverage under this general permit, operators shall incorporate into their SWPPP all conditions applicable to their discharges necessary for consistency with the assumptions and requirements of the TMDL within the timeframes established in the TMDL. If a specific numeric allocation has been established that

applies to the project's discharges, the operator shall incorporate that allocation into its SWPPP and implement necessary steps to meet that allocation. If a numeric limit has been assigned to the facility, quarterly monitoring shall be submitted to DEQ demonstrating compliance with the assigned Waste Load Allocation established in the TMDL. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge into a receiving stream with a TMDL, then DEQ may require additional BMPs.

E. *Discharges into Impaired Receiving Waters (303(d) List).* If stormwater discharges from a construction site enters the receiving water listed as impaired under Section 303(d) of the Clean Water Act (https://www.adeq.state.ar.us/water/planning/integrated/), the permittee shall incorporate into the SWPPP the additional BMPs needed to sufficiently protect water quality. Please note that DEQ will be reviewing this information. If it is determined that the project will discharge to an impaired water body, then DEQ may require additional BMPs.

F. *Discharges into an Extraordinary Resource Water (ERW), Natural and Scenic Waterway (NSW), or Ecologically Sensitive Waterbody (ESW).* Discharges from a construction site located within the watershed of any water body or waterway designated as an Outstanding Resource Water as defined in the APC&EC Rule 2.203, including ERWs, NSWs, or ESWs are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. For the purposes of this permit, the watershed of an Outstanding Resource Water will be identified by the United States Geological Survey's twelve (12) digit Hydrological Unit Code (HUC). Please note that DEQ will be reviewing this information. If the site will discharge to an ERW, NSW, or ESW, then DEQ may determine that additional requirements are necessary.

G. *Discharges into an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas.* Discharges from a construction site located within the watershed of any potential losing stream and/or sensitive aquatic species native to the area are not eligible for coverage under this permit unless the permittee develops and certifies a SWPPP that includes additional BMPs needed to prevent to the maximum extent possible exposure to precipitation and to stormwater of pollutants that could potentially impact water quality. In accordance with Part I.B.3, it is the responsibility of the permittee to prevent activity which may take or otherwise risk harm to endangered species. Please note that DEQ will be reviewing this information. If the site will discharge to an area of the state which includes potential losing stream and/or sensitive aquatic species native to these areas, then DEQ may determine that additional requirements are necessary.

**12. Short Term Activity Authorization (STAA).** Any work being conducted in waters of the State will require a STAA from DEQ in accordance with Rule 2.305. An STAA is necessary for any in-stream activity that has the potential to exceed the water quality standards, including, but not limited to: gravel removal, bridge or crossing repair/maintenance, bank stabilization, debris removal, culvert replacement, flood control projects, and stream relocation. Any work being conducted in Waters of the United States may require a Section 404 permit from the U.S. Army Corps of Engineers. This permit does not authorize any activity under an STAA, Individual 401 Certification, or Section 404 permit. The necessary forms to apply for coverage under an STAA or Individual 401 Certification can be found on the following website:

https://www.adeq.state.ar.us/water/planning/instream/

The SWPPP shall be updated to include a copy of the STAA letter (and Individual 401 Certification if needed) upon receipt. Re-submittal of the SWPPP is not required unless specifically requested by DEQ.

**13. Effluent Limitation Guidelines (ELG).** All permittees shall comply with the following effluent limits:

A. *Erosion and Sediment Controls.* Design, install, and maintain effective erosion controls and sediment controls to minimize the discharge of pollutants. At a minimum, such controls shall be designed, installed and maintained to:

1) Control stormwater volume and velocity to minimize soil erosion in order to minimize pollutant discharges;
2) Control stormwater discharges, including both peak flowrates and total stormwater volume, to minimize channel and streambank erosion and scour in the immediate vicinity of discharge points;
3) Minimize the amount of soil exposed during construction activity;
4) Minimize the disturbance of steep slopes;
5) Minimize sediment discharges from the site. The design, installation and maintenance of erosion and sediment controls shall address factors such as the amount, frequency, intensity and duration of precipitation, the nature of resulting stormwater runoff, and soil characteristics, including the range of soil particle sizes expected to be present on the site;
6) Provide and maintain natural buffers around waters of the State, direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible;
7) Minimize soil compaction. Minimizing soil compaction is not required where the intended function of a specific area of the site dictates that it be compacted; and
8) Unless infeasible, preserve topsoil. Preserving topsoil is not required where the intended function of a specific area of the site dictates that the topsoil be disturbed or removed.

B. *Soil Stabilization.* Stabilization of disturbed areas must, at a minimum, be initiated immediately (unless weather conditions do not allow immediate initiation) whenever any clearing, grading, excavating or other earth disturbing activities have permanently ceased on any portion of the site, or temporarily ceased on any portion of the site and will not resume for a period exceeding fourteen (14) calendar days. In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures must be employed as specified by the permitting authority. Stabilization must be completed within fourteen (14) calendar days. In limited circumstances, stabilization may not be required if the intended function of a specific area of the site necessitates that it remain disturbed.

C. *Dewatering.* Discharges from dewatering activities, including discharges from dewatering of trenches and excavations, are prohibited unless managed by appropriate controls. There shall be no turbid discharges to waters of the State resulting from dewatering activities. If trench or ground waters contain sediment, it shall pass through a sediment settling pond or other equally effective sediment control device, prior to being discharged from the construction site. Alternatively, sediment may be removed by settling in place or by dewatering into a sump pit, filter bag, or comparable practice. Ground water dewatering which does not contain sediment or other pollutants is not required to be treated prior to discharge. However, care shall be taken when discharging ground water to ensure that it does not become pollutant-laden by traversing over disturbed soils or other pollutant sources.

D. *Pollution Prevention Measures.* Design, install, implement, and maintain effective pollution prevention measures to minimize the discharge of pollutants. At a minimum, such measures shall be designed, installed, implemented and maintained to:

1) Minimize the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other wash waters. Wash waters shall be treated in a sediment basin or BMP control that provides equivalent or better treatment prior to discharge;
2) Minimize the exposure of building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials present on the site to precipitation and to stormwater. Minimization of exposure is not required in cases where the exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use); and
3) Minimize the discharge of pollutants from spills and leaks and implement chemical spill and leak prevention and response procedures.

E. *Prohibited discharges.* The following discharges are prohibited:

1) Wastewater from washout of concrete, unless managed by an appropriate control;
2) Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds and other construction materials;
3) Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance; and
4) Soaps, solvents, or detergents used in vehicle, equipment washing, or external building washdown.
5) Toxic or hazardous substances from a spill or release.

F. *Surface Outlets.* When discharging from basins and impoundments, utilize outlet structures that withdraw water from the surface, unless infeasible.

**14. Natural Buffer Zones.** A natural buffer zone as stated below shall be maintained at all times and direct stormwater to vegetated areas and maximize stormwater infiltration to reduce pollutant discharges, unless infeasible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law.

A. For construction projects where construction activities or construction support activities occur, the SWPPP shall provide at least twenty-five (25) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from any waters of the State.

B. DEQ will require at least fifty (50) feet of natural buffer zone, as measured horizontally from the top of the bank to the disturbed area, from established TMDL water bodies, streams listed on the 303(d) list, an Extraordinary Resource Water (ERW), Ecologically Sensitive Waterbody (ESW), Natural and Scenic Waterway (NSW), or any other uses at the discretion of the Director.

C. Linear projects will be evaluated individually by DEQ to determine natural buffer zone setbacks.

**15. Waivers from Permit Coverage.** The Director may waive the otherwise applicable requirements of this general permit for stormwater discharges from construction activities under the terms and conditions described in this section.

A. *Waiver Applicability and Coverage*. Based upon 40 C.F.R. §122.26.b.15.i.A, operators of small construction activities may apply for and receive a waiver from the requirements to obtain this permit.

B. *No Stormwater Leaving the Site.* If all of the stormwater from the construction activity is captured on-site under any size storm event and allowed to evaporate, soak into the ground on-site, or is used for irrigation, a permit is not needed.

C. *TMDL Waivers.* This waiver is available for sites with automatic coverage if the DEQ has established or approved a TMDL that addresses the pollutant(s) of concern and has determined that controls on stormwater discharges from small construction activity are not needed to protect water quality. The pollutant(s) of concern include sediment (such as total suspended solids, turbidity or siltation) and any other pollutant that has been identified as a cause of impairment of any water body that will receive a discharge from the construction activity. The operator must certify to the Director that construction activity will take place, and storm water discharges will occur within the drainage area addressed by the TMDL or equivalent analysis. Information on approved TMDLs is available on DEQ's website:

https://www.adeq.state.ar.us/water/planning/integrated/tmdl/.

**16. Notice of Termination (NOT).** When all construction activities that disturbed soil are complete, the site has reached final stabilization (100% stabilization with 80% density or greater, or as defined in Part I.A.25.B for sites where background native vegetation will cover less than 100% of the ground), all stormwater discharges from construction activities authorized by this permit are eliminated and all temporary sediment controls are removed and properly disposed, the operator of the facility may submit a complete Notice of Termination (NOT) to the Director. Along with the NOT, pictures that represent the entire site shall be submitted for review. Final stabilization is not required if the land is returned to its pre-construction agriculture use. Operators of small construction sites are not required to submit NOTs for their construction sites. However, final stabilization is required on all sites. If a NOT is not submitted when the project is completed, the operator will be responsible for annual fees.

**17. Responsibilities of the Operator of a Larger Common Plan of Development or Sale.**

A. The operator is ultimately responsible for the runoff from the perimeter of the entire development. Regardless of the reason for the runoff, the operator is responsible for ensuring sufficient overall controls of the development.

B. The operator shall not terminate the permit coverage until the following conditions have been met:

1) After all construction activities including landscaping and lot development has been completed; and
2) All lots are sold and developed.

The following exceptions to this requirement may apply:

a. Less than 100% sold and developed at the discretion of the Director, or
b. Separation of the larger common plan if twenty-four (24) months have passed with no construction activity, or
c. All lots are developed and there are no temporary common controls for subdivision outfalls, i.e. sediment basins, large sediment traps, check dams, etc.

3) If lots are sold and then re-sold to a third party, permit coverage shall be obtained by each of the operators while they have ownership of the lots. The second owner is responsible for obtaining the same certification from the third owner (i.e. the certification shall pass from owner to owner).

C. The operator shall not terminate permit coverage until the operators of all of the individual lots within the larger common plan of development or sale are notified of their permitting requirements under this general permit. In this case, the signed certification statements from each operator of individual lots shall be maintained in the stormwater pollution prevention plan for the larger common plan of development or sale. A copy of the signed certifications shall be submitted to DEQ with the NOT. The certification shall be as follows:

"I, _____, operator of an individual lot #_____, block #_____ of _____ subdivision, certify under penalty of law that I was notified by the operator of the larger common plan of the stormwater permitting requirements for my construction site(s). I understand prior to commencement of any construction activity I have to prepare and comply with a SWPPP and post the Construction Site Notice . I understand that prior to the sale of this lot to another party; I must notify the new owner of DEQ requirements and obtain this certification from the new owner."

Signature _____

D. The following examples are provided as clarification:

1) If a small portion of the original common plan of development remains undeveloped and there has been a period of time (i.e., more than 24 months) where there are no ongoing construction activities (i.e., all areas are either undisturbed or have been finally stabilized), operators may re-evaluate the original project based on the acreage remaining from the original "larger common plan of development or sale." If less than five (5) but more than one (1) acre remains to build out the original "common plan", coverage under the large permit may not be required. However, operators will need to comply with the terms and conditions for Small Construction Sites in the Construction General Permit. If less than one acre remains of the original common plan, the individual project may be treated as a part of a less than one acre development and no permit would be required.
2) If operators have a long-range master plan of development or sale where some portions of the master plan are conceptual rather than a specific plan of future development and the future construction activities would, if they occur at all, happen over an extended period of time (i.e., more than 24 months), operators may consider the "conceptual" phases of development to be separate "common plans" provided the periods of construction for the physically interconnected phases will not overlap.
3) Where discrete construction projects within a larger common plan of development or sale are located ¼ mile or more apart and the area between the projects is not being disturbed, each individual project can be treated as a separate plan of development or sale provided any interconnecting road, pipeline or utility project that is part of the same "common plan" is not concurrently being disturbed. For example, if an interconnecting access road or pipeline were under construction at the same time, they would generally be considered as a part of a single "common plan" for permitting purposes.
4) If the operator sells all the lots in the subdivision to one or more multi-lot homebuilder(s), provisions shall be made to obtain stormwater permit coverage by one of the following options:
   a. The permit may be transferred from the first "operator" to the new/second "operator".
   b. A new, separate permit coverage may be obtained by the second "operator".
   NOTE: If a new permit coverage is to be obtained, then it shall be obtained before the first/original permit is terminated.
5) If the operator retains ownership of any lots in the subdivision, the operator shall maintain permit coverage for those lots under the original permit coverage. The operator shall modify the SWPPP by stating which lots are owned and marking the lots on the site map. If there are one (1) or two (2) lots remaining and the total acreage is less than five (5) acres, the original permit coverage could be terminated and those lots could be covered as a small site.

**18. <u>Change in Operator</u>.** For stormwater discharges from large construction sites where the operator changes, including instances where an operator is added after the initial NOI has been submitted, the new operator shall ensure that a permit transfer form is received by DEQ at least two (2) weeks prior to the new operator beginning work at the site.

**19. <u>Late Notifications</u>.** A discharger is not precluded from submitting an NOI in accordance with the requirements of this part after the dates provided in Part I.B.7 of this permit. In such instances, the Director may bring an enforcement action for failure to submit an NOI in a timely manner or for any unauthorized discharges of stormwater associated with construction activity that have occurred on or after the dates specified in this permit.

**20. <u>Failure to Notify</u>.** The operator of a construction site who fails to notify the Director of their intent to be covered under this permit, and who potentially discharges pollutants (sediment, debris, etc.) to waters of the State without an NPDES permit, is in violation of the Arkansas Water and Air Pollution Control Act.

**21. <u>Maintenance</u>.** Determination of the acreage of disturbance does not typically include disturbance for routine maintenance activities on existing roads where the original line and grade, hydraulic capacity, or original purpose of the road is not being altered, nor does it include the paving of existing roads. Maintenance activities (returning to original conditions) are not

regulated under this permit unless one or more acres of underlying or surrounding soil are cleared, graded, or excavated as part of the operation.

**22. Releases in Excess of Reportable Quantities.**

A. The discharge of hazardous substances or oil in the stormwater discharge(s) from a facility shall be prevented or minimized in accordance with the applicable stormwater pollution prevention plan for the facility. This permit does not relieve the operator of the reporting requirements of 40 C.F.R. §110, §117 and §302. Where a release containing a hazardous substance or oil in an amount equal to or in excess of a reporting quantity established under either 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302, occurs during a twenty-four (24) hour period, the following action shall be taken:

1) Any person in charge of the facility is required to notify the National Response Center (NRC) (800-424-8802) in accordance with the requirements of 40 C.F.R. §110, 40 C.F.R. §117, or 40 C.F.R. §302 as soon as he/she has knowledge of the discharge;
2) The operator shall submit within five (5) calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, and the circumstances leading to the release, and steps to be taken in accordance with Part II.B.17 of this permit to the DEQ.
3) The SWPPP described in Part II.A of this permit shall be modified within fourteen (14) calendar days of knowledge of the release to:

    a. Provide a description of the release and the circumstances leading to the release; and
    b. The date of the release;

4) Additionally, the SWPPP shall be reviewed to identify measures to prevent the reoccurrence of such releases and to respond to such releases, and the plan shall be modified where appropriate.

B. *Spills*. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.

**23. Attainment of Water Quality Standards.**

The operator shall select, install, implement, and maintain control measures at the construction site and construction support activities off site that minimize the discharge of pollutants for which a stream is impaired at the discretion of the Director as necessary to protect water quality. In general, except in situations explained below, the stormwater controls developed, implemented, and updated to be considered stringent enough to ensure that discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.

At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:

A. Develop a supplemental BMP action plan describing SWPPP modifications to address adequately the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

B. Cease discharges of pollutants from construction activity and submit an individual permit application.

All written responses required under this part shall include a signed certification consistent with Part II.B.9.

**24. Requiring an Individual Permit**

The Director may require any person eligible for coverage under the general permit to apply for and obtain an individual permit. In addition, any interested person(s) may submit an application for an individual permit. The Director may consider the issuance of individual permits according to the criteria in 40 C.F.R. §122.28(b)(3).

Coverage of the facility under this general permit is may be terminated by DEQ if the operator fails to submit or respond to the permitting process or requests for information in a timely manner.

Any operator covered under this general permit may request to be excluded from the coverage of this permit by applying for an APC&EC Rule 6 individual permit. The operator shall submit an application for an individual permit with the reasons supporting the application to DEQ. If a final, individual NPDES permit is issued to an operator otherwise subject to this general permit, the operator is required to submit a NOT. Coverage under this general permit will then be terminated no earlier than the effective date of the individual NPDES permit. Otherwise, the applicability of this general permit to the facility remains in full force and effect.

# PART II
# STANDARD CONDITIONS

Information in **Part II** is organized as follows:

**Section A:** Stormwater Pollution Prevention Plans (SWPPP):

1. Deadlines for Plan Preparation and Compliance
2. Signature, SWPPP, Inspection Reports, and Notice of Coverage (NOC)
3. Keeping SWPPP Current
4. Contents of the Stormwater Pollution Prevention Plan
5. Plan Certification

**Section B:** Standard Permit Conditions:

1. Retention of Records
2. Duty to Comply
3. Penalties for Violations of Permit Conditions
4. Continuance of the General Permit
5. Need to Halt or Reduce Activity Not a Defense
6. Duty to Mitigate
7. Duty to Provide Information
8. Other Information
9. Signatory Requirements
10. Certification
11. Penalties for Falsification of Reports
12. Penalties for Tampering
13. Oil and Hazardous Substance Liability
14. Property Rights
15. Severability
16. Transfers
17. Proper Operation and Maintenance
18. Inspection and Entry
19. Permit Actions
20. Re-Opener Clause
21. Local Requirements
22. Applicable Federal, State Requirements

## SECTION A: STORMWATER POLLUTION PREVENTION PLANS (SWPPP)

The operator shall prepare a SWPPP before permit coverage. The SWPPP shall follow the order outlined in Part II.A.4 & 5 below. This basic DEQ format is available through DEQ's website https://www.adeq.state.ar.us/water/permits/npdes/stormwater/. Other formats may be used at the discretion of the Director if the format has been approved by DEQ prior to use. The operator shall implement the SWPPP as written from initial commencement of construction activity until final stabilization is complete, with changes being made as deemed necessary by the permittee, local, state or federal officials. The plan shall be prepared in accordance with good engineering practices, by qualified personnel and shall:

- Identify potential sources of pollution which may reasonably be expected to affect the quality of stormwater discharges from the construction site and construction support activities off site;
- Identify, describe and ensure the implementation of BMPs, with emphasis on initial site stabilization, which are to be used to reduce pollutants in stormwater discharges from the construction site and construction support activities off site;
- Be site specific to what is taking place on a particular construction site;
- Ensure compliance with the terms and conditions of this permit; and
- Identify the responsible party for on-site SWPPP implementation.

### 1. Deadlines for Plan Preparation and Compliance.

A. *Automatic Coverage Sites.*

The plan shall be completed prior to obtaining permit coverage and commencement of construction activities and updated as appropriate. Submittal of the NOI, permit fee and SWPPP is not required. All conditions set forth in Part II.A must be followed, and the NOC must be posted at the site prior to commencing construction activities. In addition, a copy of the SWPPP must be available at the construction site in accordance with Part II.A.2.B and D prior to commencing construction.

B. *Large Construction Sites.*

The plan shall be completed and submitted for review, along with an NOI and initial permit fee ten (10) business days prior to the commencement of construction activities. Submittals of updates to the plan during the construction process are required in accordance with Part I.B.6.C or if requested by the Director.

C. *Existing Permittees.*

Existing permittees that were permitted prior to the issuance of this renewal permit are required to update their plan as appropriate to come into compliance with the requirements contained in Part II.A.4 by the effective date of this permit.

### 2. Signature, SWPPP, Inspection Reports and Notice of Coverage (NOC).

A. The SWPPP and inspection reports shall be signed by the operator (or cognizant official) in accordance with Part II.B.9 and be retained at the construction site during normal business hours (8:00 A.M. – 5:00 P.M.). The inspections frequency shall be conducted in accordance with Part II.A.4.N.1.

B. The operator shall make SWPPP and inspection reports available, upon request, to the Director, the EPA, or a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or, in the case of a stormwater discharge associated with construction activity which discharges through a municipal separate storm sewer system with an NPDES permit, to the municipal operator of the system.

C. The Director, or authorized representative, may notify the operator at any time that the plan does not meet one or more of the minimum requirements of this Part. Within seven (7) business days of such notification from the Director (or as otherwise provided by the Director) or authorized representative, the operator shall make the required changes to the plan and submit to the Director a written certification that the requested changes have been made. DEQ may request re-submittal of the SWPPP to confirm that all deficiencies have been adequately addressed. DEQ may also take appropriate enforcement action for the period of time the operator was operating under SWPPP that did not meet the minimum requirements of this permit.

D. The operator shall post the NOC near the main entrance of the construction site and visible to the public. The NOC shall indicate the location of the SWPPP. If the SWPPP location is changed from the initial location, the NOC shall be updated to reflect the correct location of the SWPPP.

**3. Keeping SWPPP Current.** The operator shall amend the SWPPP within seven (7) business days or whenever there is a change in design, construction, operation, or maintenance at the construction site which has or could have a significant effect on the potential for the discharge of pollutants to the waters of the State that has not been previously addressed in the SWPPP. The SWPPP shall also be modified if a determination has been made through inspections, monitoring (if required), ***or*** investigation by the operator, local, state, or federal officials that the discharges are causing or contributing to water quality violation or the plan proves to be ineffective in eliminating or significantly minimizing pollutants from sources identified in stormwater discharges from the construction site.

**4. Contents of the SWPPP.** The SWPPP shall include the following items:

A. *Site Description*. SWPPP shall provide a description of the following:

1) A description of the nature of the construction activity and its intended use after the NOI is filed (i.e., residential subdivision, shopping mall, etc.);
2) A description of the intended sequence of major activities which disturb soils for major portions of the site (e.g. grubbing, excavation, grading, infrastructure installation, etc.);
3) Estimates of the total area of the site including off-site borrow and fill areas and the total area of the site that is expected to be disturbed by excavation, grading or other activities; and
4) An estimate of the runoff coefficient of the site for pre- and post-construction activities and existing data describing the soil or the quality of any discharge from the site.

B. *Responsible Parties*. The SWPPP shall identify (as soon as this information is known) all parties (i.e., General Contractors, Landscapers, Project Designers, and Inspectors) responsible for particular construction activities and services they provide to the operator to comply with the requirements of the SWPPP for the project site and construction support activities off site, and areas over which each party has control. If these parties change over the life of the permit, or new parties are added, the SWPPP shall be updated to reflect these changes.

C. *Receiving Waters*. The SWPPP shall include a clear description of the nearest receiving water(s), or if the discharge is to a MS4, the name of the operator of the municipal system, and the ultimate receiving water(s).

D. *Documentation of Permit Eligibility Related to the 303(d) list and Total Maximum Daily Loads (TMDL)*. The SWPPP shall include information on whether or not the stormwater discharges from the site enter a waterbody that is on the most recent 303(d) list or with an approved TMDL. If the stormwater discharge does enter a waterbody that is on the most recent 303(d) list or with an approved TMDL, then the SWPPP shall address the following items:

1) Identification of the pollutants that the 303(d) list or TMDL addresses, specifically whether the 303(d) list or TMDL addresses sediment or a parameter that addresses sediment (such as total suspended solids, turbidity, or siltation);
2) Identification of whether the operator's discharge is identified, either specifically or generally, on the 303(d) list or

any associated assumptions and allocations identified in the TMDL for the discharge; and

3) Measures taken by the operator to ensure that its discharge of pollutants from the site is consistent with the assumptions and allocations of the TMDL.

If DEQ determines during the review process that the proposed project will be discharging to a receiving water that is on the most recent 303(d) list or with an approved TMDL, then DEQ may notify the applicant to include additional Best Management Practices in the SWPPP.

E. *Documentation of Permit Eligibility Related to Discharges into an ERW, NSW, or ESW*. The SWPPP shall include information whether or not the construction site located within a watershed of an ERW, ESW, or NSW. If the construction site is located within a watershed of an ERW, ESW, or NSW, then the SWPPP should consider using additional BMPs for these areas. The practices shall be considered during the progression of site activities and updates to the construction site SWPPP for continued protection of underground water resources.

F. *Documentation of Permit Eligibility related to potential losing stream and/or sensitive aquatic species native to these areas.* The SWPPP shall include information whether or not the construction site located within a watershed of a potential losing stream, and/or sensitive aquatic species native to these areas. If the construction site is located within a watershed of a potential losing stream and/or sensitive aquatic species native to these areas, then the SWPPP shall consider using BMPs for losing stream areas. The practices should be considered during the progression of site activities and updates to the facility SWPPP for continued protection of underground water resources.

G. *Attainment of Water Quality Standards After Authorization*.

1) The permittee shall select, install, implement, and maintain BMPs at the construction site and at the construction support activities off site that minimize pollutants in the discharge as necessary to meet applicable water quality standards. In general, except in situations explained below, the SWPPP shall be developed, implemented, and updated to be considered as stringent as necessary to ensure that the discharges do not cause, have the reasonable potential to cause, or contribute to an excursion above any applicable water quality standard.

2) At any time after authorization, DEQ may determine that the stormwater discharges may cause, have reasonable potential to cause, or contribute to an excursion above any applicable water quality standard. If such a determination is made, DEQ will require the permittee to:

   a. Develop a supplemental BMP action plan describing SWPPP modifications to adequately address the identified water quality concerns and submit valid and verifiable data and information that are representative of ambient conditions and indicate that the receiving water is attaining water quality standards; or

   b. Cease discharges of pollutants from construction activity and submit an individual permit application.

3) All written responses required under this part shall include a signed certification (Part II.B.9).

H. *Site Map*. The SWPPP shall contain a legible site map (or multiple maps, if necessary) complete to scale, showing the entire site, that identifies, at a minimum, the following:

1) Pre-construction topographic view;
2) Direction of stormwater flow (i.e., use arrows to show which direction stormwater will flow) and approximate slopes anticipated after grading activities;
3) Delineate on the site map areas of soil disturbance and areas that will not be disturbed with regards to the construction activities and construction support activities off site under the coverage of this permit;
4) Location of major structural and nonstructural controls identified in the plan;
5) Location of main construction entrance and exit;

6) Location where stabilization practices are expected to occur;
7) Locations of all construction support activities off-site (i.e. materials, waste, borrow area, or equipment storage areas);
8) Location of areas used for concrete wash-out;
9) Location of all waters of the State with associated natural buffer boundary lines. Identify floodplain and floodway boundaries, if available;
10) Locations where stormwater is discharged to waters of the State or a municipal separate storm sewer system if applicable,
11) Locations where stormwater is discharged off-site (shall be continuously updated);
12) Areas where final stabilization has been accomplished and no further construction phase permit requirements apply;
13) A legend that clearly specifies any erosion and sediment control measure symbols/labels used in the site map and/or detail sheet; and
14) Locations of any storm drain inlets on the site and in the immediate vicinity of the site.

I. *Stormwater Controls*. Each plan shall include a description of appropriate controls and measures that will be installed and implemented at the construction site. The plan shall clearly describe each construction activity identified in the project description control measures associated with the construction activity and the schedule during the construction process that the measures will be implemented. Perimeter controls for the site shall be installed after the clearing and grubbing necessary for installation of the measure, but before the clearing and grubbing for the remaining portions of the site. Perimeter controls shall be actively maintained until final stabilization of those portions of the site upward of the perimeter control. Temporary controls shall be removed and properly disposed of after final stabilization. The description and implementation of controls shall address the following minimum components:

1) Initial Site Stabilization, Erosion, and Sediment Controls and Best Management Practices. Design, install, implement, and maintain effective erosion and sediment controls to minimize the discharge of pollutants. At a minimum the following controls and BMPs shall be designed, installed, implemented, and maintained. Therefore, the SWPPP shall address, at a minimum, the following:

   a. For larger common plans of development or sale, only streets, drainage, utility areas, areas needed for initial construction of streets (e.g., borrow pits, parking areas, etc.) and areas needed for stormwater structures may be disturbed initially. Upon stabilization of the initial areas, additional areas may be disturbed.
   b. The construction-phase erosion (such as site stabilization) and sediment controls (such as check dams) shall be designed to retain sediment on-site to the extent practicable.
   c. All control measures shall be properly selected, installed, and maintained in accordance with the manufacturer's specifications, good engineering, and construction practices. If periodic inspections or other information indicates a control has been used inappropriately or incorrectly, the permittee shall replace or modify the control for site situations.
   d. If sediment escapes the construction site, off site accumulations of sediment shall be removed before the next business day to minimize off-site impacts (e.g., to prevent fugitive sediment in a street could be washed into storm sewers by the next rain or pose a safety hazard to users of public streets). This permit does not give the authority to trespass onto other property; therefore this condition should be carried out along with the permission of neighboring land owners to remove sediment.
   e. Sediment shall be removed from sediment traps (if used, please specify what type) or sedimentation ponds when design capacity has been reduced by 50%.
   f. Litter, construction debris, and construction chemicals exposed to precipitation and to stormwater shall be prevented from becoming a pollutant source for stormwater discharges (e.g., screening outfalls picked up daily).
   g. Construction support activities off site (i.e. material storage areas, overburden and stockpiles of dirt, borrow areas, etc.) used solely by the permitted project are considered a part of the project and shall be addressed in the SWPPP.

2) Stabilization practices. The SWPPP shall include, at a minimum, the following information:

a. Description and Schedule: A description of initial, interim, and permanent stabilization practices, including site-specific scheduling of the implementation of the practices. Site plans shall ensure that existing vegetation is preserved where attainable and that disturbed areas are stabilized. Stabilization practices may include, but not limited to: mulching, temporary seeding, permanent seeding, geotextiles, sod stabilization, natural buffer strips, protection of trees, and preservation of mature vegetation and other appropriate measures.

b. Description of natural buffer areas: DEQ requires that a natural buffer zone be established between the top of stream bank and the disturbed area. The SWPPP shall contain a description of how the site will maintain natural buffer zones. For construction projects where clearing and grading activities will occur, SWPPP shall provide at least twenty-five (25) feet of natural buffer zone from any named or unnamed streams, creeks, rivers, lakes or other water bodies. The plan shall also provide at least fifty (50) feet of natural buffer zone from established TMDL waterbodies, waterbodies listed on the 303(d) list, an ERW, ESW, NSW, or other uses at the discretion of the Director. If the site will be disturbed within the recommended buffer zone, then the buffer zone area shall be stabilized as soon as possible. Exceptions from this requirement for areas such as water crossings, limited water access, and restoration of the buffer are allowed if the permittee fully documents in the SWPPP the circumstances and reasons for the buffer zone encroachment. Additionally, this requirement is not intended to interfere with any other ordinance, rule or regulation, statute or other provision of law. Please note that above-grade clearing that does not disturb the soil in the buffer zone area does not have to comply with buffer zone requirements.

c. Records of Stabilization: A record of the dates when grading activities occur, when construction activities temporarily or permanently cease on a portion of the site, and when stabilization measures are initiated shall be included in the plan.

d. Deadlines for Stabilization After Construction Activity Temporarily Ceases: Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily ceased, but in no case more than fourteen (14) calendar days after the construction activity in that portion of the site has temporarily ceased, except:

(1) Where the initiation of stabilization measures by the fourteenth ($14^{th}$) calendar day after construction activity temporarily ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.

(2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.

e. Deadline for Stabilization After Construction Activity Permanently Ceases: Stabilization measures shall be initiated immediately in portions of the site where construction activities have permanently ceased, except:

(1) Where the initiation of stabilization measures immediately after construction activity permanently ceases is precluded by snow cover, stabilization measures shall be initiated as soon as practicable.

(2) In arid, semiarid, and drought-stricken areas where initiating vegetative stabilization measures immediately is infeasible, alternative stabilization measures shall be employed as specified by the permitting authority.

3) Structural Practices. A description of structural practices to divert flows from exposed soils, store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site to the degree attainable. Structural practices should be placed on upland soils to the degree attainable. The installation of these devices may

be subject to Section 404 of the Clean Water Act. Such practices may include but are not limited to:

- silt fences (installed and maintained);
- earthen dikes to prevent run-on;
- drainage swales to prevent run-on;
- check dams;
- subsurface drains;
- pipe slope drains;
- storm drain inlet protection;
- rock outlet protection;
- sediment traps;
- reinforced soil retaining systems;
- gabions;
- temporary or permanent sediment basins.

A combination of erosion and sediment control measures is encouraged to achieve maximum pollutant removal. Adequate spillway cross-sectional area and re-enforcement shall be provided for check dams, sediment traps, and sediment basins.

a. Sediment Basins:

(1) For common drainage locations that serve an area with ten (10) or more acres (including run-on from other areas) draining to a common point, a temporary or permanent sediment basin that provides storage based on either the smaller of 3600 cubic feet per acre, or a size based on the runoff volume of a 10 year, 24 hour storm, shall be provided where attainable (so as not to adversely impact water quality) until final stabilization of the site. In determining whether installing a sediment basin is attainable, the operator may consider factors such as site soils, slope, available area on site, etc. Proper hydraulic design of the outlet is critical to achieving the desired performance of the basin. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. If "non-attainability" is claimed, then an explanation of non-attainability shall be included in the SWPPP**.** Where a sediment basin is not attainable, smaller sediment basins or sediment traps shall be used. Where a sediment basin is un-attainable, natural buffer strips or other suitable controls which are effective are required for all side slopes and down slope boundaries of the construction area. The plans for removal or final usage of the sediment basin shall be included with the description of the basin in the SWPPP.

(2) For drainage locations serving an area less than ten (10) acres, sediment traps, silt fences, or equivalent sediment controls are required for all side slope and down slope boundaries of the construction area unless a sediment basin providing storage based on either the smaller of 3600 cubic feet per acre, or a size based on the run off volume of a 10 year, 24 hour storm is provided. The outlet should be designed to drain the basin within twenty-four (24) to seventy-two (72) hours. (A rule of thumb is one square foot per acre for a spillway design.) The 24-hour limit is specified to provide adequate settling time; the seventy-two (72) hour limit is specified to mitigate vector control concerns. If a pipe outlet design is chosen for the outfall, then an emergency spillway is required. However, in order to protect the waters of the State, the Director, at their discretion, may require a sediment basin for any drainage areas draining to a common point.

b. Velocity Dissipation Devices:

Velocity dissipation devices shall be placed at discharge locations, within concentrated flow areas serving two

or more acres, and along the length of any outfall channel to provide a non-erosive flow velocity from the structure to a water course so that the natural physical and biological characteristics and functions are maintained and protected (i.e., no significant changes in the hydrological regime of the receiving water). Please note that the use of hay-bales is not recommended in areas of concentrated flow.

J. *Other Controls*.

1) No solid materials identified in Part I.B.13.D shall be discharged to waters of the State or offsite.
2) Off-site vehicle tracking of sediments and the generation of dust shall be minimized through the use of a stabilized construction entrance and exit or vehicle tire washing.
3) For lots that are less than one (1) acre in size an alternative method may be used in addition to a stabilized construction entrance. An example of an alternative method could be daily street sweeping. This could allow for the shortening of the construction entrance.
4) The plan shall ensure and demonstrate compliance with applicable State or local waste disposal, temporary and permanent sanitary sewer or septic system regulations.
5) No liquid concrete waste shall be discharged to waters of the State. Appropriate controls to prevent the discharge of concrete washout waters shall be implemented if concrete washout will occur on-site.
6) No contaminants from fuel storage areas, hazardous waste storage and truck wash areas shall be discharged to waters of the State or offsite. Methods for protecting these areas shall be identified and implemented. These areas shall not be located near a waterbody, if there is a water body on or near the project.

K. *Non-stormwater discharges*. Sources of non-stormwater listed in Part I.B.10 of this permit that are combined with stormwater discharges associated with construction activity shall be identified in the plan. This list shall be site specific non-stormwater discharges.

L. *Post-Construction Stormwater Management*. The operator is required to provide a description of measures that will be installed during the construction process to control pollutants in stormwater discharges that will occur after construction operations have been completed. Structural measures shall be placed on upland soils to the degree attainable. The installation of these devices may be subject to Section 404 (Corps of Engineers) of the Clean Water Act. This permit only addresses the installation of stormwater management measures, and not the ultimate operation and maintenance of such structures after the construction activities have been completed and the site has undergone final stabilization. However, post-construction stormwater BMPs that discharge pollutants from a point source once construction is completed may need authorization under a separate DEQ NPDES permit. Such practices may include but are not limited to:

- infiltration of runoff onsite;
- flow attenuation by use of open vegetated swales and natural depressions;
- stormwater retention structures;
- stormwater detention structures (including wet ponds);
- sequential systems, which combine several practices.

A goal of at least eighty percent 80 % removal of total suspended solids from these flows which exceed predevelopment levels should be used in designing and installing stormwater management controls (where practicable). Where this goal is not met, the operator shall provide justification for rejecting each practice listed above based on site conditions.

M. *Applicable State or Local Programs*. The SWPPP shall be updated as necessary to reflect any revisions to applicable federal, state, or local requirements that affect the stormwater controls implemented at the site.

N. *Inspections*. Inspections shall be conducted by qualified personnel (provided by the operator). Inspections shall include all areas of the site disturbed by construction activity and construction support activities located off site that are exposed to precipitation and to stormwater. Inspectors shall look for evidence of, or the potential for, pollutants entering

the stormwater conveyance system. All stormwater control measures shall be observed to ensure proper installation, operation, and maintenance. Discharge locations shall be inspected to determine whether all stormwater control measures are effective in preventing significant impacts to waters of the State or offsite, where accessible. Where discharge locations are inaccessible, nearby downstream locations shall be inspected to the extent that such inspections are practicable. Locations where vehicles enter or exit the site shall be inspected for evidence of off-site sediment tracking. Inspections may not be required if the remaining lot(s) within a larger common plan of development or sale disturb less than one acre of land In addition, inspections may not be required on a completed section of a linear project if final stabilization has been completed for that section. Stabilized areas of the project shall be indicated in the SWPPP and site map and show what date they were stabilized. The operator shall ensure that no sediment will leave the lot(s) that are stabilized. These lots shall be identified within the SWPPP and show what date they were stabilized. If the operator is unable to ensure this, then inspections shall continue.

1) Inspection Frequency. Inspections shall be conducted in accordance with one of the following schedules listed below. The schedule **must be specified** in the SWPPP.

   a. At least once every seven (7) calendar days, or
   b. At least once every fourteen (14) calendar days and within twenty-four (24) hours of the end of a storm event of 0.25 inches or greater (a rain gauge must be maintained on-site).

2) Inspection Form. The DEQ inspection form should be used for all inspections. The inspection form shall include all stormwater controls that are being used on site as well as at construction support activities off site. The form is available on DEQ's website www.adeq.state.ar.us. If a different form is used, it shall at a minimum contain the following information:

   a. Inspector name and title;
   b. Date of Inspection;
   c. Amount of rainfall and days since last rain event (only applicable to Part II.A.4.N.1.b);
   d. Approximate beginning and duration of the storm event;
   e. Description of any discharges during inspection;
   f. Locations of discharges of sediment/other pollutants;
   g. Locations of BMPs in need of maintenance or where maintenance was performed;
   h. If the BMPs are in working order and if maintenance is required (including when scheduled and completed);
   i. Locations that are in need of additional controls;
   j. Location and dates when major construction activities begin, occur or cease;
   k. Signature of qualified signatory official, in accordance with Part II.B.9.

   Additional information may be added to the inspection report at the permittee's discretion.

3) Inspection Records. Each report shall be retained as part of the SWPPP for at least three (3) years from the date the site is finally stabilized. Each report shall be signed and have a certification statement in accordance with Parts II.B.9 and 10 of this permit.

4) Winter Conditions. Inspections will not be required at construction sites nor the construction support activities located off site where snow cover exists over the entire site for an extended period, and melting conditions do not exist. If there is any runoff from the site at any time during snow cover, melting conditions are considered to be existent at the site and this inspection waiver does not apply. Regular inspections, as required by this permit, are required at all other times as specified in this permit. If winter conditions prevent compliance with the permit, documentation of the beginning and ending date of winter conditions shall be included in the SWPPP.

5) Adverse Weather Conditions. Adverse conditions are those that are dangerous or create inaccessibility for personnel, such as local flooding, high winds, or electrical storms, or situations that otherwise make inspections

impractical, such as extended frozen conditions. When adverse weather conditions prevent the inspection of the site, an inspection shall be completed as soon as is safe and feasible. If adverse weather conditions prevent compliance with the permit, documentation of the beginning and ending date of adverse weather conditions shall be included in the SWPPP.

O. *Maintenance*. A description of procedures to maintain vegetation, erosion and sediment control measures and other protective measures in good, effective operating condition shall be outlined in the plan. Any repairs that are needed based on an inspection shall be completed, when practicable, before the next storm event, but not to exceed a period of three (3) business days of discovery, or as otherwise directed by state or local officials. However, if conditions do not permit large equipment to be used, a longer time frame is allowed if the condition is thoroughly documented on the inspection form. Maintenance for manufactured controls shall be done at a minimum of the manufacturer's specifications. Maintenance for non-manufactured controls, i.e. check dams and sediment traps, shall be done when 50% of treatment capacity remains.

P. *Employee Training*. The permittee/operator is responsible for training personnel, who are responsible for implementing activities identified in the SWPPP, on the components and requirements of the SWPPP and the requirements of the general permit. This includes contractors and subcontractors. Training shall be given by a knowledgeable and qualified trainer. The SWPPP shall identify periodic dates for such training for all personnel and records of training shall be maintained with the SWPPP. Training records that are maintained electronically (i.e. database, etc.) do not need to be maintained with the SWPPP, but shall be accessible upon request. Formal training classes given by Universities or other third-party organizations are not required but recommended for qualified trainers; the permittee is responsible for the content of the training being adequate for personnel to implement the requirements of the permit.

**5. Plan Certification.** The SWPPP Certification shall be signed by either the operator or the cognizant official identified on the NOI. All documents required by the permit and other information requested by the Director shall be signed by operator or by a duly authorized representative of the operator (Please see Part II.B.10 below for certification).

## SECTION B: STANDARD PERMIT CONDITIONS

1. **Retention of Records.**

   A. The operator shall retain records of all Stormwater Pollution Prevention Plans, all inspection reports required by this permit, and records of all data used to complete the NOI to be covered by this permit for a period of at least three (3) years from the date the NOT letter is signed by DEQ. This period may be extended by request of the Director at any time.

   B. The operator shall retain a signed copy of the SWPPP and inspection reports required by this permit at the construction site from the date of project initiation to the date of final stabilization.

2. **Duty to Comply.** The operator shall comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the federal Clean Water Act and the Arkansas Water and Air Pollution Control Act and is grounds for: enforcement action; permit termination, revocation and re-issuance, or modification; or denial of a permit renewal application.

3. **Penalties for Violations of Permit Conditions.** The Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.) provides that any person who violates any provisions of a permit issued under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year, or a criminal penalty of not more than twenty five thousand dollars ($25,000) or by both such fine and imprisonment for each day of such violation. Any person who violates any provision of a permit issued under the Act may also be subject to civil penalty in such amount as the court shall find appropriate, not to exceed ten thousand dollars ($10,000) for each day of such violation. The fact that any such violation may constitute a misdemeanor shall not be a bar to the maintenance of such civil action. Any person that purposely, knowingly, or recklessly causes pollution of the water of the state in a manner not otherwise permitted by law and thereby places another person in imminent danger of death or serious bodily injury shall be guilty of a felony and shall be subject to imprisonment, a fine not more than two hundred fifty thousand dollars ($250,000), or both such fine and imprisonment.

4. **Continuance of the General Permit.** Permittees wishing to continue coverage under this general permit shall submit a Renewal NOI (see Part I.B.4 for where to submit documentation) up to 180 days prior to the expiration date, but no later than thirty (30) days prior to the expiration date. No additional fee is required to be submitted along with the Renewal NOI.

   An expired general permit continues in force and effect until a new general permit is issued. If this permit is not re-issued or replaced prior to the expiration date, it will be administratively continued in accordance with Ark. Code Ann. § 8-4-203(m) and remain in force and effect. If a permittee was granted permit coverage prior to the expiration date, the permittee will remain covered by the continued permit until the earliest of:

   A. The effective date of the re-issuance or replacement of this permit and a timely submittal of a renewal NOI by the operator; or

   B. The operator's submittal and DEQ approval of a NOT; or

   C. Issuance and effectiveness of an individual permit for the project's discharges and completion of item B of this section (see Part I.B.24); or

   D. A formal permit decision by DEQ to not re-issue this general permit, at which time operators must seek coverage under an alternative permit (see Part I.B.24).

   Small site operators are responsible for ensuring that the site is in compliance with any changes or updates of this general permit by reviewing DEQ's website at:

https://www.adeq.state.ar.us/water/permits/npdes/stormwater/

5. **Need to Halt or Reduce Activity Not a Defense.** It shall not be a defense for an operator in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

6. **Duty to Mitigate.** The operator shall take all reasonable steps to minimize or prevent any discharge or sludge use or disposal in violation of this permit which has reasonable likelihood of adversely affecting human health or the environment.

7. **Duty to Provide Information.** The operator shall furnish to the Director, an authorized representative of the Director, the EPA, a State or local agency reviewing sediment and erosion plans, grading plans, or stormwater management plans, or in the case of a stormwater discharge associated with industrial activity which discharges through a MS4 with an NPDES permit, to the municipal operator of the system, within a reasonable time, any information which is requested to determine compliance with this permit.

8. **Other Information.** When the operator becomes aware that he or she failed to submit any relevant facts or submitted incorrect information in the NOI or in any other report to the Director, he or she shall promptly submit such facts or information.

9. **Signatory Requirements.** All NOIs, reports, or information submitted to the Director shall be signed and certified by the operator.

   A. All NOI shall be signed as follows:

      1) For a corporation: by a responsible corporate officer. For purposes of this section, a responsible corporate officer means:

         a. A president, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or

         b. The manager of one or more manufacturing, production, or operating facilities, provided, the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to ensure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

      2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively;

      3) For a municipality, State, Federal or other public agency: by either a principal executive or ranking elected official. For purposes of this section, a principal executive officer of a Federal agency includes:

         a. The chief executive officer of the agency; or

         b. A senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency.

   B. All reports required by the permit and other information requested by the Director shall be signed by a person described

above or by a duly authorized representative of that person. A person is a duly authorized representative only if:

1) The authorization is made in writing by a person described above and submitted to the Director;

2) The authorization specifies either an individual or a person having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility, or position of equivalent responsibility for environmental matters for the company (A duly authorized representative may thus be either a named individual or any individual occupying a named position); and

3) Changes to authorization. If an authorization under this Part is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the above requirements shall be submitted to the Director prior to or together with any reports, information, or applications to be signed by an authorized representative.

**10. Certification.** Any person signing a document under this section shall make the following certification:

"I certify under penalty of law that this document and all attachments such as Inspection Form were prepared under my direction or supervision in accordance with a system designed to ensure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Note: For this permit only, “this document” refers to the Stormwater Pollution Prevention Plan, “attachments” refers to the site map and inspection forms, and “system” is referencing the project site.

**11. Penalties for Falsification of Reports.** The Arkansas Water and Air Pollution Control Act provides that any person who knowingly makes any false statement, representation, or certification in any application, record, report, plan or other document filed or required to be maintained under this permit shall be subject to civil penalties specified in Part II.B.3 of this permit and/or criminal penalties under the authority of the Arkansas Water and Air Pollution Control Act (Ark. Code Ann. 8-4-101 et seq.).

**12. Penalties for Tampering.** The Arkansas Water and Air Pollution Control act provides that any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained under the Act shall be guilty of a misdemeanor and upon conviction thereof shall be subject to imprisonment for not more than one (1) year or a fine of not more than twenty five thousand dollars ($25,000) or by both such fine and imprisonment.

**13. Oil and Hazardous Substance Liability.** Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the operator from any responsibilities, liabilities, or penalties to which the operator is or may be subject under Section 311 of the Clean Water Act or Section 106 of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA).

**14. Property Rights.** The issuance of this permit does not convey any property rights of any sort or any exclusive privileges, nor does it authorize any injury to private property, any invasion of personal rights, or any infringement of Federal, State, or local laws or regulations.

**15. Severability.** The provisions of this permit are severable. If any provisions of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provisions to other circumstances and the remainder of this permit shall not be affected thereby.

**16. Transfers.** This permit is not transferable to any person except after notice to the Director. A transfer form shall be submitted to DEQ as required by this permit.

**17. Proper Operation and Maintenance.** The operator shall at all times:

A. Properly operate and maintain all systems of treatment and control (and related appurtenances) which are installed or used by the operator to achieve compliance with the conditions of this permit. This provision requires the operation of backup or auxiliary facilities or similar systems which are installed by an operator only when the operation is necessary to achieve compliance with the conditions of the permit.
B. Provide an adequate operating staff which is duly qualified to carry out operation, inspection, maintenance, and testing functions required to ensure compliance with the conditions of this permit.

**18. Inspection and Entry.** The operator shall allow the Director, the EPA, or an authorized representative, or, in the case of a construction site which discharges to a municipal separate storm sewer, an authorized representative of the municipal operator of the separate sewer system receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:

A. Enter upon the operator's premises where a regulated facility or activity is located or conducted, or where records shall be kept under the conditions of this permit;
B. Have access to and copy, at reasonable times, any records that shall be kept under the conditions of this permit;
C. Inspect at reasonable times any facilities or equipment, including monitoring and control equipment and practices or operations regulated or required by the permit;
D. Sample or monitor at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by the CWA, any substances or parameters at any location on the permitted property.

**19. Permit Actions.** This permit may be modified, revoked and reissued, or terminated for any cause including, but not limited to, the following;

A. Violation of any terms or conditions of this permit;
B. Obtaining this permit by misrepresentation or failure to fully disclose all relevant facts;
C. A change in any conditions that requires either a temporary or permanent reduction or elimination of the authorized discharge;
D. A determination that the permitted activity endangers human health or the environment and can only be regulated to acceptable levels by permit modification or termination; or
E. Failure of the operator to comply with the provisions of DEQ Rule 9 (Fee Rule). Failure to promptly remit all required fees shall be grounds for the Director to initiate action to terminate this permit under the provisions of 40 C.F.R. §122.64 and §124.5(d), as adopted by reference in DEQ Rule 6, and the provisions of DEQ Rule 8.

**20. Re-Opener Clause.**

A. If there is evidence indicating potential or realized impacts on water quality due to any stormwater discharge associated with industrial activity covered by this permit, the operator of such discharge may be required to obtain an individual permit or an alternative general permit in accordance with Part I.B.24 of this permit, or the permit may be modified to include different limitations and/or requirements.

B. Permit modification or revocation will be conducted in accordance with the provisions of 40 C.F.R. §122.62, §122.63, §122.64 and §124.5, as adopted by reference in DEQ Rule 6.

**21. Local Requirements.** All dischargers shall comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding any discharges of stormwater to storm drain systems or other water sources under their jurisdiction, including applicable requirements in municipal stormwater management programs developed to

comply with the DEQ permits. Dischargers shall comply with local stormwater management requirements, policies, or guidelines including erosion and sediment control.

22. **Applicable Federal, State, or local Requirements.** Permittees are responsible for compliance with all applicable terms and conditions of this permit. Receipt of this permit does not relieve any operator of the responsibility to comply with any other applicable federal, state or local statute, ordinance policy, or regulation. Nothing in this permit shall be construed to preclude the institution of any legal action or enforcement actions or relieve the permittee from any responsibilities, liabilities, or penalties established pursuant to any applicable local state, or federal law or regulation.

DUMPSTER NOT SHOWN YET!!!

PARKING SPACES:
2 HANDICAP SPACES
90 CUSTOMER SPACES
92 PARKING SPACES TOTAL

VOLLEYBALL NETTING SYSTEM

STORM DRAIN BOX (TYP.) SEE SHEET C3.0

#2389 SSMH FL ELEV: 385.46 RIM ELEV=390.28

#6205 Ssmh 9.10 INV RIM ELEV=397.59

#2388 SSMH FL ELEV: 390.36 RIM ELEV=394.62

25' SETBACK - UTILITY - DRAINAGE EASEMENT

70' DETENTION AREA ESMT.

24'

5' WIDE STAIR WITH RAILING (7 STEPS)

BUILDING FINISH FLOOR = 400
21,225 SQUARE FEET

ARDOT STANDARD TYPE A CURB

6.5' WIDE WALK

SIGN TO DESIGNATE SPOT AS HANDICAP ACCESSIBLE (2 TOTAL)

6.5' WIDE WALK

HENRY AVENUE

SIDEWALK

CURB 6" TURN DOWN

CURB & ASPH. FLUSH

CURB STOP (TYP.) (4 TOTAL)

CURB & ASPH. FLUSH

CURB 6" TURN DOWN

7' WIDE WALK

PARKING SPACE (TYP.)
9'

18'

24'

24'

24'

EXISTING PATH

8IKE/WALK PATH

ELECTRIC BOX

#2351 Ssmh rim 5.88 Inv RIM ELEV=388.79

#2351 Ssmh rim 4.88 Inv RIM ELEV=389.12

REMOVE 5' OF PATH TO INSTALL STORM DRAIN THEN REBUILD AND CONSTRUCT REST OF PATH TO INTERSECTION.

#1571 7.02 Inv curb inlet rim RIM ELEV=408.34

#1569 Curb inlet rim 7.5 Inv RIM ELEV=408.61

CHRISTY LANE

INSTALL 48 LF OF MODIFIED CURB

LEGEND:

PROPOSED CONCRETE

PROPOSED ASPHALT

EXISTING CONCRETE

NOTES:

1. SITE PAVEMENT MARKINGS SHALL BE 4" WIDE WHITE PAINT (PER ARDOT STANDARD SPECIFICATION SECTION 718)

20' 10' 0 20'

| BY | REVISION | DATE |
|---|---|---|
| | | |


GNE Designing our client's success
GarNat Engineering, LLC
P.O. Box 116 Benton, AR 72018
3825 Mt Carmel Rd Bryant, AR 72022
garnatengineering@gmail.com
Ph (501) 408-4650


# A NEW ELITE VOLLEYBALL ACADEMY GYM FOR JOHN ECKART VERNIA OFFICE PARK BRYANT, ARKANSAS

STATE OF ARKANSAS
Vernon J. Williams
REGISTERED PROFESSIONAL ENGINEER
NO. 9551
VERNON J. WILLIAMS

03-13-2023

CONTENTS:

SITE PLAN

PROJECT NO: 22140

DATE: MARCH 13, 2023

SHEET NO: C1.0

GNE

3825 Mt Carmel Rd.
Bryant, AR 72022

**GarNat Engineering, LLC**

P.O. Box 116
Benton, AR 72018

March 8, 2023

Mr. Truett Smith
Bryant Planning Coordinator/Planning Commission Secretary
210 SW 3rd Street
Bryant, AR 72022

Re: Large Scale Development Commercial Building – A New Elite Voleyball

Dear Mr. Smith:

Please accept this letter and following list of enclosures to serve as my application for approval of the referenced large scale development. It is my desire that this matter be included on the agenda for your May 2023 City of Bryant Planning Commission Meeting.


List of Enclosures


- 2 Full Set Plans
- Affidavit
- 8 copies of Site Plan
- Drainage Study
- Bryant Large Development Checklist
- ADA/ABA Form

If you have questions or need any additional information, please do not hesitate to contact me.

Sincerely,
GarNat Engineering, LLC

Vernon J. Williams, P.E., President







BASIS OF BEARING
GRID NORTH
AR SOUTH ZONE
NAD 83
CF 0.9999542
CONV. -0°17'27"
(GROUD DISTANCES)

SOURCE OF TITLE: 2022-28534, 2023-00543

OWNER OF RECORD: KALRU 786 INC
14301 ARCH STREET
LR, AR.

NAME OF SUBDIVIDER: KALRU 786 INC
14301 ARCH STREET
LR, AR.

CURRENT ZONING: CI

CERTIFICATE OF OWNER

WE, THE UNDERSIGNED, OWNERS OF THE REAL ESTATE SHOWN AND DESCRIBED HEREIN DO HEREBY CERTIFY THAT WE HAVE LAID OFF, PLATTED AND SUBDIVIDED, AND DO HEREBY LAY OFF, PLAT AND SUBDIVIDE SAID REAL ESTATE IN ACCORDANCE WITH THE PLAT.

_____ _____
DATE OF EXECUTION KALRU 786 INC

CERTIFICATE OF SURVEYING ACCURACY:

I, KERRY D. LANE, HEREBY CERTIFY THAT THIS PROPOSED PLAT CORRECTLY PRESENTS A SURVEY COMPLETED BY ME, OR UNDER MY SUPERVISION ON MARCH 16, 2023; THAT THE BOUNDARY LINE SHOWN HEREON CORRESPOND WITH THE DESCRIPTION IN THE DEEDS CITED IN THE ABOVE SOURCE OF TITLE; AND THAT ALL MONUMENTS WHICH WERE FOUND OR PLACED ON THE PROPERTY ARE CORRECTLY DESCRIBED AND LOCATED.

BY: _____, ARKANSAS PROFESSIONAL SURVEYOR NO. 1141,

DATE 3-29-2023

CERTIFICATE OF FINAL PLAT APPROVAL:

PURSUANT TO THE CITY OF BRYANT SUBDIVISION RULES AND REGULATIONS, THIS DOCUMENT WAS GIVEN APPROVAL BY THE BRYANT PLANNING COMMISSION AT A METTING HELD_____ 20_____. ALL OF THE DOCUMENT IS HEREBY ACCEPTED, AND THIS CERTIFICATE EXECUTED UNDER THE AUTHORITY OF SAID RULES AND REGULATIONS.

DATE OF EXECUTION BRYANT PLANNING COMMISSION

_____ _____

CERTIFICATE OF RECORDING

THIS DOCUMENT, NUMBER_____, FILED FOR RECORD_____, 20____

IN PLAT BOOK_____ PAGE_____

CLERK

_____


SURVEY DESCRIPTION.
THAT PORTION OF THE NORTHEAST QUARTER OF THE SOUTHEAST QUARTER, SECTION 20, T-1-S, R-14-W, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS; COMMENCING AT THE NORTHEAST CORNER OF SAID NE1/4 OF SE1/4, RUN THENCE SOUTH 02°34'54" WEST, A DISTANCE OF 175.99 FEET TO THE POINT OF BEGINNING; THENCE SOUTH 02°34'54" WEST, ALONG THE EAST LINE THEREOF A DISTANCE OF 210.82 FEET; THENCE NORTH 88°32'52" WEST, A DISTANCE OF 417.42 FEET; THENCE NORTH 02°34' 55" EAST, A DISTANCE OF 210.82 FEET; THENCE SOUTH 88°32'52" EAST, A DISTANCE OF 417.42 FEET TO THE POINT OF BEGINNING, CONTAINING 2.02 ACRES, MORE OR LESS.

UNLESS SPECIFICALLY STATED OR SHOWN, THIS BOUNDARY SURVEY IS MADE SUBJECT TO AND DOES NOT DELINEATE: BUILDING SETBACK LINES, ZONING REGULATIONS, RESTRICTIONS, OR OTHER ITEMS WHICH MAY AFFECT DEVELOPMENT. NO STATEMENT IS MADE CONCERNING SUBSURFACE CONDITIONS, OR THE EXISTANCE OF UNDERGROUND OR OVERHEAD CONTAINERS OR FACILITIES, UNLESS SPECIFICALLY SHOWN, WHICH MAY AFFECT THE USE OR DEVELOPMENT OF THE TRACT. TRACT MAY BE SUBJECT TO EASEMENTS, RESTRICTIVE COVENANTS, SUBDIVISION RESTRICTIONS, AND PLANNING AND ZONING REGULATIONS OF RECORD, IF ANY, AND IS SUBJECT TO SUCH FACTS WHICH A CURRENT TITLE SEARCH MAY DISCLOSE. I HEREBY CERTIFY THAT THE ABOVE PLAT REPRESENTS A BOUNDARY SURVEY PERFORMED BY ME OR UNDER MY SUPERVISION ON THIS DAY.

DATE: 3-29-2023

GRAPHIC SCALE 1"=60'

0 60 120




| DRAWING NO. | REAL ESTATE SERVICES OF SALINE COUNTY,INC. | |
|---|---|---|
| 021-23 | 501-315-8866 lanesurveying@gmail.com | |
| REVISIONS BY | FOR USE AND BENEFIT OF: | DRAWN BY |
| DATE | KALRU 786 INC | CHECKED BY |
| | | APPROVED BY |
| | 1200 FERGUSON DR., SUITE 5, BENTON, AR., 72015 | |
| | STATE FILING CODE: 500-015-14W-0-20-210-62-1141 | |




LEGEND
- SET #5 BAR/CAP
- EXISTING MON.
- CALC. POINT
- FENCE
- OH ELECTRIC
- SEWER
- WATER LINE